

## VPDES PERMIT FACT SHEET

This document gives pertinent information concerning the reissuance of the VPDES permit listed below. This permit is being processed as a Major Municipal permit. The effluent limitations contained in this permit will maintain the Water Quality Standards of 9 VAC 25-260 et seq. The discharges result from the operation of a sewage treatment facility and from the operation of a paper mill (the Bear Island Paper Company). This permit action includes revisions to some effluent limitations, the frequency of effluent monitoring for some parameters, and the special conditions.

1. Facility Name and Address:

Hanover County  
Doswell Wastewater Treatment Plant  
Department of Public Utilities  
P. O. Box 470  
Hanover, Virginia 23069-0470

Location: 15468 Theme Park Way in Doswell  
Ashland topo (149C) – see **Attachment 1**.

2. SIC Codes: 4952 for the Doswell Wastewater Treatment Plant and 2621 for the Bear Island Paper Company.

3. Permit No. VA0029521  
Expiration Date: May 18, 2008

4. Owner Contact: David Van Gelder  
Chief of Operations and Maintenance  
Telephone Number: 804/365-6235  
Facsimile Number: 804/365-6245  
E-mail: dfvangelder@co.hanover.va.us

5. Application Complete Date: April 4, 2008

Permit Drafted By: Ray Jenkins, Piedmont Regional Office  
Date: August 20, 2008

Reviewed By: Gina Kelly  
Curt Linderman  
Kyle Winter

Date: September 2, 2008  
November 18, 2008  
January 8, 2009

6. Receiving Stream: Name: North Anna River  
Basin: York River  
Subbasin: NA  
Section: 3  
Class: III  
Special Standards: None

River Mile: 8-NAR003.55

1-Day, 10-Year Low Flow:	42 cfs (27 MGD)
7-Day, 10-Year Low Flow:	45 cfs (29 MGD)
30-Day, 10- Year Low Flow	49 cfs (32 MGD)
30-Day, 5-Year Low Flow:	51 cfs (33 MGD)
Harmonic Mean Flow:	126 cfs (81 MGD)

7. Operator License Requirements: Class II licensed operators are required at Doswell and at Bear Island. A Class I operator is required at Bear Island following mill expansion.
- 8 Reliability Class: Class I for the Doswell Wastewater Treatment Plant.
9. Permit Characterization: (Check as many as appropriate)
- |   |  |
|---|--|
| <input type="checkbox"/> Issuance                         | <input checked="" type="checkbox"/> Existing Discharge                 |
| <input checked="" type="checkbox"/> Reissuance            | <input checked="" type="checkbox"/> Proposed Discharge                 |
| <input type="checkbox"/> Revoke & Reissue                 | <input checked="" type="checkbox"/> Effluent Limited                   |
| <input type="checkbox"/> Owner Modification               | <input checked="" type="checkbox"/> Water Quality Limited              |
| <input type="checkbox"/> Board Modification               | <input type="checkbox"/> WET Limit                                     |
| <input type="checkbox"/> Change of Ownership/Name         | <input type="checkbox"/> Interim Limits in Permit                      |
| Effective Date:   | <input type="checkbox"/> Interim Limits in Other Document (attached)   |
| <input checked="" type="checkbox"/> Municipal             | <input type="checkbox"/> Compliance Schedule Required                  |
| SIC Code(s): 4952   | <input type="checkbox"/> Site Specific WQ Criteria                     |
| <input checked="" type="checkbox"/> Industrial            | <input type="checkbox"/> Variance to WQ Standards                      |
| SIC Code(s): 2621   | <input type="checkbox"/> Water Effects Ratio                           |
| <input checked="" type="checkbox"/> POTW                  | <input type="checkbox"/> Discharge to 303(d) Listed Segment            |
| <input type="checkbox"/> PVOTW                            | <input checked="" type="checkbox"/> Toxics Management Program Required |
| <input checked="" type="checkbox"/> Private (Bear Island) | <input type="checkbox"/> Toxics Reduction Evaluation                   |
| <input type="checkbox"/> Federal                          | <input checked="" type="checkbox"/> Pretreatment Program Required      |
| <input type="checkbox"/> State                            | <input type="checkbox"/> Storm Water Management Plan                   |
| <input type="checkbox"/> Publicly-Owned Industrial        | <input type="checkbox"/> Possible Interstate Effect                    |
10. Water Flow and Treatment Schematics: See **Attachments 2 and 12**. Attachment 2 shows the current condition. Attachment 12 reflects the proposed mill expansion at Bear Island.
11. Sewage Sludge Use or Disposal: Sewage sludge is aerobically digested, dewatered by belt press, and disposed at sanitary landfill. The Bear Island sludge is incinerated on the Bear Island site in the bark burner.

12. **Material Storage:** At the Doswell treatment plant, magnesium hydroxide, which is used for pH adjustment, is stored in a 4,000 gallon above ground tank. No containment is provided; topography however, would confine any spill to the area around the tank. Polymer for sludge dewatering is stored in the belt press building.

At the Bear Island treatment plant, aqua ammonia is stored in a 24,000 gallon above ground tank that is located within a concrete dike. Phosphoric acid, polymer, and defoamer are stored in tanks in the operations building, which is designed to provide containment equal to the volume of the largest tank. Also, floor drains in the building discharge to the emergency holding basin. Additionally, diesel fuel (10,000 gallons) and gasoline (900 gallons) tanks are located in a concrete containment area.

13. **Ambient Water Quality Information:** See **Attachments 3 and 4**. **Attachment 3** presents ambient data on the North Anna River at the Route 30 bridge (river mile 8-NAR005.42; 1.87 miles above the discharge point). The temperature, pH, and hardness data are used to develop the waste load allocations in Attachment 7 ("MSTRANTI" calculations). **Attachment 4** develops the statistical flows on which effluent limitations are based (memorandum dated April 7, 2008 from Jennifer Palmore).

The North Anna River at the discharge point was assessed during the 2006 305(b) / 303(d) cycle as fully supporting of all its designated uses (that is, assessed as Category 1).

14. **Antidegradation Review and Comments:**

The State Water Control Board's Water Quality Standards include an antidegradation policy (9 VAC 25-260-30). All state surface waters are provided one of three levels of antidegradation protection. For Tier 1 existing uses of the water body and the water quality to protect those uses must be maintained. Tier 2 water bodies have water quality that is better than the water quality standards. Significant lowering of the water quality of Tier 2 waters is not allowed without an evaluation of the economic and social impacts. Tier 3 water bodies are exceptional waters and are so designated by regulatory amendment. The antidegradation policy prohibits new or expanded discharges into exceptional waters.

The receiving stream is a Tier 1 waterbody. The stream was considered Tier 1 in previous effluent limitation evaluations. As those evaluations established the basis for the limitations (or lack thereof) in the permit, the stream continues to be classified as Tier 1.

15. **Site Inspection:** Date: September 21, 2007 Performed by: Michael Dare  
See **Attachment 5**

16. **Effluent Screening and Limitation Development:**

See **Attachments 6, 7, and 14** and Tables I through IV.

Attachment 6 presents effluent data – Outfalls 001, 101, and 102.

Attachments 7 (existing facility) and 14 (with expansion at Bear Island) present mixing zone calculations (MIX.exe), the calculation of wasteload allocations (MSTRANTI), reasonable potential analyses for pollutants detected in the effluent (STATS), and human health evaluations for Outfall 001.

17. Antibacksliding: All limitations in the proposed permit (2009 reissuance) are the same or more stringent than the limitations in the 2006 permit. The control equations in the proposed permit, however, are applied to larger statistical stream low flows than in the 2006 permit, resulting in the calculation of increased BOD<sub>5</sub> loadings to the receiving stream. As the underlying concentrations have not increased, the increased BOD<sub>5</sub> loadings do not represent backsliding. The statistical stream low flows increased because those flows were reestablished based on actual measurements at the stream gages in the Doswell area versus deriving the flows based on guaranteed release rates from Lake Anna and subtracting intervening withdrawals (see “Outfall 001 – Supplement to Table 1 for additional information).
18. Compliance Schedules: There are no compliance schedules in the proposed permit.
19. Special Conditions:

Part I.B of the 2006 permit (see **NOTE** at end of paragraph) required that Outfall 001 be sampled and analyzed for the water quality criteria parameters and the results reported with the permit renewal application. Monitoring for permit renewal purposes is no longer being required by special condition in the permit; it is now being included in the reissuance reminder letter advising the permittee to include such monitoring in the permit renewal application. The requirement to submit such data (Part I.B in the 2006 permit) has therefore, been removed from the permit. However, as the draft permit addresses an expansion of the Bear Island paper mill, it is necessary to include a requirement for water quality criteria monitoring on the expanded discharge if the expansion occurs during the term of the permit. Such a requirement is included in the draft permit as Part I.C. **[NOTE:** The permit that was reissued in 2003 was modified in October 2006 to remove cyanide limitations on Outfall 001 (pre and post expansion) and a compliance schedule to meet the cyanide limitations that was included as Part I.D.1 in the permit that was reissued in 2003. When the cyanide compliance schedule was removed, a second compliance schedule requiring the construction of a river gaging station on the North Anna River above the Little River was moved from I.D.2 to I.D.1. A formatting change to the cover page of the permit was also included in the 2006 modification. Therefore, throughout this fact sheet, the existing permit is referred to as the 2006 permit.]

The following special conditions were in Part I.C of the 2006 permit. They are in Part I.B of the proposed permit (2009 reissuance).

- a. Special Condition 1 – Whole Effluent Toxicity (WET) Monitoring Program



VPDES Permit Regulation, 9 VAC 25-31-210 and 220 I, requires monitoring in the permit to provide for and assure compliance with all applicable requirements of the State Water Control Law and the Clean Water Act. The proposed WET monitoring program is discussed in **Attachment 8**. Attachment 8 contains a summary of toxicity tests done during the term of the 2006 permit and spreadsheets which calculate the WET endpoints for the existing effluent flow and for the proposed expansion flow.

The required testing is the same as in the 2006 permit. The acute endpoints have been revised to a NOAEC = 100% (versus endpoints in the 2006 permit of a  $LC_{50} \geq 100\%$ ). The chronic endpoints are less restrictive than in the 2006 permit due to the use of higher stream flows in the determination of the endpoints. The verbiage of the program has also been revised. Whereas the 2006 language required a retest if unacceptable results were obtained, the proposed permit indicates that all test results will be evaluated for reasonable potential to determine the need for a WET limitation.

b. Special Condition 2 – Notification Levels

This special condition is required by VPDES Permit Regulation, 9 VAC 25-31-200 A for all manufacturing, commercial, mining, and silvicultural dischargers.

This special condition is the same as in the 2006 permit.

c. Special Condition 3 – Contractual Agreement

This special condition addresses the need for an appropriate contractual agreement between Hanover County and Bear Island as the County is responsible for permit compliance.

This special condition is the same as in the 2006 permit.

d. Special Condition 4 – River Flow Measurement

This special condition establishes the stream flow measurement requirements for use in the control equations in Part I.A of the permit.

This special condition has been revised to reflect the construction of the gaging station on the North Anna River above the Little River. The use of the gaging station at Route 30 is now included as a back-up gaging location. The 2006 permit did not assume that river flows would be continuously measured and recorded (at least not until the Bear Island mill was expanded). However, both gaging stations, which are owned and operated by DEQ, now continuously report data to the U. S. Geological Survey. The river flow measurement requirements in Part I.A of the permit are therefore, indicated as CONTINUOUS RECORDED. In the event that continuous data are not recorded however, this special condition establishes the required frequency of manually recording flows.

The next to last paragraph of the special condition is new to acknowledge the maximum measurement capacity of the gage above the Little River.

A reporting requirement has also been added. River flow has always been included in the reports required by the permit, but a reporting requirement was not explicitly stated in the permit.

e. Special Condition 5 – Dissolved Oxygen Monitoring

This special condition establishes the requirements of a river monitoring program for dissolved oxygen and temperature. Such monitoring provides actual information on the accuracy of the BOD control equations in the permit, which are based on limiting the dissolved oxygen sag to 0.2 mg/L.

Regarding the conditions under which this monitoring is not required, previous language in the permit waived the monitoring if the river was at flood stage, which was defined to be 1840 cfs. When the permit was reissued in 2003, this flow was revised to 750 cfs. Hanover County asked for that revision because the river can be dangerous at flows at and above 750 cfs. Dissolved oxygen data from January 1, 1995 through December 29, 2001 were evaluated. During that time there were nine occasions on which the flow was equal to or greater than 750 cfs and less than 1840 cfs. The average dissolved oxygen depletion on those nine occasions was 0.14 mg/L. The flow was therefore, revised because no significant impact was indicated at flows above 750 cfs and because of the concern about the safety of County employees.

This special condition also establishes that dissolved oxygen monitoring is not required when the river temperature is less than or equal to 10 °C and the ratio of effluent BOD<sub>5</sub> (in pounds per day) divided by river flow (daily mean flow in cfs) is less than or equal to 2.0. This empirical relationship was established years ago by compiling and comparing flow and loading data. The relationship must be reestablished after the expansion of the Bear Island mill.

This special condition has been revised to cite both gaging stations in regard to the high flow at which the dissolved oxygen monitoring is no longer required, “Q<sub>PLAN</sub>” was deleted in the third paragraph, reference to the Regional Director was deleted in the fourth paragraph, and the reopener included as special condition 9 in the 2006 permit was moved to the end of this special condition. A low flow exclusion was also added to the second paragraph in response to a request from Hanover County. At flows below 30 cfs (as measured at the gage on the North Anna above the Little River) it is often necessary to portage for segments of the run. It is therefore, proposed that the run not be required at flows less than 30 cfs.

**[Special Condition 6 – TKN vs. Ammonia Limitation – in the 2006 permit was deleted. This condition addressed substitution of an ammonia limitation for the TKN limitation if approved by the DEQ staff. This condition has been in the permit since at least 1988 and the permittee has not pursued such a substitution. If such a substitution is determined to be desirable, the permittee may submit an appropriate application and the permit can be reopened as necessary.]**

f. Special Condition 6 – Pretreatment

This special condition establishes the pretreatment program for industrial users. Special Condition 7 in the 2006 permit also addresses pretreatment. This special condition is required by VPDES Permit Regulation 9 VAC 25-31-730 through 900,

and 40 CFR Part 403 that require certain existing and new sources of pollution to meet specified regulations.

In the first sentence of the preamble, “or modification” was deleted for clarity. The second sentence in 6.e.(10) – “This is due no later than March 31 of each year” – was deleted because it seems to conflict with the requirement to submit the annual report by January 31 of each year.. The newspaper copies regarding noncompliance are due with the annual report on January 31.

Pretreatment is addressed in special condition 7 in the 2006 permit.

g. Special Condition 7 – Changes in Design Flow

This special condition is carried-over from previous permits and is simply a reminder that if the projected flows associated with the mill expansion change from the projections contained in the permit, the permit may have to be reopened and modified.

This special condition is the same as in the 2006 permit except that it is special condition 8 in the 2006 permit.

**[Special Condition 9 – Reopener for Dissolved Oxygen – in the 2006 permit was moved to Special Condition 5 in the proposed permit. See 19.e above.]**

h. Special Condition 8 –TKN Degradability Study

This special condition requires that the permittee repeat a TKN degradability study following the Bear Island mill expansion. The TKN limitations in the permit are based on an established percentage of the TKN concentration ultimately exerting an oxygen demand (see Supplement to Table I). That percentage will have to be reestablished after the mill expansion.

This special condition has been revised by adding language that specifically requires that the study plan include an implementation schedule and that the approved study plan and schedule will be enforceable parts of the permit

i. Special Condition 9 – Macroinvertebrate Survey

This special condition requires a yearly macroinvertebrate survey in the North Anna and Pamunkey Rivers if there are major changes (e.g., expansion) in the Bear Island mill. Past surveys have shown only a minimal effect on the receiving stream in the form of organic enrichment on the benthic community structure in the North Anna and Pamunkey Rivers.

This special condition is the same as in the 2006 permit except that it is special condition 11 in the 2006 permit.

j. Special Condition 10 – Dioxin and Dibenzofuran

This special condition requires dioxin and dibenzofuran monitoring if deemed necessary, contains a reopener for limitations if needed, and limits the use of purchased, chlorine bleached Kraft pulp to 10% of the total pulp use by Bear Island.

This special condition is the same as in the 2006 permit except that it is special condition 12 in the 2006 permit.

k. Special Condition 11 – Plans and Specifications for Effluent Filter

When the Bear Island mill is expanded, the effluent from the Doswell sewage treatment facility will be filtered and used as a water source by Bear Island. This special condition is a reminder that plans and specifications for those facilities must be approved by the DEQ prior to starting construction.

This special condition is the same as in the 2006 permit except that the reference to the Virginia Department of Health has been deleted as plan approval now rests with the DEQ and it is special condition 13 in the 2006 permit.

l. Special Condition 12 – Plans and Specifications for Effluent Holding Pond

The Bear Island mill expansion will require that the effluent holding pond be expanded to 60 million gallons. This special condition requires that plans for that pond be submitted and approved prior to starting construction.

This special condition is the same as in the 2006 permit except that it is special condition 14 in the 2006 permit.

m. Special Condition 13 – EPA Application Form 2C

This special condition requires appropriate characterization of the effluent following the Bear Island mill expansion.

This special condition is the same as in the 2006 permit except that it is special condition 15 in the 2006 permit.

n. Special Condition 14 – Licensed Wastewater Operators

This special condition requires appropriately licensed wastewater works operators at the Doswell and Bear Island treatment plants. Licensed operators are required by VPDES Permit Regulation 9 VAC 25-31-200 C and the Code of Virginia § 54.1-2300 et seq., Rules and Regulations for Waterworks and Wastewater Works Operators (18 VAC 160-20-10 et seq.).

This special condition is the same as in the 2006 permit except that it is special condition 16 in the 2006 permit.

o. Special Condition 15 – 95% Design Capacity

This special condition requires that the permittee develop plans for maintaining compliance if the influent flows to the Doswell Wastewater Treatment Facility reach 95% of design capacity for any three consecutive month period. This is required by VPDES Permit Regulation 9 VAC 25-31-200 B 2 for all publicly and privately owned treatment works.

This special condition is the same as in the 2006 permit except that it is special condition 17 in the 2006 permit.

p. Special Condition 16 – Reliability Class

This special condition establishes that the Doswell Wastewater Treatment Facility meet Reliability Class I requirements. This is required by the Sewage Collection and Treatment Regulations, 9 VAC 25-60-20 and 40, for all municipal facilities.

This special condition is the same as in the 2006 permit except that it is special condition 18 in the 2006 permit.

q. Special Condition 17 – CTC and CTO Requirements

In the 2006 permit, special condition 19 addresses CTC and CTO requirements and Operation and Maintenance (O&M) Manual requirements.

In the proposed permit (2009 reissuance), the O&M Manual requirements have been moved to new special condition 25.

The CTC and CTO requirements have been revised in accordance with Guidance Memorandum 07-2008 and the Sewage Collection and Treatment Regulations are cited in the proposed permit versus the Sewerage Regulations. These requirements are addressed by the Code of Virginia §62.1-44.19 and the Sewage Collection and Treatment Regulations at 9 VAC 25-790.

r. Special Condition 18 – Concept Engineering Report (CER) for New or Expanded Wastewater Treatment Facilities at Bear Island

This special condition requires submittal and approval by DEQ staff of a Concept Engineering Report for construction of any new treatment facilities at Bear Island. § 62.1-44.16 of the Code of Virginia requires industrial facilities to obtain DEQ approval for proposed discharges of industrial wastewater.

This is a new special condition.

s. Special Condition 19 – Sewage Sludge Disposal

This special condition requires disposal of the sludge from the Doswell Wastewater Treatment Facility in accordance with the “VPDES Sludge Permit Application Form” submitted with the permit renewal application. VPDES Permit Regulation at 9 VAC 25-31-100 P, 220 B 2, and 420 through 720; and 40 CFR Part 503 require all treatment works treating domestic sewage to submit information on sludge use and disposal practices and to meet specified standards for sludge use and disposal.

This special condition was revised to delete reference to the Virginia Department of Health as DEQ now has responsibility for biosolids disposal and to delete reference to the "VPDES Sewage Sludge Permit Application Form". Sewage sludge disposal is addressed in special condition 20 in the 2006 permit.

t. Special Condition 20 – Sewage Sludge Reopener

This special condition is a permit reopener if any standard or disposal requirement promulgated under Section 405(d) of the Clean Water Act is more stringent than the requirements of the proposed permit. This reopener is required by the VPDES Permit Regulation at 9 VAC 25-31-220 C.

This special condition is the same as in the 2006 permit except that it is special condition 21 in the 2006 permit.

u. Special Condition 21 – Compliance Reporting

VPDES Permit Regulation 9 VAC 25-31-190 J.4 and 220.I authorize this special condition. This condition establishes quantification levels for certain parameters and establishes protocols for calculation of reported values. This condition is necessary when pollutants are monitored by the permittee and a maximum level of quantification and/or a specific analytical method is required in order to assess compliance with a permit limit or to compare effluent quality with a numeric criterion.

Ammonia and phosphorus have been removed from part a of this special condition. The language in the remaining parts of the special condition has also been revised. Note that the language in Part 21.b regarding calculation of weekly averages is not the standard DEQ language. The standard language was revised to address complete calendar weeks to be consistent with Parts I.A.1.e and I.A.4.e of the proposed permit. The standard language of this special condition instructs the permittee to compute weekly averages for only those weeks that are entirely contained within the month for which the monitoring report is being submitted. The control equations in Part I.A of the permit establish weekly average limitations for BOD<sub>5</sub> and TSS at Outfall 001. There are no monthly average limitations for those parameters at Outfall 001. Also, the control equation for BOD<sub>5</sub> establishes the allowable discharge level given any stream flow; that is, the allowable discharge does not remain constant at a level based on the 7Q10 stream flow as in other permits. Therefore, it is essential that data for all weeks of the year be included in the determination of permit compliance.

Compliance Reporting is addressed in special condition 22 in the 2006 permit.

v. Special Condition 22 – Indirect Dischargers

This special condition requires notification of changes in the quantity or quality of discharges into the sewage treatment system by someone other than the owner of the treatment works. It is required by VPDES Permit Regulation 9 VAC 25-31-200 B.1 and B.2 for POTWs and PVOTWs that receive waste from someone other than the owner of the treatment works.

This special condition is the same as in the 2006 permit except that it is special condition 23 in the 2006 permit.

w. Special Condition 23 – Reopener for WET Endpoints

This special condition was added at the permittee's request during reissuance of the permit in 2003 to acknowledge the permittee's belief that additional data may change or allow deletion of the proposed WET endpoints.

This special condition is the same as in the 2006 permit except that it is special condition 24 in the 2006 permit.

x. Special Condition 24 – Effluent Monitoring Frequencies

Permittees are granted a reduction in monitoring frequency based on a history of permit compliance. To remain eligible for the reduction, the permittee should not have violations related to the effluent limitations for which reduced frequencies were granted. If permittees fail to maintain the previous level of performance, the baseline monitoring frequencies should be reinstated for those parameters that were previously granted a monitoring frequency reduction.

Refer to Attachments 6B (Outfall 001) and 6C (Outfalls 101 and 201) of this fact sheet which present effluent data and comparisons of effluent data to limitations. Note that the baseline monitoring frequencies shown in these attachments and below are taken from the 1995 permit for all parameters except TSS on Outfall 201. TSS was initially included on Outfall 201 with the reissuance of the permit in 2003 at a frequency of 3 days per week, therefore 3/Week is the baseline. The indicated, allowable reductions in sampling frequencies are as follow:

Outfall 001: BOD<sub>5</sub> from 1/Day to 1/Week (Current frequency 1/Day.)  
TSS from 1/Day to 3/Week (Current frequency 3/Week.)  
TKN from 1/Day to 3/Week (Current frequency 3/Week.)

Outfall 101: BOD<sub>5</sub> from 1/Day to 1/Week (Current frequency 5/Week.)  
TSS from 1/Day to 3/Week (Current frequency 3/Week.)  
(There is not a limitation on TKN at Outfall 101, so a reduction cannot be computed. Current frequency 1/Month. The current frequency of 1/Month was established pursuant to a request from the permittee and the staff's best engineering judgment when the permit was reissued in 2003.)

Outfall 201 BOD<sub>5</sub> from 1/Day to 1/Week. (Current frequency 5/Week.)  
TSS from 3/Week to 1/Week. (Current frequency 3/Week.)  
(There is not a limitation on TKN at Outfall 201, so a reduction cannot be computed. Current frequency 2/Month. The current frequency of 2/Month was established pursuant to a request from the permittee and the staff's best engineering judgment when the permit was reissued in 2003.)

The proposed permit (2009 reissuance) requires a monitoring frequency of 3/Week for BOD<sub>5</sub>, TSS, and TKN for Outfall 001. Once per week for BOD<sub>5</sub> would not be sufficient given the control equations; i.e., the complexity of the control equations demand more than the minimum frequency allowed. Three per week is also consistent with TSS and TKN.

For Outfalls 101 and 201, frequencies of 1/Week are proposed for BOD<sub>5</sub> and TSS. This is consistent with the indicated reductions presented above except for TSS at Outfall 101. Current Agency protocol suggests 1/Month TSS monitoring in all municipal permits. Once per week is appropriate however, given the control equation for TSS in the permit. It also represents a significant reduction in the current monitoring frequency. TKN monitoring frequencies are the same as in the 2006 permit.

Effluent Monitoring Frequencies are addressed in special condition 25 in the 2006 permit. The language has been revised to be consistent with current guidance.

y. Special Condition 25 – O&M Manual

An O&M Manual is required by Code of Virginia § 62.1-44.19; the Sewage Collection and Treatment Regulations, 9 VAC 25-790; and the VPDES Permit Regulation, 9 VAC 25-31-190 E.

O&M Manual requirements were previously addressed in Special Condition 19. Special Condition 25 is new in this proposed permit and the format is consistent with current guidance. Note that both the Doswell and Bear Island wastewater treatment plants are addressed.

z. Special Condition 26 – Materials Handling/Storage

This special condition implements the requirements of 9 VAC 25-31-50 A which prohibits the discharge of any wastes into State waters unless authorized by permit. Code of Virginia § 62.1-44.16 and 62.1-44.17 authorizes the Board to regulate the discharge of industrial waste or other waste.

This is a new special condition. This condition is included in all industrial and municipal VPDES permits.

aa. Special Condition 27 – Nutrient and TMDL Reopeners

Regarding part a of this special condition, Section 303(d) of the Clean Water Act requires that TMDLs (Total Maximum Daily Loads) be developed for waters listed as impaired. This special condition is to allow the permit to be reopened if necessary to bring it into compliance with any applicable TMDL approved for the receiving waters. The re-opener recognizes that, according to section 402(o)(1) of the Clean Water Act, limits and/or conditions may be either more or less stringent than those contained in this permit. Specifically, they can be relaxed if they are the result of a TMDL, basin plan, or other wasteload allocation prepared under section 303 of the Act. This special condition is included in all VPDES permits.



Regarding parts b and c of this special condition, 9 VAC 25040-70 A authorizes DEQ to include technology-based annual concentration limits in the permits of facilities that have installed nutrient control equipment, whether by new construction, expansion, or upgrade. 9 VAC 25-31-390 A authorizes DEQ to modify VPDES permits to promulgate amended water quality standards.

This is a new special condition.

bb. Special Condition 28 – Reclamation and Reuse Reopener

The mill expansion at Bear Island proposes reuse of the effluent from the Doswell WWTP. This special condition provides for reopening of the permit to incorporate appropriate reuse requirements. The reopener is included in the permit as a best engineering judgment.

This is a new special condition.

cc. Special Condition 29 – Closure of Industrial Wastewater Treatment Facilities

This special condition establishes the requirement to submit a closure plan for the Bear Island wastewater treatment facilities if the facilities are being replaced or closed (reference State Water Control Board Statutes § 62.1-44.19). (Closure of sewage treatment facilities is addressed by the Virginia Sewage Collection and Treatment Regulations.)

This is a new special condition.

dd. Special Condition 30 – Dissolved Oxygen Modeling

Due to concerns with previous modeling efforts, the DEQ has determined that remodeling of the Doswell WWTP discharge is necessary. The VPDES permit currently limits the effluent by use of a “control” equation that was derived by the DEQ in 1978. In addition, the York River Basin Water Quality Management Plan limits the discharge to 690 lbs/day of cBOD<sub>5</sub>. The discharge has been addressed by several later modeling reports, including a 1988 model of the North Anna and Pamunkey Rivers by HDR Infrastructure, a 1995 regional model for the Pamunkey River by Black & Veatch, and a 1999 Conceptual Engineering Report in support of Bear Island Paper Company LLC (BIPCO) by AWARE Environmental.

The current permit authorizes a total maximum flow of 5.75 MGD, comprised of 1.0 MGD from the municipal plant, and 4.75 MGD from BIPCO. Each of the previous modeling efforts (1978, 1988, 1995, or 1999) incorporate a total discharge flow that is different than the 5.75 MGD authorized flows. Consequently, water quality model results do not currently exist representing the combined authorized 5.75 MGD discharge flows.

The historical modeling efforts have been found to be in need of update to, among several factors: a) reflect current ambient and effluent conditions (including recent legislative Lake Contingency Plan and North Anna Lake Minimum Instream Flow policies, the effects of a heated BIPCO discharge on seasonal mixed ambient temperatures, etc.); b) address issues regarding the

application of anti-degradation policies; c) to reconcile the 1988 HDR report conclusions stating that supersaturated effluent oxygenation may be needed to protect water quality when North Anna instream flows were at levels greater than 7Q10 low flows; and d) to reconcile the 1995 Black & Veatch report conclusions indicating that anticipated dissolved oxygen violations would be expected under design conditions in the Pamunkey River due to the contributing BOD loadings from the Ashland and Doswell WWTPs. In addition, water quality modeling efforts performed by DEQ in 2010 for the Hanover County Courthouse STP (VA0062154) indicate a potential upstream contributing influence from the Doswell WWTP that extends beyond the historical modeled segments. Consequently, there is a need for the model to be updated to extend the length of modeled segments to full dissolved oxygen (DO) sag recovery for each of the included discharges.

An updated WQ model is also warranted to a) eliminate the current “control” equation, so that the Doswell WWTP permit will conform to current DEQ guidance that limits permits to a maximum of two ambient stream flow tiers for effluent limitation development purposes, and b) to assess the municipal and BIPCO effluents as two separate permitted discharges. The Environmental Protection Agency (EPA) Region III has expressed the need for industrial effluents (such as BIPCO’s) that share an outfall, but do not send their industrial wastewaters to the head works of a municipal treatment system, to secure their own separate individual permit coverage. Prior to undertaking such a step, an updated WQ model would be necessary to establish the respective effluent waste load allocations between BIPCO and the municipal plant.

This special condition establishes DEQ’s intent to have the WQ model of the Doswell WWTP updated during the term of this permit. As written, the special condition is not intended to reflect a mandate for the permittee to undertake the expense and efforts to develop an updated WQ model. Rather, the special condition provides the permittee an opportunity to voluntarily take the lead in re-modeling efforts. Alternatively, if the permittee does not pursue or complete re-modeling efforts, or if the permittee’s modeling submittal is rejected by DEQ staff, then DEQ will take discretionary control over developing the modeling analyses to be applied in the subsequent reissued permit cycle. This may include, but is not limited to, utilization of the DEQ Regional Water Quality Model for Free Flowing Streams. Modeling efforts are to address updated 7Q10 values, but modeling may also be performed for other 7Q10 values. The Department is willing to review the results of such modeling when developing limits for the next permit reissuance.

The two (2) year schedule is intended to facilitate regulatory modification of the cBOD<sub>5</sub> waste load allocation in the York River Basin Water Quality Management Plan (9VAC25-720-120), to incorporate a) final model results if they support a different cBOD<sub>5</sub> WLA value; and b) to establish a line item waste load allocation for BIPCO.

In 2010, BIPCO submitted, in response to DEQ’s suggestion, preliminary updated simulation results, using the Qual2K model, prepared by AWARE Environmental. However, DEQ staff review of AWARE’s preliminary submittal has found additional model development efforts to be needed for it to be

considered approvable and consistent with the special condition requirements. Further coordination with DEQ staff during the interim schedule period is encouraged. Since Hanover County is the current permit holder, the ultimate responsibility and decision to submit modeling results under this special condition rests with Hanover County.

Part I.C – Water Quality Criteria Monitoring (flowing Expansion of the Bear Island mill)

As mentioned at the beginning of this section, Part I.C of the proposed permit (2009 reissuance) requires water quality criteria sampling at Outfall 001 after the Bear Island expansion. State Water Control Law §62.1-44.21 authorizes the Board to request information needed to determine the discharge's impact on State waters. States are required to review data on discharges to identify actual or potential toxicity problems, or the attainment of water quality goals, according to 40 CFR Part 131, Water Quality Standards, subpart 131.11. To ensure that water quality criteria are maintained, the permittee is required to analyze the facility's effluent for the substances noted in Part I.C of this permit. As previously mentioned, this requirement is implemented for existing discharges as part of the application process. This special condition requires this sampling on the expanded discharge if the expansion occurs during the term of the permit.

20. Part II, Conditions Applicable to All VPDES Permits

The VPDES Permit Regulation at 9 VAC 25-31-190 requires all VPDES permits to contain or specifically cite the conditions listed.

These conditions are the same as in the 2006 permit.

21. Changes to Permit: See Table V

22. Variances/Alternate Limits or Conditions: None

23. Public Notice Information required by 9 VAC 25-31-280 B:

Publication Dates: TBD and TBD in the Richmond Times-Dispatch

Comment period      Start Date:      End Date:

All pertinent information is on file and may be inspected or copied by contacting Ray Jenkins at:

Virginia Department of Environmental Quality (DEQ)  
Piedmont Regional Office  
4949-A Cox Road  
Glen Allen, Virginia 23060-6296

Telephone Number 804/527-5037  
Facsimile Number 804/527-5106  
Email rrjenkins@deq.state.va.us

Persons may comment in writing or by email to the DEQ on the proposed permit action, and may request a public hearing, during the comment period. Comments shall include the name, address, and telephone number of the writer and of all persons represented by the commenter/requester, and shall contain a complete, concise statement of the factual basis for comments. Only those comments received within this period will be considered. The DEQ may decide to hold a public hearing, including another comment period, if public response is significant and there are substantial, disputed issues relevant to the permit. Requests for public hearings shall state 1) the reason why a hearing is requested; 2) a brief, informal statement regarding the nature and extent of the interest of the requester or of those represented by the requester, including how and to what extent such interest would be directly and adversely affected by the permit; and 3) specific references, where possible, to terms and conditions of the permit with suggested revisions. Following the comment period, the Board will make a determination regarding the proposed permit action. That determination will become effective, unless the DEQ grants a public hearing. Due notice of any public hearing will be given.

The public may review the draft permit and application at the DEQ Piedmont Regional Office by appointment.

24. Additional Comments:

- a. Storm Water: Storm water at the Doswell wastewater treatment plant is addressed by VPDES Industrial Storm Water general permit VAR051377. (Storm water at Bear Island is addressed by individual permit VA0077763.)
- b. Effective August 7, 2008, a fast-track rule making procedure to amend the *Water Quality Management Planning Regulation* (9 VAC 25-720-120.C) was completed, establishing total nitrogen and total phosphorus nutrient allocations for Bear Island that are separate from Hanover County. On October 23, 2008, Bear Island filed a Registration Statement (General Permit VAN030133) for coverage under the *General VPDES Watershed Permit Regulation for Total Nitrogen and Total Phosphorus Discharges and Nutrient Trading in the Chesapeake Bay Watershed in Virginia* (9 VAC 25-820). These actions were in accordance with a November 15, 2007 Settlement Agreement leading to the dismissal of the litigation *Bear Island Paper Company LLC v. State Water Control Board*. The Settlement Agreement further stipulates that "If Bear Island installs treatment technology for the control of nitrogen or phosphorus, whether by new construction, expansion, or upgrade to its wastewater treatment plant..." Bear Island will apply for and be subject to an individual VPDES permit." At that time DEQ staff intends to address all of Bear Island's discharge requirements in an individual permit(s) issued to Bear Island (i.e., Bear Island will not be included in the permit issued to Hanover County).
- c. DEQ staff intends to review the modeling and development of the control equations in this permit prior to reissuance of the permit in 2016. The purpose of that review will be to develop seasonal, effluent limitation tiers to replace the current control equations, and may include modification of the York River Water Quality Management Plan.

- d. Previous Board Action: No action affecting this permit.
- e. The 2006 permit was not reissued before its expiration date due to administrative priorities.
- f. Public Comment: *will be added at conclusion of public comment period*

25. Summary of attachments to this Fact Sheet:

Attachment 1	Location maps
Attachment 2	Treatment and Water Flow Schematics for current condition
Attachment 3	Ambient Data on North Anna River
Attachment 4	Flow Frequency Memorandum
Attachment 5	Site inspection
Attachment 6	Effluent data
Attachment 7	Effluent Limitation Development for current condition
Attachment 8	WET Evaluation
Attachment 9	Development of control equations
Attachment 10	Lake Level Contingency Plan
Attachment 11	TKN degradability study
Attachment 12	Treatment and Water Flow Schematics for Bear Island expansion
Attachment 13	Development of control equation for the Bear Island expansion
Attachment 14	Effluent Limitation Development for the Bear Island expansion

TABLE I  
 Effluent Limitations for Doswell Wastewater Treatment Plant, VA0029521  
 Outfall 001 – Prior to Mill Expansion at Bear Island

PARAMETER	BASIS			PERMIT LIMIT				MONITORING REQUIREMENTS	
	EFFLUENT GUIDELINES	BEJ*	WATER QUALITY <sup>(1)</sup>	MONTHLY AVERAGE	WEEKLY AVERAGE	MINIMUM	MAXIMUM	FREQUENCY	SAMPLE TYPE
Flow of North Anna at gaging station above Little River	Monitoring of stream flow required to use equations I.A.1.c.(1) and I.A.1.f.(1)							Continuous	Recorded
Flow of North Anna at Route 30 gaging station								Continuous	Recorded
Effluent Flow	Monitoring only			NL	NL	NA	NL	Continuous	TIRE**
pH			1	NA	NA	6.0 SU	9.0 SU	1 / Day	Grab
BOD <sub>5</sub>			2	Also see <b>Attachment 9</b>		NA	2393 kg/d	3 / Week	24 HC
TSS	√	√		Also see <b>Attachment 9</b>		NA	2393 kg/d	3 / Week	24 HC
Dissolved Oxygen			2	NA	NA	6.5 mg/L	NL	1 / Day	Grab
Total Kjeldahl Nitrogen			2	NL	13.0 mg/L	NA	NA	3 / Week	24 HC
Temperature (°F)	Monitoring only			NL	NA	NA	NL	1 / Day	Immersion Stabilization
	Ambient stream temperature shall not be increased by more than 3 °C								
Also see attached supplement to this table									

\* Best Engineering Judgment

\*\* Totalizing, Indicating, and Recording Equipment

“NL” means that an effluent limitation has not been established. Monitoring and reporting however, are required.

“NA” means not applicable.

“24HC” means 24-hour composite.

- (1) Key:
1. State Water Quality Standards, 9 VAC 25-260, effective February 12, 2004 with amendments effective January 12, 2006 and September 11, 2007.
  2. Water Quality Standards based on wasteload allocation modeling – see attached supplement.

### Outfall 001 – Supplement to Table 1

#### Flow

The Doswell Wastewater Treatment Plant is designed for 1.0 MGD monthly average.

The Bear Island flows have evolved as follows:

1. Original design flow of the wastewater treatment plant was 1.5 MGD.
2. WWTP upgraded to 2.88 MGD average and 3.45 MGD maximum to include wastewater from the sulfonation process (1987/88).
3. WWTP re-rated to 3.39 MGD average and 3.87 MGD maximum to accommodate an increase (“debottlenecking”) in the use of recycled pulp (October 1994).
4. By letter dated June 10, 2002, Bear Island requested a rerating of the hydraulic capacity of their wastewater treatment facility to 4.2 MGD average and 4.8 MGD daily maximum.
5. Proposed mill expansion will increase flows to 5.75 MGD average and 6.34 MGD maximum. These flows include the flow from the Doswell Wastewater Treatment Plant.

#### Control Equations

**Attachment 9** contains memoranda dated June 19, 1978 and July 12, 1978 and hand-written notes dated May 21, 1985 that document the development of the initial control equation and modifications made in the permit reissued in 1988 permit.

Regarding the control equations for the current condition (i.e., pre Bear Island expansion) the following information is provided:

1. The initial control equation (1978) did not address water withdrawals. When the permit was modified in 1988 to first reflect a proposed expansion at Bear Island, the subtraction of a fixed water withdrawal of 10.85 cfs was incorporated into the equation (10.85 cfs was the total capacity of the Doswell Water Treatment Plant (WTP) and Bear Island river water intakes). With the reissuance of the permit in 1995, the fixed value of 10.85 cfs was replaced with a variable,  $Q_W$ , that still reflected the Doswell WTP and Bear island intakes only. In 2003,  $Q_W$  was replaced with a specifically identified withdrawal variable –  $Q_{BIPCO}$  – and a fixed value of 2.6 cfs reflecting two water withdrawals – Paramount’s Kings Dominion and Engel Farm – that were not previously incorporated into the equation. The withdrawal for the Doswell Water Treatment Plant was taken out of the equation because that withdrawal was reflected in the river gage reading at Route 30 (i.e., the previous permits double counted the withdrawal at the water plant). The equation was further modified to include another variable,  $Q_{PLAN}$ , which was an addition to the flow used in the calculation.  $Q_{PLAN}$  was the reduction (below 40

cfs) in the Lake Anna dam release during implementation of the Lake Level Contingency Plan (see **Attachment 10**). Also, a second control equation was developed for a gaging station to be located on the North Anna River above the Little River. The Lake Level Contingency Plan allows Dominion Power to reduce the guaranteed water release rate from Lake Anna when low water levels in the lake threaten operation of the power station (see additional information below regarding the Lake Level Contingency Plan). By regulation however, implementation of the Plan is not to impact downstream riparian owners.  $Q_{PLAN}$  therefore, was added to the flows in the equation in order to prevent impact (i.e., a lower calculated effluent limitation). The Plan also provides for returning the release rate to 40 cfs if downstream water quality problems are noted.

2. Water withdrawals are as follow:
  - a. Bear Island has a withdrawal capacity of 4.0 MGD. (Note that this value of 4.0 MGD differs from the value in Attachment 2, which shows a withdrawal of up to 6.5 MGD. The capacity of the existing pumps however, is 4.0 MGD.)
  - b. Engel Farms withdraws water from the North Anna to irrigate approximately 420 acres of farmland. A total of 5.0 MGD can be withdrawn – 2.2 MGD from intakes above Route 30 for irrigation of 190 acres of farm land, and 2.8 MGD below Route 30 for 230 acres. (This information on the withdrawal capacities of Engel Farms was obtained from a telephone conversation with Kevin Engel.) Pumping however, would have to continue for 24 consecutive hours, which is unlikely, in order to reach those capacities. A more reasonable assessment of the actual withdrawal amount was to assume an irrigation rate of 1 inch per acre per week. For the 190 acres above Route 30, that results in a daily withdrawal of 0.74 MGD. For the 230 acres below Route 30 the result is 0.89 MGD.
  - c. Paramount Kings Dominion has a withdrawal capacity of approximately 0.8 MGD below Route 30 for non-potable uses in the park. When the Park is preparing in early March to open for the season, water is continuously pumped from the river to fill water attractions.
  - d. The withdrawal for the Doswell Water Treatment Plant is 4.0 MGD (but is no longer a subtraction in any control).
3. The Kings Dominion withdrawal of 0.8 MGD and the Engel Farm withdrawal of 0.89 MGD below Route 30 must be subtracted from the gage reading at Route 30 in the control equation at I.A.1.f.(1).  $0.8 + 0.89 = 1.69$  MGD, or 2.6 cfs.
4. In the proposed permit (2009 reissuance),  $Q_{PLAN}$  has been removed from the equation in Part I.A.1.f.(1).  $Q_{PLAN}$  was removed because use of the equation is no longer forced to the low stream flows where  $Q_{PLAN}$  becomes a significant issue – see discussion in item 5 below.
5. Part I.A.1.f.(2) (previously I.A.1.c.(3)) establishes a lower limit on the applicability of the control equation when the Route 30 gaging station is used. This is



consistent with all permits, which base BOD<sub>5</sub> (and CBOD<sub>5</sub>) effluent limitations on the 7Q10 of the receiving stream. The minimum low flow to be used in the equation was established in the 2006 permit by subtracting all withdrawals from the 7Q10 flow in an attempt to establish the actual flow that had a return frequency of 7 consecutive days every 10 years. In hindsight, subtracting the withdrawals did not technically accomplish that, but it did introduce some conservatism to counterbalance the altered return frequency created by the controlled release of water from Lake Anna. With this reissuance (2009), data at both the gaging stations at Route 30 and at the North Anna above the Little River (using regression analysis) have been evaluated to establish theoretical low flows at those locations. The 7Q10 flow at the Route 30 gaging station is 39 cfs. (Note that the 7Q10 of the Little River is no longer added to the North Anna low flows to determine flows at the outfall.) The proposed permit (2009 reissuance) therefore, indicates 39 cfs as the low flow to which the equation is applicable (compared to 35.66 cfs in the 2006 permit).  $Q_{PLAN}$  has been deleted because use of the equation is no longer forced to the low stream flows where  $Q_{PLAN}$  becomes a significant issue.

6. In the proposed permit (2009 reissuance),  $Q_{PLAN}$  has been removed from the equation in Part I.A.1.c.(1).  $Q_{PLAN}$  was removed because use of the equation is no longer forced to the low stream flows where  $Q_{PLAN}$  becomes a significant issue – see discussion in item 7 below.
7. Part I.A.1.c.(3) establishes a lower limit on the applicability of the control equation for the gaging station on the North Anna above the Little River (which is now the normal condition). The 7Q10 at that location was determined to be 45 cfs using data from both gages and regression analysis. The proposed permit (2009 reissuance) therefore, indicates 45 cfs as the low flow to which the equation is applicable (compared to 26.86 cfs in the 2006 permit after subtracting all upstream withdrawals; see discussion above).  $Q_{PLAN}$  was deleted because use of the equation is no longer forced to the low stream flows where  $Q_{PLAN}$  becomes a significant issue.

#### BOD and TKN Loadings at 7Q10 Stream Flow

The York River Basin 303(e) Water Quality Management Plan (WQMP) allocates at 7Q10 stream flow an ultimate biochemical oxygen demand (BOD) of 1,125 pounds per day to the Doswell discharge (including the Bear Island discharge). 690 pounds per day of that allocation is cBOD<sub>5</sub>.

The 1995 permit and previous permits that addressed Bear Island contained a specific statement limiting discharge at 7Q10 to 690 pounds per day BOD<sub>5</sub>. The 2006 permit does not explicitly contain that restriction because the control equations in that permit generate loadings less than 690 at the adjusted stream flows which are used in the equations (i.e., when upstream withdrawals are subtracted from stream gage readings). With the development of actual 7Q10 flows at the two gaging stations however (see discussion above – Control Equations, #5), the calculated loadings at 7Q10 exceed 690 pounds per day (312 kg/d). It is necessary therefore, to reestablish this limitation.

The permit has not previously addressed TKN loading at 7Q10, which represents the nitrogenous portion of the ultimate BOD allocation. For similar reasons that apply to reestablishing the 690 pound per day BOD<sub>5</sub> limitation, it is necessary to limit, at 7Q10, nitrogenous demand via a TKN loading limitation. A limitation of 507 pounds per day (229 kg/d) was developed as follows: The York River 303(e) Plan assigns a percentage of ultimate nitrogenous demand to each segment of the basin reflecting the percentage of discharged nitrogen that is expected to remain once it reaches tidal waters and exert a demand. Twenty-five (25) percent is the value assigned to “headwaters”. (The other designated waters are “Tidal/Non-Tidal Interface” and “Tidal”.) The Plan also defines ultimate BOD<sub>5</sub> as BOD<sub>5</sub> ÷ 0.8. The TKN loading limitation at 7Q10 therefore, is as follows:

$$1125 - (690 \div 0.8) = 262.5 \text{ pounds per day nitrogenous demand}$$

$$262.5 \div 4.5 \text{ (conversion factor)} = 58.333 \text{ pounds per day TKN}$$

$$58.333 \times 4 \text{ (“headwaters” percentage)} \div 0.46 \text{ (see TKN discussion below)} = 507.2 \text{ pounds per day, which will be written in the permit as 507 pounds per day (229 kg/d).}$$

#### BOD and TSS Daily Maximum Limitations

A decision was made when control equations were first included in the permit to put a cap on the BOD and TSS that could be discharged so that the permit would not be completely open-ended in regard to the quantities of those pollutants that could be discharged. A maximum (or cap) is also needed to insure compliance with the Federal effluent guidelines that apply to Bear Island – see “Outfall 201 – Supplement to Table III”. The calculation of 5,275 pounds per day is based on an earlier version of the control equation with inputs of an effluent flow of 4.45 MGD (1.0 MGD for the Doswell sewage treatment plant and 3.45 MGD daily maximum for Bear Island; see section titled Flow above) and a stream flow of 300 cfs. The value of 5,275 pounds per day remains an appropriate cap regardless of subsequent changes in design flow. The TSS cap was set at the same value as the BOD<sub>5</sub> cap.

#### TKN

The original modeling that was used to establish the control equation assumed a TKN concentration of 6 mg/L. The information presented in **Attachment 11** indicates that only 46% of the TKN decomposes and exerts an oxygen demand. The limitation of 13 mg/L reflects this percentage (i.e.,  $6 \div 0.46 = 13$ ). The 1995 permit required that this degradation study be repeated to determine if the addition of recycled paper facilities altered the percentage of decomposition. That study confirmed that 46% conservatively establishes the percentage of decomposition. Therefore, the 2006 permit and the proposed permit (2009 reissuance) maintain the limitation of 13 mg/L as a weekly average.

The TKN limitation of 13 mg/L effectively limits ammonia to concentrations below toxic levels. See STATS printout for ammonia in Attachment 7.

### Temperature

From Attachment 6B, Outfall 001 effluent temperatures (July 2005 through June 2008) are as follow:

- 36°C (maximum)
- 34°C (90<sup>th</sup> percentile maximum)
- 30.6°C (90<sup>th</sup> percentile average)
- 27°C (90<sup>th</sup> percentile minimum)

From Attachment 3, ambient stream temperatures (January 1979 through March 2008) are as follow:

- 0.5°C (minimum)
- 5.5°C. (10<sup>th</sup> percentile)

The North Anna Lake Contingency Plan is triggered at stream flows less than 40 cfs and design effluent flow is 5.8 MGD (9.0 cfs).

From the attached spreadsheet titled "North Anna River Delta Ts" of actual delta Ts calculated from January 2006 through November 2008, the following observations are noted:

- Emphasis should be given to conditions occurring in the late Fall and Winter when ambient stream temperatures are cool, and stream flows are low. Based on the historic stream data, there are Fall/Winter cool temperature dates where flows approached the Lake Contingency Plan flow threshold. It would thus appear appropriate to use annual or lake contingency low flows, rather than winter tier high flows, in analyzing "worse-case" permitting design conditions.
- The attached spreadsheet indicates that exceedances of the delta 3°C standard may have occurred on two dates, 11/26/07 and 11/27/07. On those dates, the potential delta T was calculated to be 4.67 and 5.01°C, respectively. Those data confirm the reasonable potential for the delta T of 3°C to be exceeded *in the field*.

Manipulating the worksheets confirmed some scenarios at flows greater than 40 cfs that would result in delta temperatures greater than 3°C. Using data from February 5, 2002, North Anna flows were 46.4 cfs with an ambient stream temperature of 3.36°C. At a design effluent flow of 9 cfs, and using the 90<sup>th</sup> percentile minimum value of 27°C, the predicted delta T would be 3.84°C. Using the more conservative 90<sup>th</sup> percentile maximum value, the predicted delta T would be 4.98°C.

Repeating the above steps using more recent stream data (November 12, 2008 @ 60 cfs and 10°C) coupled with design effluent data (flow of 9 cfs and 90% max temp of 34°C) would result in a predicted delta T of 3.13°C.

Using lake contingency flows (40 cfs), 10<sup>th</sup> percentile stream temperature (5.5°C), effluent design flow (9 cfs), and 90% max effluent temp (34°C) would result in a predicted "worse case" design-condition delta T of 5.23°C.

Given the November 2007 historical cases, the hybrid scenarios outlined above (using historical stream data with effluent design data), and the permitting design condition (design stream data with effluent design data), there appears to be several scenarios for a reasonable potential to exist where stream temperatures may rise more than 3°C due to the heated Doswell discharge. It is therefore, appropriate to limit the instream temperature change (delta T) to 3 °C in the permit.

A compliance schedule is not needed in regard to meeting this delta T requirement because of the cooling that can be achieved in the effluent holding pond.

#### Lake Level Contingency Plan

The VPDES permit issued to the North Anna Nuclear Power Station contains a Lake Level Contingency Plan as required by §62.1-44.15:1.2 of the Code of Virginia, adopted in 2000. See Attachment 10. Dominion Virginia Power was previously required to release a minimum of 40 cfs from Lake Anna. That 40 cfs is included in the calculation of the statistical low flows. The Lake Level Contingency Plan however, allows Dominion Virginia Power to reduce the release from the lake to 20 cfs under specified conditions. If any downstream user identifies an adverse impact during such low flow conditions however, that impact is to be reported to the DEQ and the Director of DEQ is to decide if the release rate should be returned to 40 cfs. It is the intent of this legislation that downstream users not be burdened as a result of implementing the Contingency Plan.

TABLE II

Effluent Limitations for Outfall 101 – Discharge from the Doswell Wastewater Treatment Plant

PARAMETER	BASIS			PERMIT LIMIT				MONITORING REQUIREMENTS	
	EFFLUENT GUIDELINES	BEJ*	WATER QUALITY <sup>(1)</sup>	MONTHLY AVERAGE	WEEKLY AVERAGE	MINIMUM	MAXIMUM	FREQUENCY	SAMPLE TYPE
Flow	Monitoring only			NL	NL	NA	NL	Continuous	TIRE
BOD <sub>5</sub>	√			30 mg/L	45 mg/L	NA	NA	1 / Week	24 HC
TSS	√			30 mg/L	45 mg/L	NA	NA	1 / Week	24 HC
<i>E. coli</i> (n/100ml)			1	126**	NA	NA	NL	3 Days / Week	Grab
Total Kjeldahl Nitrogen	Monitoring only			NL	NL	NA	NA	1 / Month	24 HC
The permit also requires 85% removal of BOD <sub>5</sub> and TSS.									

\* Best Engineering Judgment

\*\* Geometric mean

“NL” means that an effluent limitation has not been established. Monitoring and reporting however, are required.

“NA” means not applicable.

“24HC” means 24-hour composite.

- (1) Key: 1. State Water Quality Standards, 9 VAC 25-260, effective February 12, 2004 with amendments effective January 12, 2006 and September 11, 2007.

TABLE III

Effluent Limitations for Outfall 201 – Discharge from the Bear Island Wastewater Treatment Plant

PARAMETER	BASIS			PERMIT LIMIT				MONITORING REQUIREMENTS	
	EFFLUENT GUIDELINES	BEJ*	WATER QUALITY	MONTHLY AVERAGE	WEEKLY AVERAGE	MINIMUM	MAXIMUM	FREQUENCY	SAMPLE TYPE
Flow	Monitoring only			NL	NL	NA	NL	Continuous	TIRE
BOD <sub>5</sub>	Monitoring only			NL	NL	NA	NA	1 / Week	24 HC
TSS	Monitoring only			NL	NL	NA	NA	1 / Week	24 HC
Total Kjeldahl Nitrogen	Monitoring only			NL	NL	NA	NA	2 / Month	24 HC
Also see attached supplement to this table									

\* Best Engineering Judgment

“NL” means that an effluent limitation has not been established. Monitoring and reporting however, are required.

“NA” means not applicable.

“24HC” means 24-hour composite.

### Outfall 201 – Supplement to Table III

#### Comparison of effluent limitations in proposed permit (2009 reissuance) to limitations in Federal Effluent Guidelines

Bear Island has certified (by letter dated July 8, 2008) that they do not use zinc hydrosulfite for bleaching or chlorophenolic-containing biocides. Therefore, limitations for **zinc**, **pentachlorophenol**, and **trichlorophenol** as contained in the Guidelines are not required.

#### **BOD<sub>5</sub> and TSS**

Bear Island reported the following quantities that are representative of actual production levels: 410 tons per day of thermo-mechanical pulp (which includes 50 tons per day of purchased Kraft pulp) and 300 tons per day of recycled pulp. Thermo-mechanical pulping is addressed by Subpart M of the guidelines and recycled pulp is addressed by Subpart Q – Deink Subcategory.

From Federal Guidelines (numbers expressed as pounds per 1000 pounds of production):

	30-day Average	Daily Maximum
Thermo-mechanical Subcategory – 40 CFR Part 430.132, Subpart M, BPT		
BOD <sub>5</sub>	5.55	10.6
TSS	8.35	15.55
Deink Subcategory – 40 CFR Part 430.175, Subpart Q, NSPS*, newsprint		
BOD <sub>5</sub>	3.2	6.0
TSS	6.3	12.0

\* Recycled pulp added to process after promulgation of guidelines.

#### Calculation of effluent limitation

$$\begin{aligned} \text{BOD}_5: \text{ Average} &= [(410 \times 2000) \div 1000] \times 5.55 + [(300 \times 2000) \div 1000] \times 3.2 \\ &= 6,471 \text{ pounds per day} \end{aligned}$$

$$\text{Maximum} = 12,292 \text{ pounds per day}$$

$$\text{TSS: Average} = 10,627 \text{ pounds per day}$$

$$\text{Maximum} = 19,951 \text{ pounds per day}$$

The control equations limit BOD<sub>5</sub> (prior to mill expansion), CBOD<sub>5</sub> (following mill expansion), and TSS to levels below the above guideline values. The permitted maximum for BOD<sub>5</sub>, CBOD<sub>5</sub>, and TSS is 5275 pounds per day regardless of stream flow.

TABLE IV

Effluent Limitations for Doswell Wastewater Treatment Plant, VA0004669  
 Outfall 001 – After Mill Expansion at Bear Island

PARAMETER	BASIS			PERMIT LIMIT				MONITORING REQUIREMENTS	
	EFFLUENT GUIDELINES	BEJ*	WATER QUALITY <sup>(1)</sup>	MONTHLY AVERAGE	WEEKLY AVERAGE	MINIMUM	MAXIMUM	FREQUENCY	SAMPLE TYPE
Flow of North Anna at gaging station above Little River	Monitoring of stream flow required to use equation I.A.4.c.(1) and I.A.4.h.(1).							Continuous	Recorded
Flow of North Anna at Route 30 gaging station								Continuous	Recorded
Effluent Flow	Monitoring only			NL	NL	NA	NL	Continuous	TIRE
pH			1	NA	NA	6.0 SU	9.0 SU	1 / Day	Grab
CBOD <sub>5</sub> (also see <b>Attachment 13</b> )	√		2	NL	30 mg/L	NA	2393 kg/d	1 / Day	24 HC
TSS (also see <b>Attachment 13</b> )		√		NL	50 mg/L	NA	2393 kg/d	1 / Day	24 HC
Dissolved Oxygen									
Cascade Aeration			2	NA	NA	6.5 mg/L	NL	1 / Day	Grab
Pure Oxygen			2	See <b>Attachment 13</b>				Continuous	Measured
Total Kjeldahl Nitrogen**			2	NL	10.0 mg/L	NA	NA	1 / Day	24 HC
Temperature (°F)			1	NL	NA	NA	90	1 / Day	Immersion Stabilization
Ambient stream temperature shall not be increased by more than 3 °C									
Also see attached supplement to this table									

\* Best Engineering Judgment

\*\* Also see **Attachment 13**

“NL” means that an effluent limitation has not been established. Monitoring and reporting however, are required.

“NA” means not applicable.

“24HC” means 24-hour composite.

- (1) Key:
1. State Water Quality Standards, 9 VAC 25-260, effective February 12, 2004 with amendments effective January 12, 2006 and September 11, 2007.
  2. Wasteload allocation modeling



### **Outfall 001 – Supplement to Table IV**

#### Control Equation

See Attachment 13.

The lower limit on stream flow to be used in the control equation has been revised from 22.22 cfs to 45 cfs (Part I.A.4.c.(2)). The 7Q10 at that location was determined to be 45 cfs using data from the Route 30 gaging station, the gaging station on the North Anna River above the Little River gaging stations, and regression analysis. The proposed permit therefore, indicates 45 cfs as the low flow to which the equation is applicable.

#### Temperature

The BIPCo discharge contains heat – see Attachment 6B for temperature data at Outfall 001.

A daily maximum temperature of 90 °F (32 °C) will be continued from the 2006 permit.

As discussed in the Supplement to Table 1, it is also appropriate to limit the instream temperature change (delta T) to 3 °C.

Table V  
 Permit Processing Change Sheet

OUTFALL NO.	PARAMETER CHANGED	MONITORING CHANGED		EFFLUENT LIMITS CHANGED		RATIONALE
		FROM	TO	FROM	TO	
Cover Page	Formatting revised in accordance with new templates – wording changes in first paragraph and “City: NA” was deleted					New guidance
Part I.A.1.a Outfall 001	Added “whichever occurs first” in the first sentence of I.A.1 in regard to the expansion at Bear Island or permit expiration.					Clarity
	Included separate lines for each gaging station for river flow measurement.  Frequency and Sample Type for river flows specified as “Continuous” and “Recorded”, respectively. Special Condition I.B.4 now referenced in a footnote.					The gaging station above the Little River is now the primary location to determine river flow. Use of Route 30 gaging station included as back-up. See item 19.d for discussion of frequency and sample type.
	“Effluent” added to flow at Outfall 001.  Sample Type for effluent flow changed from “Recorded” to “Totalizing, Indicating, and Recording Equipment” (TIRE).					“Effluent” added for clarity.  TIRE more accurate and consistent with guidance.
	BOD <sub>5</sub>	1 / Day	3 / Week	No Change	No Change	Performance based reduction in monitoring frequency. Also see discussion in item 19.y of fact sheet.
	BOD <sub>5</sub> and TSS daily maximums of 2393 kg/d added to Part I.A.1 These loadings are also included at I.A.1.c.(4) and I.A.1.d.(2), respectively. Previous permits established these limitations only in conjunction with the control equations.  The loadings have been revised from 2394 kg/d to 2393 kg/d.					Permit formatting has changed over the years. These limitations are daily maximums.  The change from 2394 to 2393 is a function of the number of decimal places to which the conversion factor is carried. 2393 is consistent with the instruction added at I.A.4.b.(1) – see below.

OUTFALL NO.	PARAMETER CHANGED	MONITORING CHANGED		EFFLUENT LIMITS CHANGED		RATIONALE
		FROM	TO	FROM	TO	
Part I.A.1.a Outfall 001 (cont'd)	Total Nitrogen and Total Phosphorus	Monitoring requirement deleted.  Definition of Total Nitrogen deleted.				Monitoring and reporting now required by general permit VAN030051, which is referenced in the permit. See I.A.1.g below.
	Ammonia	Monitoring requirement deleted.				Ammonia limitations are not indicated – see Attachment 7. Also see Attachment 6B for actual ammonia concentrations in effluent.
Part I.A.1.c Outfall 001	<p>In first sentence, “daily” deleted from phrase “The average of <u>daily</u> BOD<sub>5</sub> values over a calendar week ...”</p> <p>The control equation using the gaging station above the Little River (previously I.A.1.f) was moved to I.A.1.c.(1) Seven samples per week was changed to “n” in response to reduced monitoring and to reflect whatever the number of samples collected during a week to compute the weekly average. Q<sub>PLAN</sub> was deleted. The minimum low flow to which the equation is applicable in I.A.1.c.(3) for the gaging station above the Little River was revised from 26.86 cfs to 45 cfs. (Note that the theoretical low flow no longer includes the Little River.)</p> <p>“[A]t Outfall 001” added to definition of Q<sub>E</sub> for clarity.</p> <p>In Part I.A.1.c.(2), seven samples per week was changed to “n” in response to reduced monitoring and to reflect whatever the number of samples collected during a week to compute the weekly average.</p> <p>In I.A.1.c.(3), the correct reporting form is Attachment A versus the DMR as indicated in the 2006 permit. Also, a second paragraph has been added to I.A.1.c.(3) establishing maximum BOD<sub>5</sub> and TKN loadings at 7Q<sub>10</sub> stream flow. See “Outfall 001 – Supplement to Table I” for an explanation of these maximum loadings.</p> <p>In I.A.1.c.(4), 2394 kg/d changed to 2393 kg/d – see discussion above regarding I.A.1.a.</p>					<p>With reduction in monitoring frequency, daily values will not be determined.</p> <p>The gaging station above the Little River is now the primary location to determine river flow.</p> <p>Low flow revised in accordance with Attachment 4. Also see the Supplement to Table I.</p>

OUTFALL NO.	PARAMETER CHANGED	MONITORING CHANGED		EFFLUENT LIMITS CHANGED		RATIONALE
		FROM	TO	FROM	TO	
Part I.A.1.d.(1) Outfall 001	<p>The averaging period was changed from 3 to “n” days, and the associated footnote was deleted. This change was made to reflect whatever the number of samples that are collected during a week to compute the weekly average.</p> <p>Typographical error corrected in legend – the first item is <math>L_w</math> = effluent TSS concentration ...</p>					Part I.A.1.d.(1) Outfall 001
Part I.A.1.e. Outfall 001	<p>Added the word “monitored” to “A calendar week average shall be calculated by determining each <u>monitored</u> day’s BOD<sub>5</sub> and TSS ...”</p>					Clarity
Part I.A.1.f Outfall 001	<p>The control equation for use of the Route 30 gaging station was moved from I.A.1.c.(1) in the 2006 permit to I.A.1.f.(1) for use as a back-up monitoring location if necessary. The language preceding the equation was rewritten to reflect that alternative. Seven samples per week was changed to “n” in response to reduced monitoring and to reflect whatever the number of samples collected during a week to compute the weekly average. <math>Q_{PLAN}</math> was deleted.</p> <p>Part I.A.1.f.(2), which is similar to Part I.A.1.c. (3) in the 2006 permit, establishes the minimum low flow that is to be used in the equation. That low flow has been revised from 35.66 cfs to 39 cfs. (Note that the theoretical low flow no longer includes the Little River.)</p> <p>In I.A.1.f.(2), the correct reporting form is Attachment A versus the DMR as indicated in Part I.A.1.c. (3) of the 2006 permit.</p> <p>I.A.1.f.(3) has been added to establish maximum BOD<sub>5</sub> and TKN loadings at 7Q10 stream flow. See “Outfall 001 – Supplement to Table I” for an explanation of these maximum loadings.</p>					See Supplement to Table I.
Part I.A.1.g Outfall 001	<p>Reference to coverage under the general permit issued in accordance with 9 VAC 25-820, “General VPDES Watershed Permit Regulation for Total Nitrogen and Total Phosphorus Discharges and Nutrient Trading in the Chesapeake Watershed in Virginia”, was added.</p>					Guidance Memorandum No. 07-2008 and amendments
Part I.A.1.h Outfall 001	<p>Added requirement to the permit that the discharge cannot cause an increase in stream temperature of more than 3 °C.</p>					VA Water Quality Standards
Part I.A.2 Outfall 101	<p>Sample Type for effluent flow changed from “Recorded” to “Totalizing, Indicating, and Recording Equipment” (TIRE).</p>					TIRE more accurate and consistent with guidance.

OUTFALL NO.	PARAMETER CHANGED	MONITORING CHANGED		EFFLUENT LIMITS CHANGED		RATIONALE
		FROM	TO	FROM	TO	
Part I.A.2 Outfall 101 (cont'd)	BOD <sub>5</sub>	5 Days / Week	1 / Week	NA	NA	Performance based reduction in monitoring frequency. Also see discussion in item 19.y of fact sheet.
	TSS	3 Days / Week	1 / Week	NA	NA	
	Fecal Coliform limitation replaced with <i>E. coli</i> limitation of 126 n/100 mL as a monthly geometric mean.					Water Quality Standards were revised to address <i>E. coli</i>
	Significant figures footnote added for BOD <sub>5</sub> and TSS monthly average limitations					Guidance Memorandum No. 06-2016
	Total Phosphorus and ammonia monitoring deleted.					See rationale above for I.A.1.a
	I.A.2.c was added to reference to coverage under the general permit issued in accordance with 9 VAC 25-820, "General VPDES Watershed Permit Regulation for Total Nitrogen and Total Phosphorus Discharges and Nutrient Trading in the Chesapeake Watershed in Virginia".					Guidance Memorandum No. 07-2008 and amendments
Part I.A.3 Outfall 201	Added "whichever occurs first" in the first sentence of I.A.1 in regard to the expansion at Bear Island or permit expiration.					Clarity
	Sample Type for effluent flow changed from "Recorded" to "Totalizing, Indicating, and Recording Equipment" (TIRE).					TIRE more accurate and consistent with guidance.
	BOD <sub>5</sub>	5 Days / Week	1 / Week	NA	NA	Performance based reduction in monitoring frequency. Also see discussion for in item 19.y of fact sheet.
	TSS	3 Days / Week	1 / Week	NA	NA	
	Total Phosphorus and Ammonia	Monitoring requirement deleted.				See rationale above for I.A.1.a
	I.A.3.b was added to reference to coverage under the general permit issued in accordance with 9 VAC 25-820, "General VPDES Watershed Permit Regulation for Total Nitrogen and Total Phosphorus Discharges and Nutrient Trading in the Chesapeake Watershed in Virginia".					Guidance Memorandum No. 07-2008 and amendments

OUTFALL NO.	PARAMETER CHANGED	MONITORING CHANGED		EFFLUENT LIMITS CHANGED		RATIONALE
		FROM	TO	FROM	TO	
Part I.A.4.a Outfall 001 after mill expansion	Identification of gaging station changed from “in the vicinity immediately upstream of Outfall 001” to “above Little River near Doswell”.					Identification is consistent with USGS identification.
	Added footnote (2) to frequency and sample type for this gage.					Recognizes addition of the Route 30 gaging station as a back-up.
	Added line for flow measurement at the Route 30 gaging station. Frequency and Sample Type specified as “Continuous” and “Recorded”, respectively. Special Condition I.B.4 referenced as a footnote.					Route 30 gaging station added as a back-up.  See item 19.d for discussion of frequency and sample type.
	“Effluent” added to flow from at Outfall 001					Clarity
	Sample Type for effluent flow changed from “Recorded” to “Totalizing, Indicating, and Recording Equipment” (TIRE).					TIRE more accurate and consistent with guidance.
	<p>CBOD<sub>5</sub> and TSS daily maximums of 2393 kg/d added to Part I.A.4. These loadings are also included at I.A.4.c.(3) and I.A.4.d, respectively. Previous permits established these limitations only in conjunction with the control equations.</p> <p>The loadings have been revised from 2394 kg/d to 2393 kg/d.</p> <p>In the column for TSS weekly average kg/d, “See A.4.d” has been replaced with “NL”.</p>					<p>Permit formatting has changed over the years. These limitations are daily maximums.</p> <p>The change from 2394 to 2393 is a function of the number of decimal places to which the conversion factor is carried. 2393 is consistent with the instruction added at I.A.4.b.(1) – see below.</p> <p>There is no weekly average TSS loading limitation.</p>
	Total Nitrogen and Total Phosphorus	<p>Monitoring requirement deleted.</p> <p>Definition of Total Nitrogen deleted.</p>				Monitoring and reporting now required by general permit VAN030051, which is referenced in the permit. See I.A.4.g below.
	Ammonia	Monitoring deleted.				See rationale above for I.A.1.a

OUTFALL NO.	PARAMETER CHANGED	MONITORING CHANGED		EFFLUENT LIMITS CHANGED		RATIONALE
		FROM	TO	FROM	TO	
Part I.A.4.c.(1) Outfall 001	In definition of $\underline{L}$ , added instructions for conversion of pounds per day to kg/d.  $Q_S$ revised to $Q_{GAGE}$ .					Instruction for consistency of calculations.  Terminology consistent throughout permit.
Part I.A.4.c.(2) Outfall 001	The minimum low flow to which the equation is applicable in I.A.1.c.(3) for the gaging station above the Little River was revised from 22.22 cfs to 45 cfs.  The correct reporting form is Attachment A versus the DMR as indicated in the 2006 permit.  A second paragraph has been added to establish maximum CBOD <sub>5</sub> and TKN loadings at 7Q10 stream flow. See "Outfall 001 – Supplement to Table I" for an explanation of these maximum loadings.					See Attachment 4 and Supplement to Table IV regarding the revision to stream flow.
Part I.A.4.c.(3) Outfall 001	2394 kg/d changed to 2393 kg/d – see discussion above regarding I.A.4.a.					
Part I.A.4.d Outfall 001	2394 kg/d changed to 2393 kg/d – see discussion above regarding I.A.4.a.					
Part I.A.4.g Outfall 001	Reference to coverage under the general permit issued in accordance with 9 VAC 25-820, "General VPDES Watershed Permit Regulation for Total Nitrogen and Total Phosphorus Discharges and Nutrient Trading in the Chesapeake Watershed in Virginia", was added.					Guidance Memorandum No. 07-2008 and amendments
Part I.A.4.h Outfall 001	Added to permit to establish use of the Route 30 gaging station as a back-up to the gaging station above the Little River.					
Part I.A.4.i Outfall 001	Added requirement to the permit that the discharge cannot cause an increase in stream temperature of more than 3 °C.					VA Water Quality Standards
Part I.B. 2006 permit	Part I.B in the 2006 permit required water quality criteria monitoring on existing Outfall 001 for submittal with the permit renewal application. That requirement has been deleted.					This instruction is now included in the permit "reminder letter" advising the permittee of application requirements.
Part I.B. Proposed permit	In the proposed permit (2009 reissuance), special conditions are addressed in Part I.B. See item 19 in fact sheet for discussion of changes to the special conditions.					

OUTFALL NO.	PARAMETER CHANGED	MONITORING CHANGED		EFFLUENT LIMITS CHANGED		RATIONALE
		FROM	TO	FROM	TO	
Part I.C.	<p>Special Conditions were addressed in Part I.C in the 2006 permit. Special Conditions are addressed in Part I.B of the proposed permit.</p> <p>Part I.C in the proposed permit (2009 reissuance) requires water quality criteria monitoring at Outfall 001 after expansion of the BIPCo mill. This attachment has been updated.</p>					
Part I.D 2006 permit	<p>Part I.D in the 2006 permit contained a compliance schedule for constructing a river gaging station in the North Anna River above the Little River. That schedule has been deleted. (In the permit that was reissued in 2003 Part I.D also contained a compliance schedule for cyanide limitations. The cyanide limitations were removed by permit modification in 2006.)</p>				<p>The gaging station was constructed in accordance with the schedule.</p>	
<p><b>CHANGES IN RESPONSE TO OWNER COMMENT (revisions made May 27 2009)</b></p>						
<p>Part I.A.4.c.(2), second paragraph, was revised to reference CBOD<sub>5</sub> versus BOD<sub>5</sub>. This was a staff oversight; CBOD<sub>5</sub> should have been initially cited. In Part I.A.4.h.(2), a second paragraph was added to establish the maximum CBOD<sub>5</sub> and TKN loadings at 7Q10 flow at the Route 30 gage.</p> <p>Special Condition I.B.5 was revised to include a low flow exclusion.</p>						



#### **DEQ STAFF INITIATED CHANGES – June 3, 2010**

1. Item 24.c in this fact sheet states that DEQ staff intends to review the dissolved oxygen modeling and the control equations contained in this permit with the intent to replace the control equations with fixed, seasonal tiered, effluent limitations. Toward that end, special condition I.B.30 was added to the draft permit. That condition requires the permittee to develop a calibrated and verified model for use in establishing effluent limitations. The proposed special condition also requires that the Doswell WWTP and Bear Island discharges be modeled as separate and combined discharges.
2. As DEQ has updated some of the routinely used special conditions since the previous draft of the permit was reviewed, several special conditions were revised as follows:
  - a. The wording of special conditions 21, 24, 25, and 26 was updated to reflect the most recent agency guidance. The citation in 25.e was also corrected to I.B.26 versus I.B.27.
  - b. Special Condition 28 (of 30 total special conditions) in the previous draft required radionuclide testing. That special condition was deleted because the radionuclide standards now only apply to waters designated as public water supplies. This change prompts renumbering of the two special conditions that follow the deleted condition, and the new condition described above regarding stream modeling is therefore, special condition 30.
  - c. Part I.C of the permit was updated to reflect the revised Virginia Water Quality Standards that became effective on February 1, 2010 as follows: The selenium standard is for the total recoverable form, versus dissolved. The cyanide standard is for free cyanide, versus total. Diazinon, carbon tetrachloride, and nonylphenol were added. The specific PCB arochlors 1260, 1254, 1248, 1242, 1232, 1221, and 1016; radionuclide testing; and Foaming Agents (as MBAS) were deleted. Also, the Special Composite (SC) designation for Pesticide/PCBs, Base Neutrals, Acids, and hydrogen sulfide was deleted and replaced with Composite (C) to be consistent with current guidance.

#### **DEQ STAFF INITIATED CHANGES – May 17, 2011**

Special Condition I.B.30 (see item 1 immediately above) was revised. The permittee is no longer required to develop a calibrated and verified model, but has that option in lieu of relying on DEQ modeling.

### **Attachment 1**

1. First map identifies outfall location
2. Second map more clearly shows receiving stream. Outfall location is immediately below cross section B. The cross sections designate approximate sampling locations for the dissolved oxygen monitoring required by the permit.






Figure 1  
SITE LOCATION MAP



TAKEN FROM USGS MAP  
ASHLAND QUADRANGLE,  
PHOTOREVISED 1985


**ALVARE**  
ENVIRONMENTAL INC



## **Attachment 2**

Four schematics are included:

1. Overall water flow schematic
2. Treatment facilities at the Doswell Wastewater Treatment Plant
3. Flow schematic for Bear Island
4. Treatment facilities at the Bear Island Wastewater Treatment Plant



FORM 2c II.A.i  
MILL WATER BALANCE

BEAR ISLAND PAPER COMPANY, L.L.C.  
WASTEWATER TREATMENT PLANT

SCALE NOT TO SCALE

DATE AUGUST 1999

PROJECT NUMBER  
N106-22

APPROVED BY :


DESIGNED BY :

**AWARE** ENVIRONMENTAL INC.  
9305-J MONROE RD. CHARLOTTE, NC 28270

DRAWN BY: J.K.S.

REVISED OCT. 1999


DRAWING NO.  
FIGURE



**HAZEN AND SAWYER**  
Environmental Engineers & Scientists

DOSWELL WWTP  
HANOVER COUNTY, VIRGINIA

PROCESS  
FLOW  
SCHEMATIC



FORM 2c II.A.ii MILL WATER USAGE		
BEAR ISLAND PAPER COMPANY, L.L.C. WASTEWATER TREATMENT PLANT		
SCALE NOT TO SCALE	APPROVED BY :	DRAWN BY: J.K.S.
DATE AUGUST 1999	DESIGNED BY :	REVISED
PROJECT NUMBER N106-22	 9305-J MONROE RD. CHARLOTTE, NC 28270	
		DRAWING NO. FIGURE





---

### **Attachment 3**

---

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	1/8/1979	S	.30	6.50	7.30		11.30
8-NAR005.42	3/22/1979	S	.30	12.00	7.00		10.50
8-NAR005.42	4/24/1979	S	.30	15.00	7.50		9.80
8-NAR005.42	6/14/1979	S	.30	21.00	7.00		7.20
8-NAR005.42	8/8/1979	S	.30	28.00	6.80		6.40
8-NAR005.42	9/20/1979	S	.30	18.00	7.00		8.40
8-NAR005.42	10/16/1979	S	.30	13.50	7.00		10.00
8-NAR005.42	11/14/1979	S	.30	9.50	7.00		10.50
8-NAR005.42	12/11/1979	S	.30	6.50	7.00		11.60
8-NAR005.42	1/29/1980	S	.30	4.00	7.10		11.80
8-NAR005.42	2/27/1980	S	.30	5.00	6.80		12.40
8-NAR005.42	3/17/1980	S	.30	8.50	6.70		11.20
8-NAR005.42	4/15/1980	S	.30	14.00	7.40		9.30
8-NAR005.42	5/12/1980	S	.30	18.00	7.50		9.00
8-NAR005.42	6/16/1980	S	.30	25.00	7.10		7.80
8-NAR005.42	7/10/1980	S	.30	27.00	6.80		6.80
8-NAR005.42	8/4/1980	S	.30	29.00	7.20		7.10
8-NAR005.42	9/8/1980	S	.30	25.00	6.90		7.20
8-NAR005.42	10/14/1980	S	.30	14.00	7.30		10.40
8-NAR005.42	11/24/1980	S	.30	5.50	6.90		11.40
8-NAR005.42	12/16/1980	S	.30	4.00	6.50		12.20
8-NAR005.42	1/20/1981	S	.30	.50	6.50		11.60
8-NAR005.42	2/17/1981	S	.30	5.50	7.00		12.00
8-NAR005.42	3/18/1981	S	.30	5.00	6.80		11.50
8-NAR005.42	4/16/1981	S	.30	13.00	7.50		11.00
8-NAR005.42	5/12/1981	S	.30	17.00	7.00		8.40
8-NAR005.42	6/15/1981	S	.30	28.50	7.40		8.10
8-NAR005.42	7/14/1981	S	.30	28.00	7.00		7.00
8-NAR005.42	8/12/1981	S	.30	24.70	7.00		6.40
8-NAR005.42	9/10/1981	S	.30	21.50	7.00		7.90
8-NAR005.42	11/19/1981	S	.30	9.00	7.00		5.00
8-NAR005.42	12/8/1981	S	.30	6.00	6.50		12.20
8-NAR005.42	2/9/1982	S	.30	6.00	6.70		9.40
8-NAR005.42	3/24/1982	S	.30	10.00	6.70		9.20
8-NAR005.42	4/28/1982	S	.30	15.00	6.80		
8-NAR005.42	6/29/1982	S	.30	27.00	6.80		5.90
8-NAR005.42	7/28/1982	S	.30	28.50	7.00		5.80
8-NAR005.42	8/18/1982	S	.30	24.50	6.80		6.20
8-NAR005.42	10/19/1982	S	.30	13.00	6.70		9.80
8-NAR005.42	11/17/1982	S	.30		6.70		11.40
8-NAR005.42	12/16/1982	S	.30	8.00	6.50		10.80
8-NAR005.42	1/27/1983	S	.30	3.50	6.70		12.10
8-NAR005.42	2/10/1983	S	.30	4.00	6.50		12.70
8-NAR005.42	3/15/1983	S	.30	12.00	6.70		10.00
8-NAR005.42	4/19/1983	S	.30	11.00	6.50		11.00
8-NAR005.42	5/19/1983	S	.30	17.00	6.80		9.50
8-NAR005.42	6/21/1983	S	.30	24.50	6.80		7.40
8-NAR005.42	7/12/1983	S	.30	26.00	7.00		7.20
8-NAR005.42	11/15/1983	S	.30	7.00	6.50		11.30
8-NAR005.42	12/8/1983	S	.30	8.00	6.00		12.00
8-NAR005.42	2/7/1984	S	.30	3.00	5.90		13.50

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	3/5/1984	S	.30	8.00	5.50		12.00
8-NAR005.42	4/26/1984	S	.30	9.00	5.90		9.90
8-NAR005.42	6/4/1984	S	.30	21.50	6.60		7.70
8-NAR005.42	7/2/1984	S	.30	25.00	6.92		7.70
8-NAR005.42	8/6/1984	S	.30	25.00	5.90		7.60
8-NAR005.42	9/5/1984	S	.30	21.00	6.69		12.40
8-NAR005.42	10/10/1984	S	.30	18.50	6.10		6.20
8-NAR005.42	1/7/1985	S	.30	8.00	6.06		11.10
8-NAR005.42	2/20/1985	S	.30	4.50	5.70		12.00
8-NAR005.42	3/6/1985	S	.30	6.50			12.20
8-NAR005.42	4/3/1985	S	.30	10.00	6.50		11.40
8-NAR005.42	5/7/1985	S	.30	20.00	6.50		9.90
8-NAR005.42	6/17/1985	S	.30	22.70	6.80		7.80
8-NAR005.42	7/9/1985	S	.30	24.00	6.20		8.10
8-NAR005.42	8/27/1985	S	.30	24.00	6.40		7.60
8-NAR005.42	9/24/1985	S	.30	20.90	6.70		8.60
8-NAR005.42	10/22/1985	S	.30	15.70	5.95		1.00
8-NAR005.42	12/2/1985	S	.30	11.00	6.50		11.10
8-NAR005.42	1/7/1986	S	.30	3.00	6.30		13.00
8-NAR005.42	2/4/1986	S	.30	6.00	6.60		11.80
8-NAR005.42	3/4/1986	S	.30	6.00	6.70		12.30
8-NAR005.42	4/1/1986	S	.30	16.00	6.90		10.40
8-NAR005.42	5/5/1986	S	.30	16.00	7.06		8.90
8-NAR005.42	6/12/1986	S	.30	27.00	7.51		7.50
8-NAR005.42	7/1/1986	S	.30	24.00	7.58		7.80
8-NAR005.42	8/12/1986	S	.30	24.00	7.47		7.40
8-NAR005.42	9/11/1986	S	.30	22.00	7.70		8.90
8-NAR005.42	10/15/1986	S	.30	16.50	7.50		8.00
8-NAR005.42	11/6/1986	S	.30	9.00	7.25		10.10
8-NAR005.42	12/8/1986	S	.30	5.00	7.60		11.80
8-NAR005.42	1/15/1987	S	.30	9.00	7.56		11.10
8-NAR005.42	2/10/1987	S	.30	3.70	7.24		12.40
8-NAR005.42	3/9/1987	S	.30	11.00	7.81		10.50
8-NAR005.42	4/27/1987	S	.30	14.50	7.35		10.00
8-NAR005.42	5/13/1987	S	.30	20.50	7.30		8.20
8-NAR005.42	6/10/1987	S	.30	22.80	7.10		6.00
8-NAR005.42	7/22/1987	S	.30	29.00	6.63		4.20
8-NAR005.42	7/22/1987	S	.30	29.00	6.63		4.20
8-NAR005.42	8/6/1987	S	.30	27.40	7.00		7.30
8-NAR005.42	8/6/1987	S	.30	27.40	7.00		7.30
8-NAR005.42	9/14/1987	S	.30	25.00	7.49		7.60
8-NAR005.42	10/13/1987	S	.30	11.50	7.86		10.00
8-NAR005.42	11/18/1987	S	.30	14.00	8.06		10.50
8-NAR005.42	12/22/1987	S	.30	9.00	8.54		11.20
8-NAR005.42	1/12/1988	S	.30	1.00	8.16		15.20
8-NAR005.42	3/28/1988	S	.30	12.10	7.64		10.20
8-NAR005.42	4/27/1988	S	.30	17.50	7.58		9.60
8-NAR005.42	5/10/1988	S	.30	19.00	7.29		8.70
8-NAR005.42	6/6/1988	S	.30	21.00	8.82		8.30
8-NAR005.42	7/6/1988	S	.30	24.50	7.10		8.20
8-NAR005.42	8/23/1988	S	.30	22.80	7.57		7.60

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	9/19/1988	S	.30	22.00	7.28		8.60
8-NAR005.42	10/6/1988	S	.30	14.00	7.25		9.60
8-NAR005.42	12/8/1988	S	.30				
8-NAR005.42	1/25/1989	S	.30	4.90	6.82		14.30
8-NAR005.42	2/16/1989	S	.30	10.20	7.31		11.50
8-NAR005.42	3/9/1989	S	.30				
8-NAR005.42	4/19/1989	S	.30	15.60	7.86		10.80
8-NAR005.42	5/16/1989	S	.30	14.50	7.30		9.60
8-NAR005.42	6/15/1989	S	.30	25.50	7.00		7.60
8-NAR005.42	7/25/1989	S	.30	28.20	7.00		7.20
8-NAR005.42	8/14/1989	S	.30	23.20	7.32		9.20
8-NAR005.42	9/14/1989	S	.30	24.70	6.74		7.00
8-NAR005.42	10/10/1989	S	.30	11.70	7.65		11.40
8-NAR005.42	11/15/1989	S	.30	17.30	7.33		10.20
8-NAR005.42	12/14/1989	S	.30	4.70	7.40		13.30
8-NAR005.42	1/10/1990	S	.30	6.50	7.05		12.60
8-NAR005.42	2/7/1990	S	.30	10.00	7.30		12.50
8-NAR005.42	3/7/1990	S	.30	8.20	7.90		12.70
8-NAR005.42	4/12/1990	S	.30	12.00	7.86		10.70
8-NAR005.42	5/15/1990	S	.30	18.90	6.46		8.70
8-NAR005.42	6/12/1990	S	.30	21.10	7.73		8.20
8-NAR005.42	7/17/1990	S	.30	25.70	7.34		7.20
8-NAR005.42	8/14/1990	S	.30			7.43	
8-NAR005.42	8/14/1990	B	1.00	25.78	6.97	7.43	
8-NAR005.42	9/17/1990	S	.30	20.10	7.36	7.95	8.00
8-NAR005.42	10/15/1990	S	.30	21.20	6.84	7.50	
8-NAR005.42	10/15/1990	B	1.00				
8-NAR005.42	11/28/1990	S	.30	12.60	7.04	10.16	10.20
8-NAR005.42	12/17/1990	S	.09	9.50	7.34	11.75	11.80
8-NAR005.42	1/15/1991	S	.30				
8-NAR005.42	2/5/1991	S	.30				
8-NAR005.42	3/13/1991	S	.09	7.69	7.39	11.53	11.50
8-NAR005.42	3/13/1991	B	304.50	7.70	7.39		11.50
8-NAR005.42	4/10/1991	S	.09	19.75	7.31	8.91	8.91
8-NAR005.42	4/10/1991	B	.30				
8-NAR005.42	5/8/1991	S	.09	19.30	6.95	8.27	8.30
8-NAR005.42	6/5/1991	S	.30	22.09	7.28		7.79
8-NAR005.42	7/1/1991	S	.30	27.49	6.92	7.06	
8-NAR005.42	8/5/1991	S	.30	25.62	6.40	7.11	
8-NAR005.42	9/4/1991	S	.30	21.50	6.83	8.77	
8-NAR005.42	9/30/1991	S	.30	18.17	7.43	8.87	
8-NAR005.42	9/30/1991	S	.30				
8-NAR005.42	12/3/1991	S	.30	11.57	6.67	9.60	
8-NAR005.42	1/6/1992	S	.30	7.03	6.37	11.79	
8-NAR005.42	2/18/1992	S	.30	6.80	6.45	11.88	
8-NAR005.42	3/4/1992	S	.30	10.50	6.60	11.06	
8-NAR005.42	4/13/1992	S	.30	15.90	6.39	10.05	
8-NAR005.42	5/11/1992	S	.30	16.36	6.01	8.87	
8-NAR005.42	6/10/1992	S	.30	22.86	6.66	7.49	
8-NAR005.42	7/7/1992	S	.30	23.37	6.27	6.78	
8-NAR005.42	8/17/1992	S	.30	21.12	6.02	7.89	

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	9/2/1992	S	.30	22.08	6.70	7.86	
8-NAR005.42	10/1/1992	S	.30	14.90	6.53	9.33	
8-NAR005.42	11/3/1992	S	.30	14.67	6.38	11.14	
8-NAR005.42	12/2/1992	S	.30	8.15	6.74	11.20	
8-NAR005.42	1/5/1993	S	.30	10.86	6.41	10.85	
8-NAR005.42	2/1/1993	S	.30	5.82	6.61	11.89	
8-NAR005.42	3/3/1993	S	.30	7.36	6.51	11.55	
8-NAR005.42	4/5/1993	S	.30	11.05	6.38	10.10	
8-NAR005.42	5/4/1993	S	.30	18.58	6.34	8.71	
8-NAR005.42	6/1/1993	S	.30	20.93	6.26	7.89	
8-NAR005.42	7/12/1993	S	.30	28.01	6.44	6.12	
8-NAR005.42	8/9/1993	S	.30	23.28	6.23	7.32	
8-NAR005.42	9/1/1993	S	.30	25.75	6.54	7.30	
8-NAR005.42	10/7/1993	S	.30	14.82	6.89	9.89	
8-NAR005.42	11/2/1993	S	.30	7.89	6.56	11.07	
8-NAR005.42	12/20/1993	S	.30	6.72	6.78	12.03	
8-NAR005.42	1/31/1994	S	.30	4.18	6.60	12.35	
8-NAR005.42	2/10/1994	S	.30	4.99	6.61	12.35	
8-NAR005.42	3/7/1994	S	.30	8.99	6.49	11.63	
8-NAR005.42	4/11/1994	S	.30	15.17	6.47	9.55	
8-NAR005.42	5/11/1994	S	.30	16.64	6.32	9.16	
8-NAR005.42	6/8/1994	S	.30	25.00	6.51	6.81	
8-NAR005.42	7/11/1994	S	.30	26.32	6.55	6.77	
8-NAR005.42	8/3/1994	S	.30	25.62	6.41	6.64	
8-NAR005.42	9/12/1994	S	.30	19.74	6.81	8.17	
8-NAR005.42	10/11/1994	S	.30	14.01	6.65	9.13	
8-NAR005.42	11/1/1994	S	.30	15.69	6.56	8.31	
8-NAR005.42	12/5/1994	S	.30	9.90	6.75	10.65	
8-NAR005.42	1/4/1995	S	.30	4.63	6.72	12.29	
8-NAR005.42	2/1/1995	S	.30	4.69	6.50	12.68	
8-NAR005.42	3/22/1995	S	.30	13.23	6.59	9.37	
8-NAR005.42	4/25/1995	S	.30	13.76	6.91	10.25	
8-NAR005.42	5/24/1995	S	.30	22.13	6.52	7.94	
8-NAR005.42	6/27/1995	S	.30	25.14	6.42	7.41	
8-NAR005.42	7/26/1995	S	.30	28.95	6.72	6.69	
8-NAR005.42	8/31/1995	S	.30	25.15	6.85	7.34	
8-NAR005.42	9/27/1995	S	.30	16.53	6.82	8.54	
8-NAR005.42	10/12/1995	S	.30	16.62	6.65	8.06	
8-NAR005.42	11/8/1995	S	.30	12.54	6.69	10.01	
8-NAR005.42	12/27/1995	S	.30	3.84	6.65	12.78	
8-NAR005.42	1/31/1996	S	.30	6.54	6.13	11.85	
8-NAR005.42	2/27/1996	S	.30	8.34	6.36	10.69	
8-NAR005.42	3/25/1996	S	.30	9.04	6.26	11.42	
8-NAR005.42	4/18/1996	S	.30	13.96	6.56	10.32	
8-NAR005.42	5/30/1996	S	.30	18.14	6.83	9.17	
8-NAR005.42	6/24/1996	S	.30	27.50	6.71	6.86	
8-NAR005.42	7/29/1996	S	.30	25.09	6.84	7.30	
8-NAR005.42	8/26/1996	S	.30	24.52	6.60	6.90	
8-NAR005.42	9/24/1996	S	.30	19.24	6.54	9.81	
8-NAR005.42	10/29/1996	S	.30	16.58	6.46	7.53	
8-NAR005.42	11/25/1996	S	.30	8.04	6.50	11.33	

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	12/19/1996	S	.30	9.39	6.57	10.90	
8-NAR005.42	1/27/1997	S	.30	6.27	6.77	12.22	
8-NAR005.42	2/13/1997	S	.30	6.07	6.80	12.83	
8-NAR005.42	3/17/1997	S	.30	8.57	6.74	11.01	
8-NAR005.42	4/9/1997	S	.30	13.30	6.63	9.76	
8-NAR005.42	5/5/1997	S	.30	16.03	6.67	9.14	
8-NAR005.42	6/2/1997	S	.30	20.21	6.35	7.94	
8-NAR005.42	7/2/1997	S	.30				
8-NAR005.42	8/4/1997	S	.30	25.85	6.72	7.19	
8-NAR005.42	9/25/1997	S	.30	17.86	6.96	9.00	
8-NAR005.42	10/22/1997	S	.30	12.70	7.10	10.45	
8-NAR005.42	11/10/1997	S	.60				
8-NAR005.42	11/12/1997	S	.30	13.64	6.77	9.46	
8-NAR005.42	12/8/1997	S	.30	5.86	6.65	12.08	
8-NAR005.42	1/12/1998	S	.30	8.65	6.61	11.46	
8-NAR005.42	2/12/1998	S	.30	8.69	6.78	11.11	
8-NAR005.42	3/12/1998	S	.30	8.62	6.30	11.57	
8-NAR005.42	4/13/1998	S	.30	14.38	6.64	10.30	
8-NAR005.42	5/5/1998	S	.30	16.69	6.49	8.81	
8-NAR005.42	6/1/1998	S	.30	25.76	6.75	7.24	
8-NAR005.42	7/6/1998	S	.30	26.01	6.66	7.11	
8-NAR005.42	8/19/1998	S	.30	25.25	6.56	7.41	
8-NAR005.42	9/15/1998	S	.30	23.23	6.71	6.84	
8-NAR005.42	10/6/1998	S	.30	17.31	6.68	8.46	
8-NAR005.42	11/3/1998	S	.30	11.68	6.50	9.57	
8-NAR005.42	12/14/1998	S	.30	6.98	6.35	11.08	
8-NAR005.42	1/12/1999	S	.30	1.88	6.12	13.52	
8-NAR005.42	2/9/1999	S	.30	5.68	6.46	11.97	
8-NAR005.42	3/16/1999	S	.30	9.10	6.17	11.60	
8-NAR005.42	4/19/1999	S	.30	12.70	6.70	9.88	
8-NAR005.42	5/19/1999	S	.30	20.28	6.48	8.08	
8-NAR005.42	6/22/1999	S	.30	20.95	6.83	8.35	
8-NAR005.42	7/1/1999	S	.30	24.89	6.84	6.64	
8-NAR005.42	8/3/1999	S	.30	25.75	6.83	6.76	
8-NAR005.42	9/1/1999	S	.30	20.21	6.93	8.66	
8-NAR005.42	10/18/1999	S	.30	15.88	6.54	9.01	
8-NAR005.42	11/2/1999	S	.30	14.58	6.28	8.75	
8-NAR005.42	12/28/1999	S	.30	3.71	6.71	13.17	
8-NAR005.42	1/5/2000	S	.30	9.81	6.79	10.38	
8-NAR005.42	2/3/2000	S	.30	3.11	6.54	14.70	
8-NAR005.42	3/1/2000	S	.30	10.80	7.07	10.95	
8-NAR005.42	4/12/2000	S	.30	15.66	6.84	8.90	
8-NAR005.42	5/3/2000	S	.30	17.86	6.93	8.93	
8-NAR005.42	6/7/2000	S	.30	19.10	6.56	7.85	
8-NAR005.42	7/6/2000	S	.30	26.18	6.70	6.66	
8-NAR005.42	8/8/2000	S	.30	26.80	6.58	6.17	
8-NAR005.42	9/12/2000	S	.30	22.74	6.75	6.58	
8-NAR005.42	10/16/2000	S	.30	13.89	6.81	9.33	
8-NAR005.42	11/13/2000	S	.30	9.64	6.79	9.77	
8-NAR005.42	12/27/2000	S	.30				
8-NAR005.42	1/16/2001	S	.30	4.13	6.70	12.53	

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	1/31/2001	S	.30	7.65	6.89	11.76	
8-NAR005.42	3/12/2001	S	.30	9.04	6.79	11.15	
8-NAR005.42	4/25/2001	S	.30	18.40	6.84	7.57	
8-NAR005.42	6/11/2001	S	.30	23.25	6.51	7.85	
8-NAR005.42	8/8/2001	S	.30	29.30	7.20	7.92	
8-NAR005.42	10/4/2001	S	.30	18.52	7.00	9.11	
8-NAR005.42	12/27/2001	S	.30	.91	6.11	13.57	
8-NAR005.42	2/5/2002	S	.30	3.36	6.54	12.97	
8-NAR005.42	4/3/2002	S	.30	18.96	6.97	9.51	
8-NAR005.42	6/26/2002	S	.30	28.66	7.80		
8-NAR005.42	7/24/2002	S	.30	26.25	6.65	4.98	
8-NAR005.42	9/19/2002	S	.00				
8-NAR005.42	9/19/2002	S	.30				
8-NAR005.42	11/13/2002	S	.30	13.00	6.37	10.83	
8-NAR005.42	1/2/2003	S	.30	7.84	6.59	11.34	
8-NAR005.42	3/11/2003	S	.30	6.75	7.04	11.90	
8-NAR005.42	5/21/2003	S	.30	18.61	6.60	8.75	
8-NAR005.42	7/10/2003	S	.30	26.91	6.79	6.87	
8-NAR005.42	9/16/2003	S	.30	22.41	6.94	7.65	
8-NAR005.42	11/13/2003	S	.30	15.66	6.94	8.69	
8-NAR005.42	1/21/2004	S	.30	3.69	7.17	12.94	
8-NAR005.42	4/19/2004	S	.30	19.47	6.79	9.18	
8-NAR005.42	5/13/2004	S	.30	23.27	6.86	7.94	
8-NAR005.42	7/13/2004	S	.30	27.15	6.56	6.52	
8-NAR005.42	8/12/2004	S	.30	26.26	6.71	7.31	
8-NAR005.42	9/16/2004	S	.30	24.08	6.90	7.72	
8-NAR005.42	10/5/2004	S	.30	19.65	6.55	9.19	
8-NAR005.42	12/1/2004	S	.30	12.38	7.39	12.42	
8-NAR005.42	12/21/2004	S	.30	3.66	8.64	13.14	
8-NAR005.42	1/19/2005	S	.30	5.13	6.94	13.47	
8-NAR005.42	2/8/2005	S	.30	7.78	6.34	11.65	
8-NAR005.42	3/17/2005	S	.30	8.77	6.38	10.90	
8-NAR005.42	4/21/2005	S	.30	19.30	6.72	8.65	
8-NAR005.42	5/31/2005	S	.30	21.15	7.10	6.42	
8-NAR005.42	6/6/2005	S	.30	24.39	6.39	6.54	
8-NAR005.42	8/3/2005	S	.30	26.97	6.92	6.33	
8-NAR005.42	8/17/2005	S	.30	26.11	6.82	6.54	
8-NAR005.42	9/26/2005	S	.30	22.72	7.04	7.10	
8-NAR005.42	10/13/2005	S	.30	18.02	7.00	8.44	
8-NAR005.42	11/7/2005	S	.30	13.70	6.45	8.72	
8-NAR005.42	12/8/2005	S	.30	5.98	7.20		
8-NAR005.42	1/30/2006	S	.30	8.44	6.59	11.20	
8-NAR005.42	2/28/2006	S	.30	6.67	6.94	12.40	
8-NAR005.42	3/23/2006	S	.30	9.70	7.20	11.50	
8-NAR005.42	4/25/2006	S	.30	18.50	7.40	8.60	
8-NAR005.42	6/28/2006	S	.30	23.10	6.80	7.80	
8-NAR005.42	8/16/2006	S	.30	26.30	7.30	7.50	
8-NAR005.42	8/22/2006	S	.30				
8-NAR005.42	10/16/2006	S	.30	14.80	7.30	9.80	
8-NAR005.42	12/5/2006	S	.30	7.60	6.90	11.40	
8-NAR005.42	1/4/2007	S	.30	9.80	6.80	11.50	



Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	3/8/2007	S	.30	7.30	6.20	11.20	
8-NAR005.42	3/20/2007	I	.00	10.30	6.40	10.30	
8-NAR005.42	4/11/2007	I	.00	10.40	6.70	10.60	
8-NAR005.42	4/16/2007	I	.00	11.90	6.60	10.20	
8-NAR005.42	5/8/2007	S	.30	15.60	6.80	8.80	
8-NAR005.42	5/16/2007	I	.00	21.30	6.90	7.90	
8-NAR005.42	5/30/2007	I	.00	23.00	6.80	7.20	
8-NAR005.42	6/28/2007	I	.00	28.40	7.00	7.00	
8-NAR005.42	7/9/2007	I	.00	27.10	6.90	7.40	
8-NAR005.42	7/12/2007	S	.30	30.30	5.50	4.80	
8-NAR005.42	8/6/2007	I	.00	26.40	7.10	6.50	
8-NAR005.42	9/5/2007	I	.00	22.50	7.00	7.90	
8-NAR005.42	9/11/2007	S	.30	26.20	7.20	7.40	
8-NAR005.42	10/9/2007	I	.00				
8-NAR005.42	10/9/2007	I	.00	23.40	7.40	10.00	
8-NAR005.42	10/25/2007	I	.00	16.80	6.60	7.70	
8-NAR005.42	10/29/2007	I	.00	12.10	6.80	9.70	
8-NAR005.42	11/5/2007	I	.00	10.90	6.90	10.50	
8-NAR005.42	11/5/2007	I	.00				
8-NAR005.42	11/7/2007	I	.00				
8-NAR005.42	11/26/2007	I	.00	8.00	6.90	10.60	
8-NAR005.42	11/27/2007	S	.30	12.10	6.70	10.60	
8-NAR005.42	1/7/2008	S	.30	7.10	6.30	12.00	
8-NAR005.42	1/10/2008	I	.00	7.20	7.10	11.80	
8-NAR005.42	1/29/2008	I	.00	2.60	7.10	13.20	
8-NAR005.42	1/29/2008	I	.00				
8-NAR005.42	2/3/2008	I	.00	4.20	7.00	11.90	
8-NAR005.42	2/26/2008	I	.00	7.10	7.20	12.60	
8-NAR005.42	3/4/2008	S	.30	12.50	6.50	11.80	
8-NAR005.42	3/6/2008	I	.00	11.20	6.90	11.20	
8-NAR005.42	3/9/2008	I	.00	7.90	6.90	11.20	
8-NAR005.42	3/12/2008	I	.00	8.40	6.80	12.00	
8-NAR005.42	3/27/2008	I	.00	13.60	7.00	10.50	
<b>90th Percentile</b>				<b>26.2</b>	<b>7.4</b>		
<b>10th Percentile</b>				<b>5.5</b>	<b>6.4</b>		

00900

HARDNESS, TOTAL  
(MG/L AS CaCO3)

Sta Id	Collection Date Time	Depth Desc	Depth	Container	Comment	Value	Com Code
8-NAR005.42	01/25/1989 13:20	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	02/16/1989 13:10	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	03/09/1989 13:00	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	04/19/1989 13:30	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	05/16/1989 13:00	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	06/15/1989 13:50	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	08/14/1989 14:15	S 0.3	R		STORET DATA CONVERSION	20	
8-NAR005.42	09/14/1989 14:00	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	10/10/1989 13:30	S 0.3	R		STORET DATA CONVERSION	24	
8-NAR005.42	11/15/1989 13:15	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	12/14/1989 13:35	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	01/10/1990 12:45	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	02/07/1990 13:20	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	03/07/1990 12:30	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	04/12/1990 13:20	S 0.3	R		STORET DATA CONVERSION	30	
8-NAR005.42	05/15/1990 12:15	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	06/12/1990 12:50	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	07/17/1990 12:55	S 0.3	R		STORET DATA CONVERSION	22	
8-NAR005.42	09/17/1990 12:00	S 0.3	R		STORET DATA CONVERSION	26	
8-NAR005.42	10/15/1990 12:10	S 0.3	R		STORET DATA CONVERSION		
8-NAR005.42	11/28/1990 11:30	S 0.3	R		STORET DATA CONVERSION	26	
8-NAR005.42	12/17/1990 12:30	S 0.09	R		STORET DATA CONVERSION	22	
8-NAR005.42	01/15/1991 13:15	S 0.3	R		STORET DATA CONVERSION	24	
8-NAR005.42	02/05/1991 10:45	S 0.3	R		STORET DATA CONVERSION	20	
8-NAR005.42	03/13/1991 11:46	B 304.5	R		STORET DATA CONVERSION	22	
8-NAR005.42		S 0.09	R		STORET DATA CONVERSION	22	
8-NAR005.42	04/10/1991 13:20	S 0.09	R		STORET DATA CONVERSION	40	
8-NAR005.42	05/08/1991 10:25	S 0.09	R		STORET DATA CONVERSION	46	
8-NAR005.42	06/05/1991 13:20	S 0.3	R		STORET DATA CONVERSION	26	
8-NAR005.42	08/05/1991 10:52	S 0.3	R		STORET DATA CONVERSION	34	
8-NAR005.42	09/04/1991 11:40	S 0.3	R		STORET DATA CONVERSION	34	
8-NAR005.42	12/03/1991 11:31	S 0.3	R		STORET DATA CONVERSION	26	
8-NAR005.42	01/06/1992 11:20	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	02/18/1992 10:00	S 0.3	R		STORET DATA CONVERSION	24	
8-NAR005.42	03/04/1992 11:10	S 0.3	R		STORET DATA CONVERSION	24	
8-NAR005.42	04/13/1992 12:30	S 0.3	R		STORET DATA CONVERSION	20	
8-NAR005.42	05/11/1992 09:20	S 0.3	R		STORET DATA CONVERSION	26	
8-NAR005.42	06/10/1992 10:25	S 0.3	R		STORET DATA CONVERSION	32	
8-NAR005.42	07/07/1992 10:49	S 0.3	R		STORET DATA CONVERSION	28	
8-NAR005.42	08/17/1992 10:34	S 0.3	R		STORET DATA CONVERSION	22	
8-NAR005.42	09/02/1992 10:56	S 0.3	R		STORET DATA CONVERSION	2.6	
8-NAR005.42	10/01/1992 11:37	S 0.3	R		STORET DATA CONVERSION	43	
8-NAR005.42	11/03/1992 11:20	S 0.3	R		STORET DATA CONVERSION	34	
8-NAR005.42	12/02/1992 11:00	S 0.3	R		STORET DATA CONVERSION	19	
8-NAR005.42	01/05/1993 11:38	S 0.3	R		STORET DATA CONVERSION	21	
8-NAR005.42	02/01/1993 10:17	S 0.3	R		STORET DATA CONVERSION	28	
8-NAR005.42	03/03/1993 11:33	S 0.3	R		STORET DATA CONVERSION	24	
8-NAR005.42	04/05/1993 10:30	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	05/04/1993 09:30	S 0.3	R		STORET DATA CONVERSION	20	
8-NAR005.42	06/01/1993 11:35	S 0.3	R		STORET DATA CONVERSION	21	
8-NAR005.42	07/12/1993 11:00	S 0.3	R		STORET DATA CONVERSION	24	
8-NAR005.42	08/09/1993 10:30	S 0.3	R		STORET DATA CONVERSION	20	
8-NAR005.42	09/01/1993 11:10	S 0.3	R		STORET DATA CONVERSION	18	
8-NAR005.42	10/07/1993 12:22	S 0.3	R		STORET DATA CONVERSION	26	
8-NAR005.42	11/02/1993 10:15	S 0.3	R		STORET DATA CONVERSION	38	
8-NAR005.42	12/20/1993 12:41	S 0.3	R		STORET DATA CONVERSION	20	
8-NAR005.42	01/31/1994 11:25	S 0.3	R		STORET DATA CONVERSION	14	
8-NAR005.42	02/10/1994 10:55	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	03/07/1994 12:44	S 0.3	R		STORET DATA CONVERSION	14	
8-NAR005.42	04/11/1994 12:34	S 0.3	R		STORET DATA CONVERSION	15	
8-NAR005.42	05/11/1994 11:00	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	06/08/1994 10:47	S 0.3	R		STORET DATA CONVERSION	16	
8-NAR005.42	07/11/1994 11:00	S 0.3	R		STORET DATA CONVERSION	17	

00900

**HARDNESS, TOTAL**  
**(MG/L AS CaCO3)**

Sta Id	Collection Date Time	Depth Desc	Depth	Container	Comment	Value	Com Code
8-NAR005.42	08/03/1994 12:11	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	09/12/1994 13:00	S	0.3	R	STORET DATA CONVERSION	26	
8-NAR005.42	10/11/1994 12:00	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	11/01/1994 11:00	S	0.3	R	STORET DATA CONVERSION	19	
8-NAR005.42	12/05/1994 10:00	S	0.3	R	STORET DATA CONVERSION	19	
8-NAR005.42	01/04/1995 12:22	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	02/01/1995 11:21	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	03/22/1995 09:14	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	04/25/1995 13:20	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	05/24/1995 12:30	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	06/27/1995 08:00	S	0.3	R	STORET DATA CONVERSION	15	
8-NAR005.42	07/26/1995 11:35	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	08/31/1995 11:40	S	0.3	R	STORET DATA CONVERSION	25	
8-NAR005.42	09/27/1995 11:00	S	0.3	R	STORET DATA CONVERSION	13	
8-NAR005.42	10/12/1995 10:45	S	0.3	R	STORET DATA CONVERSION	23	
8-NAR005.42	11/08/1995 10:00	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	12/27/1995 10:00	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	01/31/1996 12:05	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	02/27/1996 10:20	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	03/25/1996 09:45	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	04/18/1996 12:30	S	0.3	R	STORET DATA CONVERSION	13	
8-NAR005.42	05/30/1996 11:30	S	0.3	R	STORET DATA CONVERSION	30	
8-NAR005.42	06/24/1996 09:00	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	07/29/1996 10:30	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	08/26/1996 08:45	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	09/24/1996 07:37	S	0.3	R	STORET DATA CONVERSION	21	
8-NAR005.42	10/29/1996 12:50	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	11/25/1996 10:00	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	12/19/1996 11:11	S	0.3	R	STORET DATA CONVERSION	15	
8-NAR005.42	01/27/1997 13:22	S	0.3	R	STORET DATA CONVERSION	15.6	
8-NAR005.42	02/13/1997 09:54	S	0.3	R	STORET DATA CONVERSION	16.9	
8-NAR005.42	03/17/1997 07:55	S	0.3	R	STORET DATA CONVERSION	18.5	
8-NAR005.42	04/09/1997 11:11	S	0.3	R	STORET DATA CONVERSION	20.7	
8-NAR005.42	05/05/1997 11:44	S	0.3	R	STORET DATA CONVERSION	20.7	
8-NAR005.42	06/02/1997 10:31	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	07/02/1997 11:55	S	0.3	R	STORET DATA CONVERSION	15.7	
8-NAR005.42	08/04/1997 11:44	S	0.3	R	STORET DATA CONVERSION	19.8	
8-NAR005.42	09/25/1997 15:23	S	0.3	R	STORET DATA CONVERSION	19.1	
8-NAR005.42	10/22/1997 11:30	S	0.3	R	STORET DATA CONVERSION	16.4	
8-NAR005.42	11/12/1997 12:55	S	0.3	R	STORET DATA CONVERSION	13.3	
8-NAR005.42	12/08/1997 12:33	S	0.3	R	STORET DATA CONVERSION	21	
8-NAR005.42	01/12/1998 14:15	S	0.3	R	STORET DATA CONVERSION	48	
8-NAR005.42	02/12/1998 11:01	S	0.3	R	STORET DATA CONVERSION	13.8	
8-NAR005.42	03/12/1998 13:00	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	04/13/1998 12:40	S	0.3	R	STORET DATA CONVERSION	13.1	
8-NAR005.42	05/05/1998 11:50	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	06/01/1998 14:22	S	0.3	R	STORET DATA CONVERSION	19.6	
8-NAR005.42	07/06/1998 12:15	S	0.3	R	STORET DATA CONVERSION	13.8	
8-NAR005.42	08/19/1998 11:45	S	0.3	R	STORET DATA CONVERSION	13.7	
8-NAR005.42	09/15/1998 09:30	S	0.3	R	STORET DATA CONVERSION	11.8	
8-NAR005.42	10/06/1998 10:22	S	0.3	R	STORET DATA CONVERSION	10.7	
8-NAR005.42	11/03/1998 11:44	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	12/14/1998 10:33	S	0.3	R	STORET DATA CONVERSION	19	
8-NAR005.42	01/12/1999 10:33	S	0.3	R		44	
8-NAR005.42	02/09/1999 11:11	S	0.3	R		26	
8-NAR005.42	03/16/1999 12:15	S	0.3	R		36	
8-NAR005.42	04/19/1999 10:55	S	0.3	R		18	
8-NAR005.42	05/19/1999 13:35	S	0.3	R		20	
8-NAR005.42	06/22/1999 14:00	S	0.3	R		13.3	
8-NAR005.42	07/01/1999 11:44	S	0.3	R		12.5	
8-NAR005.42	08/03/1999 10:31	S	0.3	R		14.3	
8-NAR005.42	09/01/1999 12:00	S	0.3	R		9.8	
8-NAR005.42	11/02/1999 12:30	S	0.3	R		18.3	

00900

HARDNESS, TOTAL  
(MG/L AS CaCO3)

Sta Id	Collection Date Time	Depth Desc	Depth	Container	Comment	Value	Com Code
8-NAR005.42	12/28/1999 14:40	S	0.3	R		18.9	
8-NAR005.42	01/05/2000 15:20	S	0.3	R		25.5	
8-NAR005.42	02/03/2000 12:00	S	0.3	R		18.2	
8-NAR005.42	03/01/2000 13:00	S	0.3	R		13	
8-NAR005.42	04/12/2000 11:45	S	0.3	R		13	
8-NAR005.42	05/03/2000 12:30	S	0.3	R		15	
8-NAR005.42	06/07/2000 10:45	S	0.3	R		16	
8-NAR005.42	07/06/2000 10:40	S	0.3	R		16.3	
8-NAR005.42	08/08/2000 10:20	S	0.3	R	NORMAL FLOW	16.6	
8-NAR005.42	09/12/2000 10:30	S	0.3	R		17.5	
8-NAR005.42	10/16/2000 10:30	S	0.3	R	NORMAL FLOW	17.7	
8-NAR005.42	11/13/2000 10:30	S	0.3	R		16	
8-NAR005.42	01/16/2001 12:00	S	0.3	R		14.6	
8-NAR005.42	01/31/2001 13:00	S	0.3	R		17.2	
8-NAR005.42	03/12/2001 12:10	S	0.3	R		14.5	
8-NAR005.42	04/25/2001 12:05	S	0.3	R		5.7	
8-NAR005.42	06/11/2001 12:45	S	0.3	R		7.1	
8-NAR005.42	08/08/2001 16:00	S	0.3	R	LOW FLOW	16.3	
8-NAR005.42	10/04/2001 14:30	S	0.3	R	LOW FLOW	17.5	
8-NAR005.42	12/27/2001 11:00	S	0.3	R	BELOW NORMAL FLOW	7.2	
8-NAR005.42	02/05/2002 13:20	S	0.3	R	LOW FLOW	12.9	
8-NAR005.42	04/03/2002 13:00	S	0.3	R	NORMAL FLOW	18	
8-NAR005.42	06/26/2002 14:15	S	0.3	R	LOW FLOW	15	
8-NAR005.42	07/24/2002 11:40	S	0.3	R		44.5	
8-NAR005.42	11/13/2002 14:10	S	0.3	R		22.8	
8-NAR005.42	01/02/2003 14:10	S	0.3	R	ABOVE NORMAL FLOW	15.5	
8-NAR005.42	03/11/2003 10:45	S	0.3	R	NORMAL FLOW	20.3	
8-NAR005.42	07/10/2003 13:00	S	0.3	R	NORMAL FLOW	21.4	
8-NAR005.42	09/16/2003 13:20	S	0.3	R	NORMAL FLOW	17.7	
8-NAR005.42	11/13/2003 15:25	S	0.3	R	NORMAL FLOW.	16	
8-NAR005.42	01/21/2004 13:10	S	0.3	R	NORMAL FLOW; COMPLETELY FRI	19	
8-NAR005.42	04/19/2004 13:30	S	0.3	R		19.1	
8-NAR005.42	05/13/2004 12:15	S	0.3	R		16	
8-NAR005.42	07/13/2004 10:40	S	0.3	R	NORMAL FLOW.	18.5	
8-NAR005.42	08/12/2004 14:00	S	0.3	R	NORMAL FLOW; PH POST CALIBR/	17.5	
8-NAR005.42	09/16/2004 14:00	S	0.3	R	NORMAL FLOW.	14.7	
8-NAR005.42	10/05/2004 12:50	S	0.3	R		18.2	
8-NAR005.42	12/01/2004 10:40	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	12/21/2004 13:40	S	0.3	R		16	
8-NAR005.42	01/19/2005 10:40	S	0.3	R	ABOVE NORMAL FLOW.	15	
8-NAR005.42	02/08/2005 12:55	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	03/17/2005 11:00	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	04/21/2005 12:45	S	0.3	R		20.8	
8-NAR005.42	05/31/2005 11:20	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	06/06/2005 12:15	S	0.3	R	NORMAL FLOW	20	
8-NAR005.42	08/03/2005 11:10	S	0.3	R	LOW FLOW	20	
8-NAR005.42	08/17/2005 10:30	S	0.3	R	NORMAL FLOW	18	
8-NAR005.42	09/26/2005 12:20	S	0.3	R	LOW FLOW	18	
8-NAR005.42	10/13/2005 11:40	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	11/07/2005 11:05	S	0.3	R	NORMAL FLOW	18	
8-NAR005.42	12/08/2005 12:33	S	0.3	R	NORMAL FLOW	20	
8-NAR005.42	01/30/2006 11:00	S	0.3	R	NORMAL FLOW.	15	
8-NAR005.42	02/28/2006 12:54	S	0.3	R	BELOW NORMAL FLOW	15	
8-NAR005.42	03/23/2006 12:03	S	0.3	R	LOW FLOW	18	
8-NAR005.42	04/25/2006 12:10	S	0.3	R	NORMAL FLOW	15	
8-NAR005.42	06/28/2006 10:25	S	0.3	R	FLOOD STAGE	20	
8-NAR005.42	08/16/2006 12:30	S	0.3	R	VERY LOW FLOW	16	
8-NAR005.42	10/16/2006 14:00	S	0.3	R	NORMAL FLOW	18	
8-NAR005.42	12/05/2006 12:10	S	0.3	R	NORMAL FLOW	17	
8-NAR005.42	01/04/2007 14:30	S	0.3	R	ABOVE NORMAL FLOW.	15	
Mean						19.4	


#### **Attachment 4**

## MEMORANDUM

DEPARTMENT OF ENVIRONMENTAL QUALITY  
Piedmont Regional Office  
4949-A Cox Road Glen Allen, Virginia 23060

**SUBJECT:** Flow Frequency Determination / 303(d) Status  
Doswell WWTF – VA0029521

**TO:** Ray Jenkins

**FROM:** Jennifer V. Palmore, P.G. 

**DATE:** April 7, 2008

**COPIES:** File

The Hanover County Doswell Wastewater Treatment Facility discharges to the North Anna River at the confluence of the Little River downstream of Hart Corner, VA. The river mile for the discharge is 8-NAR003.55. Flow frequencies have been requested at this site for use in developing effluent limitations for the VPDES permit.

Previous flow frequencies were derived by using the flow frequencies for the gauge at the North Anna River at Hart Corner near Doswell, VA (#01671020), which is located at the Route 30 bridge approximately 2 miles upstream of the discharge, and then subtracting out the flow removed by several water withdrawals located between the gauge and the discharge. At the request of Hanover County, the USGS has installed a gauge on the North Anna directly upstream of the discharge (North Anna River at Little River, VA #01671025); the gauge has been in operation since July 2004. The flow measurements for the two gauges were correlated and were plotted on a logarithmic graph and a best fit power trend line was plotted through the data points.

Due to influence from the Lake Anna dam, only the period of record after 1979 was used to calculate the flow frequencies at the Route 30 gauge. The flow frequencies from the reference gage were plugged into the equation for the regression line to calculate the associated flow frequencies at the discharge point. The flow frequencies for the gauges are presented below. The regression analysis is attached.

**North Anna River at Hart Corner near Doswell, VA (#01671020):**

Drainage Area = 463 mi<sup>2</sup>

Statistical period = 1979-2003

High Flow Months = Jan - May

1Q30 = 35 cfs

High Flow 1Q10 = 49 cfs

1Q10 = 36 cfs

High Flow 7Q10 = 52 cfs

7Q10 = 39 cfs

High Flow 30Q10 = 75 cfs

30Q10 = 42 cfs

HM = 111 cfs

30Q5 = 44 cfs

**North Anna River at Little River (#01671025):**


Drainage area = 467 mi<sup>2</sup>

1Q30 = 41 cfs (26 MGD)	High Flow 1Q10 = 56 cfs (36 MGD)
1Q10 = 42 cfs (27 MGD)	High Flow 7Q10 = 60 cfs (39 MGD)
7Q10 = 45 cfs (29 MGD)	High Flow 30Q10 = 86 cfs (56 MGD)
30Q10 = 49 cfs (32 MGD)	HM = 126 cfs (81 MGD)
30Q5 = 51 cfs (33 MGD)	

The North Anna River at the discharge point was assessed as a Category 1 water during the 2006 305(b)/303(d) cycle. The river was considered fully supporting of all of its designated uses – Aquatic Life Use, Recreation, Fish Consumption, and Wildlife Use.

If you have any questions concerning this analysis, please let me know.

North Anna at Little River #01671025  
vs North Anna River at Hart Corner near Doswell, VA #01671020



SUMMARY OUTPUT

Regression Statistics	
Multiple R	0.975703111
R Square	0.951996561
Adjusted R Square	0.951961213
Standard Error	92.6009299
Observations	1360

Flow Frequencies (cfs)

@ Hart Corner	@ Little River
35	41
36	42
39	45
42	49
44	51
49	56
52	60
75	86
111	126
463	467
DA ( mi <sup>2</sup> )	
HF Months: Jan-May	
Period: 1979-2003	



## **Attachment 5**

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY**

**Wastewater Facility Inspection Report**

Revised 08/2001

<b>Facility Name:</b>	<u>Doswell WWTP</u>	<b>Facility No.:</b>	<u>VA0029521</u>
<b>City/County:</b>	<u>Hanover</u>	<b>Inspection Agency:</b>	<u>DEQ - PRO</u>
<b>Inspection Date:</b>	<u>September 20, 2007</u>	<b>Date Form Completed:</b>	<u>September 21, 2007</u>
<b>Inspector:</b>	<u>Mike Dare</u> <i>Handwritten: 9.21-08</i>	<b>Time Spent:</b>	<u>8 hrs. w/ travel &amp; report</u>
<b>Reviewed By:</b>	<i>Handwritten: M. Dare 9/21/07</i>	<b>Unannounced Insp.?</b>	<u>No</u>
		<b>FY-Scheduled Insp.?</b>	<u>Yes</u>

**Present at Inspection:** Barbara Mitchell, Gary Proffit

**TYPE OF FACILITY:**

Domestic

Industrial

☐ Federal

☒ Major

☐ Major

☐ Primary

☒ Non-Federal

☐ Minor

☐ Minor

☐ Secondary

Population Served: approx.: Varies seasonally with the operation of Kings Dominion

Number of Connections: approx.: 8 – the amusement park, Bear Island Paper Co. sanitary sewer & local businesses

**TYPE OF INSPECTION:**

☒ Routine

Date of last inspection: January 27 & 31, 2005

☐ Compliance

Agency: DEQ/PRO

☐ Reinspection

**INFLUENT and EFFLUENT MONITORING:**

**Please refer to the DMR file for Data**

Last month average:

BOD: \_\_\_\_ mg/L

TSS: \_\_\_\_ mg/L

Flow: \_\_\_\_ MGD

(Influent) Date:

Other: \_\_\_\_ mg/L

Last month:

CBOD: \_\_\_\_ mg/L

TSS: \_\_\_\_ mg/L

Flow: \_\_\_\_ MGD

(Effluent) Date:

Other:

Quarter average:

CBOD: \_\_\_\_ mg/L

TSS: \_\_\_\_ mg/L

Flow: \_\_\_\_ MGD

(Effluent) Date:

Other:

**CHANGES AND/OR CONSTRUCTION**

DATA VERIFIED IN PREFACE

☐ Updated

☒ No changes

Has there been any new construction?

☐ Yes\*

☒ No

If yes, were plans and specifications approved?

☐ Yes

☐ No\*

☒ N/A

DEQ approval date:

N/A

**(A) PLANT OPERATION AND MAINTENANCE**

1. Class and number of licensed operators: Class I – 4; Class II – 1
2. Hours per day plant is staffed: 13.5 hours/day, 7 days/week
3. Describe adequacy of staffing: ☐ Good ☐ Average ☒ Poor\*
4. Does the plant have an established program for training personnel? ☒ Yes ☐ No
5. Describe the adequacy of the training program: ☒ Good ☐ Average ☐ Poor\*
6. Are preventive maintenance tasks scheduled? ☒ Yes ☐ No\*
7. Describe the adequacy of maintenance: ☐ Good ☒ Average ☐ Poor\*
8. Does the plant experience any organic/hydraulic overloading? ☐ Yes\* ☒ No

If yes, identify cause and impact on plant: Two 0.5 MG Equalization Basins limit impact of surges.

9. Any bypassing since last inspection? ☐ Yes\* ☒ No
10. Is the on-site electric generator operational? ☒ Yes ☐ No\* ☐ N/A
11. Is the STP alarm system operational? ☒ Yes ☐ No \* ☐ N/A
12. How often is the standby generator exercised? ☒ Weekly ☐ Monthly ☐ Other:  
     Power Transfer Switch? ☒ Weekly ☐ Monthly ☐ Other:  
     Alarm System? ☒ Weekly ☐ Monthly ☐ Other:
13. When were the cross connection control devices last tested on the potable water service? All four tested 10/3/06
14. Is sludge disposed in accordance with the approved sludge disposal plan? ☒ Yes ☐ No\* ☐ N/A
15. Is septage received by the facility? ☐ Yes ☒ No  
     Is septage loading controlled? ☐ Yes ☐ No \* ☒ N/A  
     Are records maintained? ☐ Yes ☐ No\* ☒ N/A
16. Overall appearance of facility: ☐ Good ☒ Average ☐ Poor\*

**Comments: #1, 2 & 3) In 2000 the plant hours of operation were reduced from 24 hrs/day to 13.5 hrs/day, and the staffing was reduced, however the workload and tasks required to operate the plant did not change. The County Maintenance crew is now being called in to perform routine maintenance tasks. #4 The training program includes unit by unit OJT with the "Doswell WWTP Training Guide", VA Rural Water Assoc. training, Licensing Prep classes at John Tyler and DEQ Lab Workshops. #14 The approved plan calls for landfill disposal.**

**(B) PLANT RECORDS**

1. Which of the following records does the plant maintain?
- |   |   |                              |   |
|---|---|------------------------------|---|
| Operational Logs for each unit process                        | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A            |
| Instrument maintenance and calibration                        | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A            |
| Mechanical equipment maintenance                              | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A            |
| Industrial waste contribution ( <b>Municipal Facilities</b> ) | <input type="checkbox"/> Yes            | <input type="checkbox"/> No* | <input checked="" type="checkbox"/> N/A |
2. What does the operational log contain?
- |                      |   |                              |                              |
|----------------------|---|------------------------------|------------------------------|
| Visual Observations  | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No  | <input type="checkbox"/> N/A |
| Flow Measurement     | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No  | <input type="checkbox"/> N/A |
| Laboratory Results   | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No  | <input type="checkbox"/> N/A |
| Process Adjustments  | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| Control Calculations | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No  | <input type="checkbox"/> N/A |
| Other:               |   |                              |                              |
3. What do the mechanical equipment records contain:
- |                             |   |                              |                              |
|-----------------------------|---|------------------------------|------------------------------|
| As built plans and specs?   | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| Spare parts inventory?      | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| Manufacturers instructions? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| Equipment/parts suppliers?  | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| Lubrication schedules?      | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| Other:                      |   |                              |                              |
| Comments:                   | <u>None</u>                             |                              |                              |
4. What do the industrial waste contribution records contain:
- (Applicable to municipal facilities only)*
- |                                |                              |                              |   |
|--------------------------------|------------------------------|------------------------------|---|
| Waste characteristics?         | <input type="checkbox"/> Yes | <input type="checkbox"/> No* | <input checked="" type="checkbox"/> N/A |
| Locations and discharge types? | <input type="checkbox"/> Yes | <input type="checkbox"/> No* | <input checked="" type="checkbox"/> N/A |
| Impact on plant?               | <input type="checkbox"/> Yes | <input type="checkbox"/> No* | <input checked="" type="checkbox"/> N/A |
| Other:                         | <u>N/A</u>                   |                              |   |
| Comments:                      | <u>None</u>                  |                              |   |
5. Are the following records maintained at the plant:
- |                                |   |                              |   |
|--------------------------------|---|------------------------------|---|
| Equipment maintenance records  | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A            |
| Operational Log                | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A            |
| Industrial contributor records | <input type="checkbox"/> Yes            | <input type="checkbox"/> No* | <input checked="" type="checkbox"/> N/A |
| Instrumentation records        | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A            |
| Sampling and testing records   | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A            |
6. Are records maintained at a different location?
- Where are the records maintained?
- ☐ Yes      ☒ No
- All are available on site, except some original P&S that are kept at the Courthouse**
7. Were the records reviewed during the inspection?
- ☒ Yes      ☐ No
8. Are the records adequate and the O & M Manual current?
- O&M Manual date written: **February 1999, upgrade Submitted August 2003**
- Date DEQ approved O&M **VDH approval 8/18/99;**
9. Are the records maintained for required 3-year period?
- ☒ Yes      ☐ No\*

**Comments: #1. - A single operational log is kept for the entire plant. Log includes notes for various treatment units, observations, equipment adjustments and control tests. #2. - Lab records are separate from operational log.**

**(C) SAMPLING**

- |  |   |                              |                              |
|--|---|------------------------------|------------------------------|
| 1. Are sampling locations capable of providing representative samples? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 2. Do sample types correspond to those required by the permit?         | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 3. Do sampling frequencies correspond to those required by the permit? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 4. Are composite samples collected in proportion to flow?              | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 5. Are composite samples refrigerated during collection?               | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 6. Does plant maintain required records of sampling?                   | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 7. Does plant run operational control tests?                           | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |

**Comments:** Please see attached operational control data.

**(D) TESTING**

1. Who performs the testing? ☒ Plant/ Lab: BOD, TSS, pH, D.O.  
☐ Central Lab  
☒ Commercial Lab - Name: EnviroCompliance – Nutrients, Microbac – Fecals, Totopotomy WWTP Lab – Ortho/Total P

*If plant performs any testing, complete 2-4.*

2. What method is used for chlorine analysis? N/A – UV disinfection
- |   |   |                              |                              |
|---|---|------------------------------|------------------------------|
| 3. Is sufficient equipment available to perform required tests? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 4. Does testing equipment appear to be clean and/or operable?   | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |

**Comments:** Please see enclosed DEQ Laboratory Inspection Report.

**(E) FOR INDUSTRIAL FACILITIES W/ TECHNOLOGY BASED LIMITS N/A**

1. Is the production process as described in the permit application? (If no, describe changes in comments)  
☐ Yes      ☐ No\*      ☒ N/A
2. Do products and production rates correspond to the permit application? (If no, list differences in comments section)  
☐ Yes      ☐ No\*      ☒ N/A
3. Has the State been notified of the changes and their impact on plant effluent?  
☐ Yes      ☐ No\*      ☒ N/A

**Comments:** None

**FOLLOW UP TO COMPLIANCE RECOMMENDATIONS FROM THE January 27 & 31, 2005 DEQ INSPECTION:**

1. There were no Compliance Recommendations.

**FOLLOW UP TO GENERAL RECOMMENDATIONS FROM THE January 27 & 31, 2005 DEQ INSPECTION:**

1. The intensity sensor on the UV light system is malfunctioning; always indicating low intensity, even with new bulbs. The manufacturer has not been able to resolve the problem. Currently bulb cleaning is scheduled for every other week. Based on fecal coliform monitoring, this frequency of cleaning is adequate to maintain sufficient intensity for disinfection. Discussing this matter with your DEQ Permit Writer, Ray Jenkins, is recommended. ***One bank of bulbs is cleaned each week, or sooner if fecal results spike. This procedure reportedly approved by Mr. Jenkins.***
2. Repair the aerator from the East EQ basin as soon as practical. The East basin was offline and currently not needed; generally only one of the 0.5 MG basins is required. ***Aerator has been repaired.***
3. Pump station debris is being applied to drying beds. In addition to raw sewage, which carries pathogens and attracts rodents, the solids removed from the pumping stations often contain a lot of grease which may clog the drainage system. The County staff should look at other options for providing a suitable receiving station for the vac-trucks. ***Most pump station debris now going to Totopotomoy WWTP for dewatering and disposal.***

**INSPECTION REPORT SUMMARY****Compliance Recommendations/Request for Corrective Action:**

1. There are no compliance recommendations.

**General Recommendations and Observations:**

There are no General Recommendations.

Items evaluated during this inspection include (check all that apply):

<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No		Operational Units
<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No		O & M Manual
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No		Maintenance Records
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A	Pathogen Reduction & Vector Attraction Reduction
<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A	Sludge Disposal Plan
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A	Groundwater Monitoring Plan
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A	Storm Water Pollution Prevention Plan
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	Permit Special Conditions
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	Permit Water Quality Chemical Monitoring
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	Laboratory Records (see Lab Report)

**DEPARTMENT OF ENVIRONMENTAL QUALITY - WATER DIVISION  
LABORATORY INSPECTION REPORT**

10/01

<b>FACILITY NO:</b> VA0029521	<b>INSPECTION DATE:</b> September 20, 2007	<b>PREVIOUS INSP. DATE:</b> <u>January 27, 2005</u>	<b>PREVIOUS EVALUATION:</b> Deficiencies	<b>TIME SPENT:</b> 8 hours w/ travel & report
<b>NAME/ADDRESS OF FACILITY:</b>  Doswell Wastewater Treatment Plant P.O. Box 470 Hanover, VA 23069	<b>FACILITY CLASS:</b>  (X) MAJOR ( ) MINOR ( ) SMALL ( ) VPA/NDC	<b>FACILITY TYPE:</b>  (X) MUNICIPAL ( ) INDUSTRIAL ( ) FEDERAL ( ) COMMERCIAL LAB	<b>UNANNOUNCED INSPECTION?</b> ( ) YES (x) NO	
			<b>FY-SCHEDULED INSPECTION?</b> (X) YES ( ) NO	
<b>INSPECTOR(S):</b> Mike Dare <i>M. Dare 9-21-07</i>		<b>REVIEWERS:</b> <i>CMW and JPH/07</i>	<b>PRESENT AT INSPECTION:</b> Barbara Mitchell	

LABORATORY EVALUATION	DEFICIENCIES?	
	Yes	No
LABORATORY RECORDS		x
GENERAL SAMPLING & ANALYSIS		x
LABORATORY EQUIPMENT		x
DISSOLVED OXYGEN ANALYSIS PROCEDURES		x
pH ANALYSIS PROCEDURES		x
BIOCHEMICAL OXYGEN DEMAND ANALYSIS PROCEDURES	x	
TOTAL SUSPENDED SOLIDS ANALYSIS PROCEDURES		x

**QUALITY ASSURANCE/QUALITY CONTROL**

Y/N	QUALITY ASSURANCE METHOD	PARAMETERS	FREQUENCY
Y	REPLICATE SAMPLES	BOD samples, Blanks, Seed Dilutions and TSS samples	Each weekly
	SPIKED SAMPLES		
Y	STANDARD SAMPLES	BOD - GGA	Weekly
	SPLIT SAMPLES		
Y	SAMPLE BLANKS	BOD	each series
	OTHER		
Y	EPA-DMR QA DATA?	RATING: (X) No Deficiency ( ) Deficiency ( ) NA <b>Study 26</b>	
	QC SAMPLES PROVIDED?	RATING: ( ) No Deficiency ( ) Deficiency (X) NA	

COPIES TO: (X) DEQ - RO; (X) OWPP; ( ) VDH- DWE; (X) OWNER; (X) EPA-Region III; ( ) Other:

**LABORATORY RECORDS SECTION**

LABORATORY RECORDS INCLUDE THE FOLLOWING:

<input checked="" type="checkbox"/>	SAMPLING DATE	<input checked="" type="checkbox"/>	ANALYSIS DATE	<input checked="" type="checkbox"/>	CONT MONITORING CHART
<input checked="" type="checkbox"/>	SAMPLING TIME	<input checked="" type="checkbox"/>	ANALYSIS TIME	<input checked="" type="checkbox"/>	INSTRUMENT CALIBRATION
<input checked="" type="checkbox"/>	SAMPLE LOCATION	<input checked="" type="checkbox"/>	TEST METHOD	<input checked="" type="checkbox"/>	INSTRUMENT MAINTENANCE
				<input checked="" type="checkbox"/>	CERTIFICATE OF ANALYSIS

WRITTEN INSTRUCTIONS INCLUDE THE FOLLOWING:

<input checked="" type="checkbox"/>	SAMPLING SCHEDULES	<input checked="" type="checkbox"/>	CALCULATIONS	<input checked="" type="checkbox"/>	ANALYSIS PROCEDURES
-------------------------------------	--------------------	-------------------------------------	--------------	-------------------------------------	---------------------

	YES	NO	N/A
DO ALL ANALYSTS INITIAL THEIR WORK?	X		
DO BENCH SHEETS INCLUDE ALL INFORMATION NECESSARY TO DETERMINE RESULTS?	X		
IS THE DMR COMPLETE AND CORRECT? MONTH(S) REVIEWED: <i>August 2007</i>	X		
ARE ALL MONITORING VALUES REQUIRED BY THE PERMIT REPORTED?	X		

**GENERAL SAMPLING AND ANALYSIS SECTION**

	YES	NO	N/A
ARE SAMPLE LOCATION(S) ACCORDING TO PERMIT REQUIREMENTS?	X		
ARE SAMPLE COLLECTION PROCEDURES APPROPRIATE?	X		
IS SAMPLE EQUIPMENT CONDITION ADEQUATE?	X		
IS FLOW MEASUREMENT ACCORDING TO PERMIT REQUIREMENTS?	X		
ARE COMPOSITE SAMPLES REPRESENTATIVE OF FLOW?	X		
ARE SAMPLE HOLDING TIMES AND PRESERVATION ADEQUATE?	X		
IF ANALYSIS IS PERFORMED AT ANOTHER LOCATION, ARE SHIPPING PROCEDURES ADEQUATE? LIST PARAMETERS AND NAME & ADDRESS OF LAB: <i>Ammonia, TKN, Nitrate, Nitrite - EnviroCompliance Laboratories, Inc, Glen Allen, VA; Fecals - Microbac, Richmond, VA; Ortho/Total P - Totopotomy WWTP Lab.</i>	X		

**LABORATORY EQUIPMENT SECTION**

	YES	NO	N/A
IS LABORATORY EQUIPMENT IN PROPER OPERATING RANGE?	X		
ARE ANNUAL THERMOMETER CALIBRATION(S) ADEQUATE?	X		
IS THE LABORATORY GRADE WATER SUPPLY ADEQUATE?			X
ARE ANALYTICAL BALANCE(S) ADEQUATE?	X		



# LABORATORY INSPECTION REPORT SUMMARY

<b>FACILITY NAME:</b> Doswell WWTP	<b>FACILITY NO:</b> VA0029521	<b>INSPECTION DATE:</b> September 20, 2007
<b>LABORATORY EVALUATION:</b>	(X) Deficiencies ( ) No Deficiencies	
<b>LABORATORY RECORDS</b>		
No Deficiencies – As allowed by the permit, Ms. Mitchell will begin including DMR data for any incomplete calendar week at months end in the following monthly reporting period.		
<b>GENERAL SAMPLING AND ANALYSIS</b>		
No Deficiencies		
<b>LABORATORY EQUIPMENT</b>		
No Deficiencies		
<b>INDIVIDUAL PARAMETERS</b>		
<p>pH, Dissolved Oxygen, and Total Suspended Solids Analysis Procedures: No deficiencies</p> <p><u>Biochemical Oxygen Demand Analysis Procedures:</u></p> <p>1. Two of five seed corrections for period 7/29/07 to 8/2/07 are &gt;1.0 mg/L. Data not flagged. Flag on bench sheet and DMR.</p>		

## **Attachment 6**

Subsections this Attachment are identified as 6A, 6B, and 6C

**Attachment 6A** presents the results of water quality criteria monitoring on Outfall 001

**Attachment 6B** presents Discharge Monitoring Report (DMR) data for Outfall 001

**Attachment 6C** presents DMR data for Outfalls 101 and 102

**Attachment 6A**

Results of water quality criteria monitoring on Outfall 001

## Attachment 6A

Items in bold face are considered to be present in the discharge and require evaluation. See Attachment 7 of this fact sheet. Dioxin was not tested at the required QL and is also addressed in Attachment 7.

	Required QL (µg/L)	February 28, 2007	May 23, 2007	July 25, 2007
Parameter				
<b>METALS (µg/L)</b>				
Antimony, dissolved	18000	<100	<100	<100
Arsenic, dissolved	210	<60	<60	<60
Cadmium, dissolved	3.1	<0.50	<0.50	<0.50
Chromium, dissolved	---	<10	<10	<10
Chromium III, dissolved	570			<10
Chromium VI, dissolved	9.2			<5.0
Copper, dissolved	30	6	<5	<5
Lead, dissolved <sup>(A)</sup>	44	<20	<20	30
Mercury, dissolved	1.0	<0.1	<0.1	<0.1
Nickel, dissolved	57	<10	<10	<10
Selenium, dissolved	10.0	<2	<2	<2
Silver, dissolved	11.0	<5	<5	<5
Thallium, dissolved	(B)	<40	<40	<40
Zinc, dissolved <sup>(A)</sup>	180	108	101	134
<b>PESTICIDES / PCBs (µg/L)</b>				
Aldrin	0.05			<0.05
Chlordane	0.2			<0.20
Chlorpyrifos	(B)			<0.10
DDD	0.1			<0.05
DDE	0.1			<0.05
DDT	0.1			<0.05
Demeton	(B)			<0.10
Dieldrin	0.1			<0.05
Alpha-Endosulfan	0.1			<0.05
Beta-Endosulfan	0.1			<0.05
Endosulfan sulfate	0.1			<0.05
Endrin	0.1			<0.05
Endrin Aldehyde	(B)			<0.05
Guthion	(B)			<0.10
Heptachlor	0.05			<0.05
Heptachlor Epoxide	(B)			<0.05
Alpha-BHC	(B)			<0.05
Beta-BHC	(B)			<0.05
Gamma-BHC or Lindane	0.05			<0.05
Kepone	(B)			<0.40
Malathion	(B)			<0.10
Methoxychlor	(B)			<0.05
Mirex	(B)			<0.05
Parathion	(B)			<0.10
PCB 1260	1.0			<1
PCB 1254	1.0			<1
PBC 1248	1.0			<1
PCB 1242	1.0			<1
PCB 1232	1.0			<1
PCB 1221	1.0			<1
PCB 1016	1.0			<1
PCB Total	7.0			<7
Toxaphene	5.0			<5.0
<b>BASE NEUTRALS (µg/L)</b>				
Acenaphthene	10.0	<10.0	<10.0	<10.0
Anthracene	10.0	<10.0	<10.0	<10.0
Benzidine	(B)	<10.0	<10.0	<10.0
Benzo (a) anthracene	10.0	<10.0	<10.0	<10.0
Benzo (b) fluoranthene	10.0	<10.0	<10.0	<10.0
Benzo (k) fluoranthene	10.0	<10.0	<10.0	<10.0
Benzo (a) pyrene	10.0	<10.0	<10.0	<10.0
Bis 2-Chloroethyl Ether	(B)	<10.0	<10.0	<10.0
Bis 2-Chloroisopropyl Ether	(B)	<10.0	<10.0	<10.0
Butyl benzyl phthalate	10.0	<10.0	<10.0	<10.0
2-Chloronaphthalene	(B)	<10.0	<10.0	<10.0
Chrysene	10.0	<10.0	<10.0	<10.0

	Required QL (µg/L)	February 28, 2007	May 23, 2007	July 25, 2007
Parameter				
Dibenz(a,h)anthracene	20.0	<10.0	<10.0	<10.0
Dibutyl phthalate	10.0	<10.0	<10.0	<10.0
1,2- Dichlorobenzene	10.0	<10.0		
1,3- Dichlorobenzene	10.0	<10.0		
1,4- Dichlorobenzene	10.0	<10.0		
3,3-Dichlorobenzidine	(B)	<10.0	<10.0	<10.0
Diethyl phthalate	10.0	<10.0	<10.0	<10.0
Di-2-Ethylhexyl Phthalate	10.0	<10.0	<10.0	<10.0
Dimethyl phthalate	(B)	<10.0	<10.0	<10.0
2,4-Dinitrotoluene	10.0	<10.0	<10.0	<10.0
1,2-Diphenylhydrazine	(B)	<10.0	<10.0	<10.0
Fluoranthene	10.0	<10.0	<10.0	<10.0
Fluorene	10.0	<10.0	<10.0	<10.0
Hexachlorobenzene	(B)	<10.0	<10.0	<10.0
Hexachlorobutadiene	(B)	<10.0	<10.0	<10.0
Hexachlorocyclopentadiene	(B)	<10.0	<10.0	<10.0
Hexachloroethane	(B)	<10.0	<10.0	<10.0
Indeno (1,2,3-cd) pyrene	20.0	<10.0	<10.0	<10.0
Isophorone	10.0	<10.0	<10.0	<10.0
Nitrobenzene	10.0	<10.0	<10.0	<10.0
N-Nitrosodimethylamine	(B)	<10.0	<10.0	<10.0
N-Nitrosodi-n-propylamine	(B)	<10.0	<10.0	<10.0
N-Nitrosodiphenylamine	(B)	<10.0	<10.0	<10.0
Pyrene	10.0	<10.0	<10.0	<10.0
1,2,4-Trichlorobenzene	10.0	<10.0	<10.0	<10.0
VOLATILES (µg/L)				
Acrolein	(B)	<10.0	<10.0	<10.0
Acrylonitrile	(B)	<10.0	<10.0	<10.0
Benzene	10.0	<10.0	<10.0	<10.0
Bromoform	10.0	<10.0	<10.0	<10.0
Carbon Tetrachloride	10.0	<10.0	<10.0	<10.0
Chlorobenzene	(B)	<10.0	<10.0	<10.0
Chlorodibromomethane	10.0	<10.0	<10.0	<10.0
Chloroform	10.0	<10.0	<10.0	<10.0
Dichloromethane	20.0	<10.0	<10.0	<10.0
Dichlorobromomethane	20.0	<10.0	<10.0	<10.0
1,2-Dichloroethane	10.0	<10.0	<10.0	<10.0
1,1-Dichloroethylene	10.0	<10.0	<10.0	<10.0
1,2-trans-dichloroethylene	(B)	<10.0	<10.0	<10.0
1,2-Dichloropropane	(B)	<10.0	<10.0	<10.0
1,3-Dichloropropene	(B)	<20.0	<20.0	<20.0
Ethylbenzene	10.0	<10.0	<10.0	<10.0
Methyl bromide	(B)	<10.0	<10.0	<10.0
1,1,2,2-Tetrachloroethane	(B)	<10.0	<10.0	<10.0
Tetrachloroethylene	10.0	<10.0	<10.0	<10.0
Toluene	10.0	<10.0	<10.0	<10.0
1,1,2-Trichloroethane	(B)	<10.0	<10.0	<10.0
Trichloroethylene	10.0	<10.0	<10.0	<10.0
Vinyl chloride	10.0	<10.0	<10.0	<10.0
RADIONUCLIDES				
Strontium 90 (pCi/L)	(B)	Sampling for radionuclides will be required by special condition in the permit to be reissued.		
Tritium (pCi/L)	(B)			
Beta Particle & Photon Activity (mrem/yr)	(B)			
Gross Alpha Particle Activity (pCi/L)	(B)			
ACIDS (µg/L)				
2-Chlorophenol	10.0	<10.0	<10.0	<10.0
2,4 Dichlorophenol	10.0	<10.0	<10.0	<10.0
2,4- Dimethylphenol	10.0	<10.0	<10.0	<10.0
2,4-Dinitrophenol	(B)	<20.0	<20.0	<10.0
2-Methyl-4,6-Dinitrophenol	(B)	<10.0	<20.0	<10.0
Pentachlorophenol	50.0	<10.0	<20.0	<10.0
Phenol	10.0	<10.0	<10.0	<10.0
2,4,6-Trichlorophenol	10.0	<10.0	<10.0	<10.0
MISCELLANEOUS (µg/L unless otherwise noted)				
Chlorides, mg/L	(B)			29

	Required QL (µg/L)	February 28, 2007	May 23, 2007	July 25, 2007
Parameter				
Total Residual Chlorine	100	See footnote (C) below		
Cyanide, Total <sup>(D)</sup>	10.0	11	10	<10
Dioxin	0.00001			<0.0000101
Hardness, mg/L	(B)	586	581	521
Hydrogen sulfide	(B)			<300 sulfide
Tributyltin	(B)			<0.030
Xylenes total	6.0			<6.00

(A) Additional Data:	Dissolved Lead	Dissolved Zinc
October 11, 2007	<20	218
October 12, 2007	<20	173
October 17, 2007	<20	98
October 18, 2007	<20	113
October 24, 2007	<20	110
October 25, 2007	<20	104
October 31, 2007	<20	109
December 19, 2007	---	204

(B) Any approved method in 40 CFR Part 136 if the parameter is addressed in 40 CFR Part 136.

(C) In March 2007, TRC concentrations of 0.19 mg/L, 0.41 mg/L, and 0.48 mg/L were determined in conjunction with WET testing on Outfall 001. These data are not considered representative of Outfall 001 as neither the Doswell treatment plant nor Bear Island use chlorine compounds. These results are thought to be due to test interferences.

(D) Additional Data from cyanide study. These data were used to modify the permit in October 2006 to remove cyanide limitations that were added to the permit at reissuance in May 2003.

March 1, 2004	7.64
March 8, 2004	10.1
March 15, 2004	10.1
March 22, 2004	15.3
March 31, 2004	9.52
April 5, 2004	13.2
April 12, 2004	14.8
April 19, 2004	8.20
April 26, 2004	8.20
May 3, 2004	11.1
May 10, 2004	10.4
May 17, 2004	8.2
May 24, 2004	16.9
January 3, 2005	<6
April 4, 2005	18.8
July 11, 2005	9.77
October 10, 2005	11.2

**Attachment 6B**

Discharge Monitoring Report (DMR) data for Outfall 001

Attachment 6B														
Outfall 001 Effluent Data														
Outfall 001 Effluent Data from Discharge Monitoring Reports														
Sample frequency is once per day unless otherwise noted.														
Date	BOD <sub>5</sub> , mg/L		TSS, mg/L (3/W)		D.O., mg/L		TKN, mg/L (3/W)		Temperature, °F		pH, Standard Units		Ammonia, mg/L (1/M) Monthly Average	
	Reported	Limitation	Reported	Limitation	Minimum	Weekly Average	Minimum	Average	Maximum	Minimum	Maximum			
Monthly Averages														
2005														
	July	8.3	40.9	17.6	47.0	6.7	7.50	80.6	86.3	93.2	7.3	7.8	3.30	
	August	15.8	43.7	23.3	46.5	6.5	10.48	82.4	87.3	91.4	7.4	7.8	0.40	
	September	6.7	43.5	17.0	47.8	6.6	4.92	73.4	84.6	89.6	7.5	7.9	0.60	
	October	5.0	48.2	14.5	48.2	7.4	4.24	68.0	77.9	87.8	7.3	7.7	0.30	
	November	6.0	49.2	16.8	49.2	7.8	4.79	64.4	72.0	80.6	7.2	7.8	0.60	
December	10.5	49.5	19.1	49.4	8.1	2.74	60.8	66.8	78.8	7.1	7.6	<0.20		
2006														
	January	5.5	49.1	15.0	49.1	7.7	3.62	59.0	67.6	80.6	7.0	7.7	1.36	
	February	9.2	49.2	15.1	49.2	8.2	2.98	60.8	70.2	77.0	7.1	7.6	<0.20	
	March	7.0	49.3	15.4	49.4	7.4	5.72	66.2	71.6	80.6	7.2	7.9	<0.20	
	April	7.9	48.9	15.6	48.9	6.8	7.90	60.8	75.0	84.2	7.1	7.8	1.10	
	May	4.2	48.9	6.2	48.9	6.9	3.14	64.4	80.7	87.8	7.2	7.8	0.29	
	June	10.1	48.6	15.4	48.6	6.5	4.53	78.8	87.1	95.0	7.1	7.8	<0.20	
	July	11.8	47.7	13.4	47.8	6.5	4.05	84.6	89.8	93.2	7.1	7.7	0.20	
	August	12.4	47.8	16.8	47.8	6.5	4.34	84.2	91.9	96.8	7.3	7.6	0.50	
	September	10.6	48.5	16.9	48.6	6.6	3.74	75.2	84.8	95.0	7.0	7.9	<0.20	
	October	7.2	48.9	13.4	49.0	6.5	4.52	68.0	77.3	84.2	7.3	7.9	2.00	
	November	8.9	48.9	20.9	48.9	6.5	4.42	60.8	70.9	80.6	7.1	7.9	1.50	
	December	8.7	49.5	17.3	49.5	6.6	3.14	66.2	74.5	82.4	7.2	7.8	0.40	
	2007													
		January	3.8	49.3	12.1	49.4	6.5	2.39	55.4	68.8	80.6	7.0	7.7	0.30
		February	10.5	49.5	26.0	49.5	7.9	2.29	53.6	69.0	75.2	7.3	7.8	<0.20
		March	7.1	49.2	18.2	49.3	7.7	3.76	57.2	70.3	82.4	7.3	7.9	<0.20
		April	2.2	49.0	8.7	49.0	7.0	3.30	60.8	76.2	84.2	7.2	7.9	<0.20
May		5.9	49.0	8.0	49.1	6.9	2.59	78.8	83.8	91.4	7.4	7.8	0.40	
June		12.4	48.3	15.5	48.5	6.9	3.55	80.6	86.2	91.4	7.1	7.8	0.20	
July		4.4	47.7	15.3	47.7	7.1	2.56	78.8	85.7	89.6	7.3	7.8	0.40	
August		3.8	47.8	12.9	47.9	6.7	4.21	80.6	86.9	89.6	7.6	7.9	<0.20	
September		9.3	48.8	13.6	48.8	6.9	3.61	80.6	85.6	89.6	7.4	7.7	<0.20	
October	3.3	48.5	10.3	48.6	6.8	5.37	71.6	78.2	84.2	7.4	7.8	1.40		



[illegible]

**Attachment 6C**

DMR data for Outfalls 101 and 102

Attachment 6C				
Date	Outfall 101		Outfall 201	
	BOD <sub>5</sub> , mg/L (5/W)	TSS, mg/L (3/W)	BOD <sub>5</sub> , mg/L (5/W)	TSS, mg/L (3/W)
Monthly Averages				
2005				
July	4.5	9.2	8.6	18.2
August	3.6	10.3	11.1	22.4
September	2.8	14.0	7.7	16.2
October	0.5	8.2	5.6	15.6
November	2.3	6.5	7.0	19.0
December	2.3	17.1	9.1	23.0
2006				
January	1.5	17.8	6.1	15.9
February	0.8	14.3	9.6	14.1
March	4.3	13.1	5.3	14.1
April	7.4	11.6	7.5	15.4
May	6.0	9.9	3.3	6.6
June	4.4	11.3	8.7	16.2
July	5.1	12.6	11.5	14.4
August	6.4	17.7	12.4	15.6
September	2.6	12.4	10.6	16.6
October	1.6	10.4	6.9	15.1
November	4.3	12.3	9.4	21.3
December	1.0	13.9	8.7	18.5
2007				
January	1.1	16.8	3.5	12.1
February	1.9	12.2	9.2	21.1
March	0.2	10.1	7.2	16.5
April	6.4	10.0	1.7	8.1
May	4.4	8.1	4.8	7.1
June	4.3	13.0	12.7	17.9
July	7.5	16.8	3.5	11.5
August	0.6	6.6	4.3	15.6
September	3.0	11.4	9.8	15.2
October	1.1	9.1	2.9	10.5
November	5.2	23.1	2.6	9.5
December	4.7	22.3	8.2	27.7
2008				
January	4.8	20.5	7.5	20.5
February	1.9	12.0	9.6	25.8
March	3.8	12.6	9.1	20.5
April	3.5	12.4	8.5	19.9
May	3.7	9.8	8.0	25.4
June	4.6	10.1	7.1	14.2
Average	3.4	12.8	7.5	16.6
Maximum	7.5	23.1	12.7	27.7
Minimum	0.2	6.5	1.7	6.6
Limitation	30	30	50	50
% of actual average versus limitation	11.3	42.7	15.0	33.2

Baseline monitoring	1 / Day	1 / Day	1 / Day	1 / Day
Allowable reduction in monitoring frequency:				
	1 / Week	3 / Week	1 / Week	3 / Week

## **Attachment 7**

Effluent Limitation Development

## Attachment 7

The data summarized in the following table were provided in the permit renewal application. The data are summarized in Attachment 6A.

If data were reported at less than a quantification level (QL) equal to or less than the required QL, the parameter was considered absent for the purpose of this evaluation. All uncensored values (that is, not a "less than" value) were evaluated in regard to the need for a water quality based effluent limitation. The parameters requiring evaluation, which are indicated in bold type in the following table are ammonia (see Attachment 6B for effluent ammonia data), copper, lead, zinc, chloride, chlorine, and cyanide.

Included in this attachment are:

- a. "Mixing Zone Predictions...". This analysis uses statistical flows and basic information about the receiving stream to predict mixing patterns in-stream.

These pages (and others) are identified in the first line as either "existing" or "expansion". The "existing" condition uses an effluent flow of 5.8 MGD. The "expansion" condition uses an effluent flow of 6.34 MGD.

- b. Spreadsheets titled "Water Quality Standards and Wasteload Allocations" (also known as MSTRANTI). These spreadsheets calculate the water quality standards and wasteload allocations given inputs for effluent and stream flow, pH, temperature, and hardness, and other stream characteristics. See Attachment 3 for stream data.
- c. Calculation sheets ("STATS") that present a reasonable potential analysis of the listed data to determine if a water quality based effluent limitation is needed. The wasteload allocations from MSTRANTI are used in these analyses.
- d. The following table shows a comparison of reported data to applicable human health wasteload allocations. No limitations are required to protect human health.

Parameter	Outfall 001	
	Expected Value*	WLA <sub>hh</sub> **
Cyanide (µg/L)	10.5	1,300,000
Dissolved Zinc (µg/L)	133.9	430,000
Dioxin*** (ppq)	10.1	49

\* See STATS printouts in this attachment.

\*\* Taken from the MSTRANTI spreadsheet for the expansion flow (see Attachment 14), which is conservative for the existing condition.

\*\*\* The required QL for the dioxin testing was 10 ppq. Dioxin was reported as < 10.1 ppq. Dioxin is associated with the production of Kraft paper using chlorine. Bear Island is not a Kraft mill and no Kraft paper is presently used at the mill (although Special Condition 12 acknowledges that up to 10% purchased Kraft could be imported). The reported result of < 10.1 ppq is therefore, a reasonable indication that dioxin can be considered absent in this effluent. As presented in the table above however, if dioxin was present at a concentration of 10.1 ppq, a limitation would not be needed. Note that the dioxin standard applies at the mean annual stream flow. The annual mean for Water Years 1980 through 2007 is 387 cfs (250 MGD). The above  $WLA_{HH}$  was obtained using the MSTRANTI spreadsheet with an effluent flow of 6.34 MGD and stream flow of 250 MGD.

## Mixing Zone Predictions for

Doswell WWTP existing

Effluent Flow = 5.8 MGD  
Stream 7Q10 = 29 MGD  
Stream 30Q10 = 32 MGD  
Stream 1Q10 = 27 MGD  
Stream slope = 0.00038 ft/ft  
Stream width = 75 ft  
Bottom scale = 2  
Channel scale = 1

---

### Mixing Zone Predictions @ 7Q10

Depth = 1.5301 ft  
Length = 5044.68 ft  
Velocity = .4694 ft/sec  
Residence Time = .1244 days

#### Recommendation:

A complete mix assumption is appropriate for this situation and the entire 7Q10 may be used.

---

### Mixing Zone Predictions @ 30Q10

Depth = 1.6092 ft  
Length = 4830.64 ft  
Velocity = .4848 ft/sec  
Residence Time = .1153 days

#### Recommendation:

A complete mix assumption is appropriate for this situation and the entire 30Q10 may be used.

---

### Mixing Zone Predictions @ 1Q10

Depth = 1.4758 ft  
Length = 5203.82 ft  
Velocity = .4587 ft/sec  
Residence Time = 3.1514 hours

#### Recommendation:

A complete mix assumption is appropriate for this situation providing no more than 31.73% of the 1Q10 is used.

---



## FRESHWATER

Doswell WWTP existing

North Anna River

Version: OWP Guidance Memo 00-2011 (8/24/00)

Stream Information		Stream Flows		Mixing Information		Effluent Information	
Mean Hardness (as CaCO <sub>3</sub> ) =	19.4 mg/L	1Q10 (Annual) =	27 MGD	Annual - 1Q10 Mix =	31.7% %	Mean Hardness (as CaCO <sub>3</sub> ) =	562 mg/L
90% Temperature (Annual) =	26.2 deg C	7Q10 (Annual) =	29 MGD	- 7Q10 Mix =	100 %	90% Temp (Annual) =	30.6 deg C
90% Temperature (Wet season) =	deg C	3Q10 (Annual) =	32 MGD	- 3Q10 Mix =	100 %	90% Temp (Wet season) =	deg C
90% Maximum pH =	7.4 SU	1Q10 (Wet season) =	0 MGD	Wet Season - 1Q10 Mix =	%	90% Maximum pH =	7.9 SU
10% Maximum pH =	6.4 SU	3Q10 (Wet season)	0 MGD	- 3Q10 Mix =	%	10% Maximum pH =	7.7 SU
Tier Designation (1 or 2) =	1	3Q05 =	33 MGD			Discharge Flow =	5.8 MGD
Public Water Supply (PWS) Y/N? =	n	Harmonic Mean =	81 MGD				
Trout Present Y/N? =	n	Annual Average =	MGD				
Early Life Stages Present Y/N? =	y						

Parameter (ug/l unless noted)	Background Conc.	Water Quality Criteria				Wasteload Allocations				Antidegradation Baseline				Antidegradation Allocations				Most Limiting Allocations			
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH
Acenaphthene	0	--	--	na	2.7E+03	--	--	na	1.8E+04	--	--	--	--	--	--	--	--	--	--	na	1.8E+04
Acrolein	0	--	--	na	7.8E+02	--	--	na	5.2E+03	--	--	--	--	--	--	--	--	--	--	na	5.2E+03
Acrylonitrile <sup>c</sup>	0	--	--	na	6.6E+00	--	--	na	9.9E+01	--	--	--	--	--	--	--	--	--	--	na	9.9E+01
Aldrin <sup>c</sup>	0	3.0E+00	--	na	1.4E-03	7.4E+00	--	na	2.1E-02	--	--	--	--	--	--	--	--	7.4E+00	--	na	2.1E-02
Ammonia-N (mg/l) (Yearly)	0	1.87E+01	2.06E+00	na	--	4.6E+01	1.3E+01	na	--	--	--	--	--	--	--	--	--	4.6E+01	1.3E+01	na	--
Ammonia-N (mg/l) (high Flow)	0	1.01E+01	2.80E+00	na	--	1.0E+01	2.8E+00	na	--	--	--	--	--	--	--	--	--	1.0E+01	2.8E+00	na	--
Anthracene	0	--	--	na	1.1E+05	--	--	na	7.4E+05	--	--	--	--	--	--	--	--	--	--	na	7.4E+05
Antimony	0	--	--	na	4.3E+03	--	--	na	2.9E+04	--	--	--	--	--	--	--	--	--	--	na	2.9E+04
Arsenic	0	3.4E+02	1.5E+02	na	--	8.4E+02	9.0E+02	na	--	--	--	--	--	--	--	--	--	8.4E+02	9.0E+02	na	--
Barium	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	--	--	--	--	na	--
Benzene <sup>c</sup>	0	--	--	na	7.1E+02	--	--	na	1.1E+04	--	--	--	--	--	--	--	--	--	--	na	1.1E+04
Benzidine <sup>c</sup>	0	--	--	na	5.4E-03	--	--	na	8.1E-02	--	--	--	--	--	--	--	--	--	--	na	8.1E-02
Benzo (a) anthracene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	--	--	--	--	na	7.3E+00
Benzo (b) fluoranthene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	--	--	--	--	na	7.3E+00
Benzo (k) fluoranthene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	--	--	--	--	na	7.3E+00
Benzo (a) pyrene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	--	--	--	--	na	7.3E+00
Bis(2-Chloroethyl) Ether	0	--	--	na	1.4E+01	--	--	na	9.4E+01	--	--	--	--	--	--	--	--	--	--	na	9.4E+01
Bis(2-Chloroisopropyl) Ether	0	--	--	na	1.7E+05	--	--	na	1.1E+08	--	--	--	--	--	--	--	--	--	--	na	1.1E+08
Bromoform <sup>c</sup>	0	--	--	na	3.6E+03	--	--	na	5.4E+04	--	--	--	--	--	--	--	--	--	--	na	5.4E+04
Butylbenzylphthalate	0	--	--	na	5.2E+03	--	--	na	3.5E+04	--	--	--	--	--	--	--	--	--	--	na	3.5E+04
Cadmium	0	1.0E+01	1.2E+00	na	--	2.6E+01	7.3E+00	na	--	--	--	--	--	--	--	--	--	2.6E+01	7.3E+00	na	--
Carbon Tetrachloride <sup>c</sup>	0	--	--	na	4.4E+01	--	--	na	6.6E+02	--	--	--	--	--	--	--	--	--	--	na	6.6E+02
Chlordane <sup>c</sup>	0	2.4E+00	4.3E-03	na	2.2E-02	5.9E+00	2.6E-02	na	3.3E-01	--	--	--	--	--	--	--	--	5.9E+00	2.6E-02	na	3.3E-01
Chloride	0	8.6E+05	2.3E+05	na	--	2.1E+06	1.4E+06	na	--	--	--	--	--	--	--	--	--	2.1E+06	1.4E+06	na	--
TRC	0	1.9E+01	1.1E+01	na	--	4.7E+01	6.6E+01	na	--	--	--	--	--	--	--	--	--	4.7E+01	6.6E+01	na	--
Chlorobenzene	0	--	--	na	2.1E+04	--	--	na	1.4E+05	--	--	--	--	--	--	--	--	--	--	na	1.4E+05

Parameter (ug/l unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Chlorobromomethane <sup>c</sup>	0	--	--	na	3.4E+02	--	--	na	5.1E+03	--	--	--	--	--	--	na
Chloroform <sup>c</sup>	0	--	--	na	2.9E+04	--	--	na	4.3E+05	--	--	--	--	--	--	na
2-Chloronaphthalene	0	--	--	na	4.3E+03	--	--	na	2.9E+04	--	--	--	--	--	--	na
2-Chlorophenol	0	--	--	na	4.0E+02	--	--	na	2.7E+03	--	--	--	--	--	--	na
Chlorpyrifos	0	8.3E-02	4.1E-02	na	--	2.1E-01	2.5E-01	na	--	--	--	--	--	2.1E-01	2.5E-01	na
Chromium III	0	1.2E+03	8.0E+01	na	--	2.9E+03	4.8E+02	na	--	--	--	--	--	2.9E+03	4.8E+02	na
Chromium VI	0	1.6E+01	1.1E+01	na	--	4.0E+01	6.6E+01	na	--	--	--	--	--	4.0E+01	6.6E+01	na
Chromium, Total	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Chrysene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	na
Copper	0	3.0E-01	9.7E+00	na	--	7.5E+01	5.8E+01	na	--	--	--	--	--	7.5E+01	5.8E+01	na
Cyanide	0	2.2E+01	5.2E+00	na	2.2E+05	5.4E+01	3.1E+01	na	1.4E+06	--	--	--	--	5.4E+01	3.1E+01	na
DDC <sup>c</sup>	0	--	--	na	8.4E-03	--	--	na	1.3E-01	--	--	--	--	--	--	na
DDE <sup>c</sup>	0	--	--	na	5.9E-03	--	--	na	8.8E-02	--	--	--	--	--	--	na
DDT <sup>c</sup>	0	1.1E+00	1.0E-03	na	5.9E-03	2.7E+00	6.0E-03	na	8.8E-02	--	--	--	--	2.7E+00	6.0E-03	na
Demeton	0	--	1.0E-01	na	--	--	6.0E-01	na	--	--	--	--	--	--	6.0E-01	na
Dibenz(a,h)anthracene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	na
Dibutyl phthalate	0	--	--	na	1.2E+04	--	--	na	8.0E+04	--	--	--	--	--	--	na
Dichloromethane	0	--	--	na	1.6E+04	--	--	na	2.4E+05	--	--	--	--	--	--	na
(Methylene Chloride) <sup>c</sup>	0	--	--	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
1,2-Dichlorobenzene	0	--	--	na	2.6E+03	--	--	na	1.7E+04	--	--	--	--	--	--	na
1,3-Dichlorobenzene	0	--	--	na	2.6E+03	--	--	na	1.7E+04	--	--	--	--	--	--	na
1,4-Dichlorobenzene	0	--	--	na	7.7E-01	--	--	na	1.2E+01	--	--	--	--	--	--	na
3,3-Dichlorobenzidine <sup>c</sup>	0	--	--	na	4.6E+02	--	--	na	6.9E+03	--	--	--	--	--	--	na
Dichlorobromomethane <sup>c</sup>	0	--	--	na	9.9E-02	--	--	na	1.5E+04	--	--	--	--	--	--	na
1,2-Dichloroethane <sup>c</sup>	0	--	--	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
1,1-Dichloroethylene	0	--	--	na	1.4E+05	--	--	na	9.4E+05	--	--	--	--	--	--	na
1,2-trans-dichloroethylene	0	--	--	na	7.9E+02	--	--	na	5.3E+03	--	--	--	--	--	--	na
2,4-Dichlorophenol	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
2,4-Dichlorophenoxy	0	--	--	na	3.9E+02	--	--	na	5.8E+03	--	--	--	--	--	--	na
acetic acid (2,4-D)	0	--	--	na	1.7E+03	--	--	na	1.1E+04	--	--	--	--	--	--	na
1,3-Dichloropropane	0	--	--	na	1.4E-03	2.4E-01	5.6E-02	na	2.1E-02	--	--	--	--	5.9E-01	3.4E-01	na
Dieldrin <sup>c</sup>	0	--	--	na	1.2E+05	--	--	na	8.0E+05	--	--	--	--	--	--	na
Diethyl Phthalate	0	--	--	na	5.9E+01	--	--	na	8.8E+02	--	--	--	--	--	--	na
Di-2-Ethylhexyl Phthalate <sup>c</sup>	0	--	--	na	2.3E+03	--	--	na	1.5E+04	--	--	--	--	--	--	na
2,4-Dimethylphenol	0	--	--	na	2.9E+06	--	--	na	1.9E+07	--	--	--	--	--	--	na
Dimethyl Phthalate	0	--	--	na	1.2E+04	--	--	na	8.0E+04	--	--	--	--	--	--	na
Di-n-Butyl Phthalate	0	--	--	na	1.4E+04	--	--	na	9.4E+04	--	--	--	--	--	--	na
2,4-Dinitrophenol	0	--	--	na	7.65E+02	--	--	na	5.1E+03	--	--	--	--	--	--	na
2-Methyl-4,6-Dinitrophenol	0	--	--	na	9.1E+01	--	--	na	1.4E+03	--	--	--	--	--	--	na
2,4-Dinitrotoluene <sup>c</sup>	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Dioxin (2,3,7,8- tetrachlorodibenzo-p-dioxin)	0	--	--	na	1.2E-06	--	--	na	na	--	--	--	--	--	--	na
(ppq)	0	--	--	na	5.4E+00	--	--	na	8.1E+01	--	--	--	--	--	--	na
1,2-Diphenylhydrazine <sup>c</sup>	0	--	--	na	2.4E+02	5.4E-01	3.4E-01	na	1.6E+03	--	--	--	--	5.4E-01	3.4E-01	na
Alpha-Endosulfan	0	2.2E-01	5.6E-02	na	2.4E+02	5.4E-01	3.4E-01	na	1.6E+03	--	--	--	--	5.4E-01	3.4E-01	na
Beta-Endosulfan	0	2.2E-01	5.6E-02	na	2.4E+02	--	--	na	1.6E+03	--	--	--	--	--	--	na
Endosulfan Sulfate	0	--	--	na	2.4E+02	--	--	na	1.6E+03	--	--	--	--	--	--	na
Endrin	0	8.6E-02	3.6E-02	na	8.1E-01	2.1E-01	2.2E-01	na	5.4E+00	--	--	--	--	2.1E-01	2.2E-01	na
Endrin Aldehyde	0	--	--	na	8.1E-01	--	--	na	5.4E+00	--	--	--	--	--	--	na

Parameter (u/g unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Ethylbenzene	0	--	--	na	2.9E+04	--	--	na	1.9E+05	--	--	--	--	--	--	1.9E+05
Fluoranthene	0	--	--	na	3.7E+02	--	--	na	2.5E+03	--	--	--	--	--	--	2.5E+03
Fluorene	0	--	--	na	1.4E+04	--	--	na	9.4E+04	--	--	--	--	--	--	9.4E+04
Foaming Agents	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	--
Guthion	0	--	1.0E-02	na	--	--	6.0E-02	na	--	--	--	--	--	--	6.0E-02	na
Heptachlor <sup>c</sup>	0	5.2E-01	3.8E-03	na	2.1E-03	1.3E+00	2.3E-02	na	3.1E-02	--	--	--	--	1.3E+00	2.3E-02	na
Heptachlor Epoxide <sup>c</sup>	0	5.2E-01	3.8E-03	na	1.1E-03	1.3E+00	2.3E-02	na	1.6E-02	--	--	--	--	1.3E+00	2.3E-02	na
Hexachlorobenzene <sup>c</sup>	0	--	--	na	7.7E-03	--	--	na	1.2E-01	--	--	--	--	--	--	1.2E-01
Hexachlorobutadiene <sup>c</sup>	0	--	--	na	5.0E-02	--	--	na	7.5E+03	--	--	--	--	--	--	7.5E+03
Hexachlorocyclohexane	0	--	--	na	1.3E-01	--	--	na	1.9E+00	--	--	--	--	--	--	1.9E+00
Alpha-BHC <sup>c</sup>	0	--	--	na	4.6E-01	--	--	na	6.9E+00	--	--	--	--	--	--	6.9E+00
Beta-BHC <sup>c</sup>	0	--	--	na	6.3E-01	2.4E+00	--	na	9.4E+00	--	--	--	--	2.4E+00	--	na
Gamma-BHC <sup>c</sup> (Lindane)	0	9.5E-01	na	na	1.7E-04	--	--	na	1.1E+05	--	--	--	--	--	--	1.1E+05
Hexachlorocyclopentadiene	0	--	--	na	8.9E+01	--	--	na	1.3E+03	--	--	--	--	--	--	1.3E+03
Hexachloroethane <sup>c</sup>	0	--	2.0E+00	na	--	--	1.2E+01	na	--	--	--	--	--	--	1.2E+01	na
Hydrogen Sulfide	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	7.3E+00
Indeno (1,2,3-cd) pyrene <sup>c</sup>	0	--	--	na	2.6E+04	--	--	na	3.9E+05	--	--	--	--	--	--	3.9E+05
Iron	0	--	--	na	0.0E+00	--	0.0E+00	na	--	--	--	--	--	--	0.0E+00	na
Isophorone <sup>c</sup>	0	3.8E+02	1.5E+01	na	--	8.9E+02	9.1E+01	na	--	--	--	--	--	8.9E+02	9.1E+01	na
Kepone	0	--	1.0E-01	na	--	--	6.0E-01	na	--	--	--	--	--	--	6.0E-01	na
Lead	0	--	--	na	5.1E-02	--	--	na	3.4E-01	--	--	--	--	--	--	3.4E-01
Malathion	0	--	--	na	4.0E+03	--	--	na	2.7E+04	--	--	--	--	--	--	2.7E+04
Manganese	0	1.4E+00	7.7E-01	na	--	--	1.8E-01	na	--	--	--	--	--	--	--	1.8E-01
Mercury	0	--	3.0E-02	na	--	--	0.0E+00	na	--	--	--	--	--	--	0.0E+00	na
Methyl Bromide	0	--	0.0E+00	na	2.1E+04	9.4E+02	1.3E+02	na	1.4E+05	--	--	--	--	9.4E+02	1.3E+02	na
Methoxychlor	0	3.8E+02	2.2E+01	na	4.6E+03	--	--	na	3.1E+04	--	--	--	--	--	--	3.1E+04
Mirex	0	--	--	na	1.9E+03	--	--	na	1.3E+04	--	--	--	--	--	--	1.3E+04
Monochlorobenzene	0	--	--	na	8.1E+01	--	--	na	1.2E+03	--	--	--	--	--	--	1.2E+03
Nickel	0	--	--	na	1.6E+02	--	--	na	2.4E+03	--	--	--	--	--	--	2.4E+03
Nitrate (as N)	0	6.5E-02	1.3E-02	na	1.4E+01	--	--	na	2.1E+02	--	--	--	--	--	--	2.1E+02
Nitrobenzene	0	--	1.4E-02	na	--	1.6E-01	7.8E-02	na	--	--	--	--	--	1.6E-01	7.8E-02	na
N-Nitrosodimethylamine <sup>c</sup>	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
N-Nitrosodiphenylamine <sup>c</sup>	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
N-Nitrosodi-n-propylamine <sup>c</sup>	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
Parathion	0	6.5E-02	1.3E-02	na	1.4E+01	--	--	na	2.1E+02	--	--	--	--	--	--	2.1E+02
PCB-1016	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1221	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1232	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1242	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1248	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1254	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1260	0	--	1.4E-02	na	--	--	8.4E-02	na	2.5E-02	--	--	--	--	--	--	2.5E-02
PCB Total <sup>c</sup>	0	--	--	na	1.7E-03	--	--	na	--	--	--	--	--	--	--	na

Parameter (ug/l unless noted) <sup>c</sup>	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Pentachlorophenol <sup>c</sup>	0	5.9E+00	3.9E+00	na	8.2E+01	1.5E+01	2.4E+01	na	1.2E+03	--	--	--	--	1.5E+01	2.4E+01	na
Phenol	0	--	--	na	4.6E+06	--	--	na	3.1E+07	--	--	--	--	--	--	na
Pyrene	0	--	--	na	1.1E+04	--	--	na	7.4E+04	--	--	--	--	--	--	na
Radionuclides (pCi/l except Beta/Photon)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Gross Alpha Activity	0	--	--	na	1.5E+01	--	--	na	1.0E+02	--	--	--	--	--	--	na
Beta and Photon Activity (mrem/yr)	0	--	--	na	4.0E+00	--	--	na	2.7E+01	--	--	--	--	--	--	na
Strontium-90	0	--	--	na	8.0E+00	--	--	na	5.4E+01	--	--	--	--	--	--	na
Tritium	0	--	--	na	2.0E+04	--	--	na	1.3E+05	--	--	--	--	--	--	na
Selenium	0	2.0E+01	5.0E+00	na	1.1E+04	5.0E+01	3.0E+01	na	7.4E+04	--	--	--	--	5.0E+01	3.0E+01	na
Silver	0	1.5E+01	--	na	--	3.8E+01	--	na	--	--	--	--	--	3.8E+01	--	na
Sulfate	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
1,1,2,2-Tetrachloroethane <sup>c</sup>	0	--	--	na	1.1E+02	--	--	na	1.6E+03	--	--	--	--	--	--	na
Trichloroethylene <sup>c</sup>	0	--	--	na	8.9E+01	--	--	na	1.3E+03	--	--	--	--	--	--	na
Thallium	0	--	--	na	6.3E+00	--	--	na	4.2E+01	--	--	--	--	--	--	na
Toluene	0	--	--	na	2.0E+05	--	--	na	1.3E+06	--	--	--	--	--	--	na
Total dissolved solids	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Toxaphene <sup>c</sup>	0	7.3E-01	2.0E-04	na	7.5E-03	1.8E+00	1.2E-03	na	1.1E-01	--	--	--	--	1.8E+00	1.2E-03	na
Tributyltin	0	4.6E-01	6.3E-02	na	--	1.1E+00	3.8E-01	na	--	--	--	--	--	1.1E+00	3.8E-01	na
1,2,4-Trichlorobenzene	0	--	--	na	9.4E+02	--	--	na	6.3E+03	--	--	--	--	--	--	na
1,1,2-Trichloroethane <sup>c</sup>	0	--	--	na	4.2E+02	--	--	na	6.3E+03	--	--	--	--	--	--	na
Trichloroethylene <sup>c</sup>	0	--	--	na	8.1E+02	--	--	na	1.2E+04	--	--	--	--	--	--	na
2,4,6-Trichlorophenol <sup>c</sup>	0	--	--	na	6.5E+01	--	--	na	9.7E+02	--	--	--	--	--	--	na
2-(2,4,5-Trichlorophenoxy) propionic acid (Silvex)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Vinyl Chloride <sup>c</sup>	0	--	--	na	6.1E+01	--	--	na	9.1E+02	--	--	--	--	--	--	na
Zinc	0	2.4E+02	1.3E+02	na	6.9E+04	6.1E+02	7.7E+02	na	4.6E+05	--	--	--	--	6.1E+02	7.7E+02	na

Notes:

1. All concentrations expressed as micrograms/liter (ug/l), unless noted otherwise
2. Discharge flow is highest monthly average or Form 2C maximum for Industries and design flow for Municipals
3. Metals measured as Dissolved, unless specified otherwise
4. "C" indicates a carcinogenic parameter
5. Regular WLAs are mass balances (minus background concentration) using the % of stream flow entered above under Mixing Information.  
Antidegradation WLAs are based upon a complete mix.  
Antideg. Baseline = (0.25(WQC - background conc.) + background conc.) for acute and chronic  
= (0.1(WQC - background conc.) + background conc.) for human health
6. WLAs established at the following stream flows: 1Q10 for Acute, 30Q10 for Chronic Ammonia, 7Q10 for Other Chronic, 30Q5 for Non-carcinogens, Harmonic Mean for Carcinogens, and Annual Average for Dioxin. Mixing ratios may be substituted for stream flows where appropriate.

Metal	Target Value (SSTV)
Antimony	2.9E+04
Arsenic	3.4E+02
Barium	na
Cadmium	4.4E+00
Chromium III	2.9E+02
Chromium VI	1.6E+01
Copper	3.0E+01
Iron	na
Lead	5.5E+01
Manganese	na
Mercury	3.4E-01
Nickel	7.9E+01
Selenium	1.8E+01
Silver	1.5E+01
Zinc	2.4E+02

Note: do not use QL's lower than the minimum QL's provided in agency guidance

Facility = Doswell WWTP existing  
Chemical = Ammonia  
Chronic averaging period = 30  
WLAa = 46  
WLAc = 13  
Q.L. = .2  
# samples/mo. = 12  
# samples/wk. = 3

Summary of Statistics:

# observations = 1  
Expected Value = 7.8  
Variance = 21.9024  
C.V. = 0.6  
97th percentile daily values = 18.9806  
97th percentile 4 day average = 12.9775  
97th percentile 30 day average = 9.40721  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

7.8

Guidance Memorandum No. 00-2011 directs that an ammonia effluent concentration of 9 mg/L be used to evaluate the need for an ammonia limitation for a municipal discharge. Although this discharge consists predominantly of industrial wastewater, it is reasonable to check to see if the cited guidance would result in a limitation. In this case, the permit already limits TKN to 13 mg/L. Ammonia typically makes up 40% to 60% of the TKN in a municipal effluent. Ammonia makes up 46% of the TKN in the Bear Island wastewater (see "Outfall 001 – Supplement to Table I"). Using 60% as a worse case scenario, the ammonia concentration could be as high 7.8 mg/L, which is the concentration used in the above analysis ( $13 \times 0.6 = 7.8$ ). The above result that "no limit is required" establishes that the TKN limitation is also protective of the ammonia water quality standard. (See Attachment 6B for ammonia data on Outfall 001.)

Facility = Doswell WWTP existing  
Chemical = Chloride  
Chronic averaging period = 4  
WLAa = 2100000  
WLAc = 1400000  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 29000  
Variance = 3027600  
C.V. = 0.6  
97th percentile daily values = 70569.1  
97th percentile 4 day average = 48249.9  
97th percentile 30 day average = 34975.5  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

29000

Facility = Doswell WWTP existing  
Chemical = Total Residual Chlorine  
Chronic averaging period = 4  
WLAa = 47  
WLAc = 66  
Q.L. = 0.1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 3  
Expected Value = 360  
Variance = 46656  
C.V. = 0.6  
97th percentile daily values = 876.030  
97th percentile 4 day average = 598.964  
97th percentile 30 day average = 434.179  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**A limit is needed based on Acute Toxicity**

Maximum Daily Limit = 47  
Average Weekly Limit = 47  
Average Monthly Limit = 47

The data are:

190  
410  
480

Chlorine is not used for disinfection at the Doswell treatment plant and chlorine is not used in the Bear Island process. The above concentrations were determined in conjunction with the failed *Ceriodaphnia dubia* chronic bioassay test in March 2007 (see Attachment 8). These TRC concentrations are believed to be false positives due to possible interference by manganese or alkalinity. Because chlorine is not used at either site, limitations are not included in the draft permit. (It is not appropriate to "force" chlorine limitations with an input of value of 20,000 µg/L per Guidance Memorandum No. 00-2011 because chlorine is not added to the system at any point.)

Facility = Doswell WWTP existing  
Chemical = Dissolved Copper  
Chronic averaging period = 4  
WLAa = 75  
WLAc = 58  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 6  
Variance = 12.96  
C.V. = 0.6  
97th percentile daily values = 14.6005  
97th percentile 4 day average = 9.98274  
97th percentile 30 day average = 7.23631  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

6

The dissolved copper data reported with the permit renewal application were 6 µg/L, <5 µg/L, and <5 µg/L (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the copper data.



Facility = Doswell WWTP  
Chemical = Cyanide  
Chronic averaging period = 4  
WLAa = 54  
WLAc = 31  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 2  
Expected Value = 10.5  
Variance = 39.69  
C.V. = 0.6  
97th percentile daily values = 25.5508  
97th percentile 4 day average = 17.4697  
97th percentile 30 day average = 12.6635  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

11  
10

The cyanide data reported with the permit renewal application were 11 µg/L, 10 µg/L, and <10 µg/L (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the cyanide data. Note in Attachment 6A that a cyanide study was conducted starting in March 2004 and ending in October 2005. The above data are consistent with the data collected during that study period. Although the data from the cyanide study are more than three years old, they are still representative and could have been included in the above analysis. The above analysis using only two data points is a more extreme analysis however, which indicates that limitations are not needed.

Facility = Doswell WWTP existing  
Chemical = Dissolved Lead  
Chronic averaging period = 4  
WLAa = 890  
WLAc = 91  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 30  
Variance = 324  
C.V. = 0.6  
97th percentile daily values = 73.0025  
97th percentile 4 day average = 49.9137  
97th percentile 30 day average = 36.1815  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

30

The dissolved lead data reported with the permit renewal application were (all in  $\mu\text{g/L}$ ): <20, <20, 30, <20, <20, <20, <20, <20, and <20 (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the lead data.

Facility = Doswell WWTP existing  
Chemical = Dissolved Zinc  
Chronic averaging period = 4  
WLAa = 610  
WLAc = 770  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 11  
Expected Value = 133.937  
Variance = 1605.77  
C.V. = 0.299185  
97th percentile daily values = 222.573  
97th percentile 4 day average = 175.236  
97th percentile 30 day average = 147.698  
# < Q.L. = 0  
Model used = lognormal

**No Limit is required for this material**

The data are:

108  
101  
134  
218  
173  
98  
113  
110  
104  
109  
204

**Attachment 8**

WET Evaluation

## Attachment 8

VPDES Permit VA00029521 – Doswell Wastewater Treatment Plant

Results of acute toxicity tests during term of current permit:

Permit endpoints:  $LC_{50} \geq 100\%$   
 $NOEC \geq 21\%$  at 5.8 MGD

TEST DATE	<i>Ceriodaphnia dubia</i>		<i>Pimephales promelas</i>		Laboratory
	LC <sub>50</sub>	PERCENT SURVIVAL IN 100% EFFLUENT	LC <sub>50</sub>	PERCENT SURVIVAL IN 100% EFFLUENT	
February 2004	>100	100	>100	95	Coastal Bioanalysts
April 2005	>100	100	>100	100	J. R. Reed
April 2006	>100	100	>100	100	J. R. Reed
March 2007	>100	100	>100	100	J. R. Reed
February 2008	>100	100	>100	100	J. R. Reed

Results of chronic toxicity tests during term of current permit:

TEST DATE**	<i>Ceriodaphnia dubia</i>		<i>Pimephales promelas</i>		Laboratory
	Survival	Reproduction	Survival	Reproduction	
February 2004	100	61	100	100	Coastal Bioanalysts
April 2005	100	50	100	100	J. R. Reed
April 2006	invalid		100	100	J. R. Reed
May 2006 <sup>(1)</sup>	100	50			J. R. Reed
March 2007	100	<6.25 <sup>(2)</sup>			J. R. Reed
April 2007 <sup>(1)</sup>	100	100			J. R. Reed
April 2007 <sup>(1)</sup>	100	100			Coastal Bioanalysts
February 2008	100	<4 <sup>(3)</sup>	100	100	J. R. Reed
April 2008 <sup>(1)</sup>	100	100 <sup>(4)</sup>			J. R. Reed
April 2008 <sup>(1)</sup>	100	100			Coastal Bioanalysts

- (1) Retest
- (2) Total residual chlorine concentrations were detected in the samples received at the laboratory. Those concentrations were determined to be false positives; chlorine is not used for disinfection of final effluent. Also, subsequent screening tests at Bear Island did not indicate toxicity.
- (3) Laboratory noted presence of large brown cotton shaped solids that surrounded the *C. dubia* during the test period.
- (4) Laboratory noted presence of brown cotton shaped solids in one of the three samples collected for the test. Also, total residual chlorine concentrations were detected in the samples received at the laboratory. Those concentrations are considered to be false positives.

Discussion

Acute toxicity is not indicated.

Chronic toxicity (reproduction effect) may be indicated. The retests however, did not confirm the toxic effects.

The proposed permit requires the continuation of annual acute and chronic WET testing with *Ceriodaphnia dubia* and *Pimephales promelas*. The results of those tests will be evaluated for reasonable potential at the conclusion of the permit term, or sooner if toxicity is noted, and appropriate effluent limitations established.

**Spreadsheet for determination of WET test endpoints or WET limits**

Excel 97 Revision Date: 01/10/06 File: WETLIM10.xls (MIXEXE required also)	Acute Endpoint/Permit Limit	Use as LC <sub>50</sub> in Special Condition, as TUa on DMR
ACUTE 100% =	NOAEC	% Use as NA
ACUTE WLAa	0.74312586	Note: Inform the permittee that if the mean of the data exceeds this TUa: 1.0
Chronic Endpoint/Permit Limit	Use as NOEC in Special Condition, as TUC on DMR	
CHRONIC 7.431258803 TU <sub>c</sub>	NOEC =	14 % Use as 7.14 TU <sub>c</sub>
BOTH* 7.431258803 TU <sub>c</sub>	NOEC =	14 % Use as 7.14 TU <sub>c</sub>
AML 7.431258803 TU <sub>c</sub>	NOEC =	14 % Use as 7.14 TU <sub>c</sub>
ACUTE WLAa,c	7.43125862	Note: Inform the permittee that if the mean of the data exceeds this TUC: 3.0538362
CHRONIC WLAa,c	6	a limit may result using WLA EXE
* Both means acute expressed as chronic		
% Flow to be used from MIXEXE	Diffuser /modeling study?	
31.73 %	Enter Y/N	1 : 1
100 %	Acute	1 : 1
Chronic	Chronic	1 : 1
N (Minimum of 10 data points, same species, needed)		Go to Page 2
N (NOEC<LC50, do not use greater/less than data)		Go to Page 3
40.37001204 % Plant flow/plant flow + 1Q10	NOTE: If the IWCa is >33%, specify the	
16.66666667 % Plant flow/plant flow + 7Q10	NOAEC = 100% test/endpoint for use	
2.477086207		
6		
0.743125862	stream criterion (0.3 TUa) X's Dilution, acute	
6	stream criterion (1.0 TUc) X's Dilution, chronic	
7.431258621	ACR X's WLA <sub>a</sub> - converts acute WLA to chronic units	
10	LC50/NOEC (Default is 10 - if data are available, use tables Page 3)	
0.6	Default of 0.6 - if data are available, use tables Page 2)	
0.4109447	Default = 0.41	
0.6010373	Default = 0.60	
2.4334175	Default = 2.43	
2.4334175	Default = 2.43 (1 samp)	No. of sample 1
3.053836345	WLAa,c X's eA	**The Maximum Daily Limit is calculated from the lowest LTA, X's eC. The LTAa,c and MDL using it are driven by the ACR.
3.6062238	WLAa,c X's eB	Rounded NOEC's
7.431258803	NOEC =	NOEC = 14 %
8.775448104	NOEC =	NOEC = 12 %
7.431258803	NOEC =	NOEC = 14 %
IF ONLY ACUTE ENDPOINT/LIMIT IS NEEDED, CONVERT MDL FROM TU <sub>c</sub> TO TU <sub>a</sub>		
0.74312588	TU <sub>a</sub>	Rounded LC50's
0.87754481	TU <sub>a</sub>	NOEC = NA
		LC50 = NA

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
<b>Page 2 - Follow the directions to develop a site specific CV (coefficient of variation)</b>														
1	IF YOU HAVE AT LEAST 10 DATA POINTS THAT ARE QUANTIFIABLE (NOT "<" OR ">")													
2	FOR A SPECIES, ENTER THE DATA IN EITHER COLUMN "G" (VERTEBRATE) OR COLUMN "J" (INVERTEBRATE). THE "CV" WILL BE PICKED UP FOR THE CALCULATIONS													
3	BELOW. THE DEFAULT VALUES FOR eA, eB, AND eC WILL CHANGE IF THE "CV" IS ANYTHING OTHER THAN 0.6.													
4						Vertebrate IC <sub>25</sub> Data or LC <sub>50</sub> Data *****	LN of data		Vertebrate IC <sub>25</sub> Data or LC <sub>50</sub> Data *****	LN of data				
5						1	0		1	0				
6						2			2					
7						3			3					
8						4			4					
9						5			5					
10						6			6					
11						7			7					
12						8			8					
13						9			9					
14						10			10					
15						11			11					
16						12			12					
17						13			13					
18						14			14					
19						15			15					
20						16			16					
21						17			17					
22						18			18					
23						19			19					
24						20			20					
<b>Coefficient of Variation for effluent tests</b>														
25						CV =	0.6 (Default 0.6)							
26						$\sigma^2 =$	0.3074847							
27						$\sigma =$	0.554513029							
<b>Using the log variance to develop eA</b>														
28						(P. 100, step 2a of TSD)								
29						Z = 1.881 (97% probability stat from table)								
30						A =	-0.88929666							
31						eA =	0.410944636							
<b>Using the log variance to develop eB</b>														
32						(P. 100, step 2b of TSD)								
33						$\sigma_e^2 =$	0.086177696		St Dev	0	NEED DATA	NEED DATA	NEED DATA	
34						$\sigma_e =$	0.293560379		Mean	0	0	0	0	
35						B =	-0.50909823		Variance	0	0.000000	0	0.000000	
36						eB =	0.601037335		CV	0	0	0	0	
<b>Using the log variance to develop eC</b>														
37						(P. 100, step 4a of TSD)								
38						$\sigma^2 =$	0.3074847							
39						$\sigma =$	0.554513029							
40						C =	0.889296658							
41						eC =	2.433417525							
<b>Using the log variance to develop eD</b>														
42						(P. 100, step 4b of TSD)								
43						n =	1		This number will most likely stay as "1" for 1 sample/month.					
44						$\sigma_n^2 =$	0.3074847							
45						$\sigma_n =$	0.554513029							
46						D =	0.889296658							
47						eD =	2.433417525							



**Page 3 - Follow directions to develop a site specific ACR (Acute to Chronic Ratio)**

To determine Acute/Chronic Ratio (ACR), insert usable data below. Usable data is defined as valid paired test results, acute and chronic, tested at the same temperature, same species. The chronic NOEC must be less than the acute LC<sub>50</sub>, since the ACR divides the LC<sub>50</sub> by the NOEC. LC<sub>50</sub>'s >100% should not be used.

**Table 1. ACR using Vertebrate data**

Set #	LC <sub>50</sub>	NOEC	Test ACR	Logarithm	Geomean	Antilog	ACR to Use
1	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
2	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
3	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
4	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
5	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
6	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
7	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
8	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
9	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
10	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
					ACR for vertebrate data:		0

Table 1. Result:

Table 2. Result:

Lowest ACR

Table 2. ACR using Invertebrate data

Set #	LC <sub>50</sub>	NOEC	Test ACR	Logarithm	Geomean	Antilog	ACR to Use
1	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
2	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
3	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
4	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
5	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
6	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
7	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
8	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
9	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
10	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
					ACR for vertebrate data:		0

Table 1. Result:

Table 2. Result:

Lowest ACR

Table 2. ACR using Invertebrate data

Set #	LC <sub>50</sub>	NOEC	Test ACR	Logarithm	Geomean	Antilog	ACR to Use
1	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
2	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
3	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
4	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
5	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
6	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
7	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
8	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
9	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
10	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	NO DATA
					ACR for vertebrate data:		0

**DILUTION SERIES TO RECOMMEND**

Table 4.	Monitoring	Limit
Dilution series based on data mean	% Effluent	TUC
Dilution series to use for limit	32.7	3.0538362
Dilution factor to recommend:	0.5722386	14
Dilution series to recommend:	100.0	100.0
	57.2	1.75
	32.7	3.05
	18.7	5.34
	10.72	9.33
Extra dilutions if needed	6.14	16.30
	3.51	28.48
		0.3

**Table 3. Convert LC<sub>50</sub>'s and NOEC's to Chronic TU's**

Table 3.	Enter LC <sub>50</sub>	TUC	Enter NOEC	TUC
1		NO DATA		NO DATA
2		NO DATA		NO DATA
3		NO DATA		NO DATA
4		NO DATA		NO DATA
5		NO DATA		NO DATA
6		NO DATA		NO DATA
7		NO DATA		NO DATA
8		NO DATA		NO DATA
9		NO DATA		NO DATA
10		NO DATA		NO DATA
11		NO DATA		NO DATA
12		NO DATA		NO DATA
13		NO DATA		NO DATA
14		NO DATA		NO DATA
15		NO DATA		NO DATA
16		NO DATA		NO DATA
17		NO DATA		NO DATA
18		NO DATA		NO DATA
19		NO DATA		NO DATA
20		NO DATA		NO DATA

If WLA EXE determines that an acute limit is needed, you need to convert the TUC answer you get to TUA and then an LC<sub>50</sub>, enter it here:

NO DATA	%LC <sub>50</sub>	TUA
NO DATA	NO DATA	NO DATA

Cell: I9

Comment:

This is assuming that the data are Type 2 data (none of the data in the data set are censored - "<" or ">").

Cell: K18

Comment:

This is assuming that the data are Type 2 data (none of the data in the data set are censored - "<" or ">").

Cell: J22

Comment:

Remember to change the "N" to "Y" if you have ratios entered, otherwise, they won't be used in the calculations.

Cell: C40

Comment:

If you have entered data to calculate an ACR on page 3, and this is still defaulted to "10", make sure you have selected "Y" in cell E21

Cell: C41

Comment:

If you have entered data to calculate an effluent specific CV on page 2, and this is still defaulted to "0.6", make sure you have selected "Y" in cell E20

Cell: L48

Comment:

See Row 151 for the appropriate dilution series to use for these NOEC's

Cell: G62

Comment:

Vertebrates are:  
Pimephales promelas  
Oncorhynchus mykiss  
Cyprinodon variegatus

Cell: J62

Comment:

Invertebrates are:  
Ceriodaphnia dubia  
Mysidopsis bahia

Cell: C117

Comment:

Vertebrates are:  
Pimephales promelas  
Cyprinodon variegatus

Cell: M119

Comment:

The ACR has been picked up from cell C34 on Page 1. If you have paired data to calculate an ACR, enter it in the tables to the left, and make sure you have a "Y" in cell E21 on Page 1. Otherwise, the default of 10 will be used to convert your acute data.

Cell: M121

Comment:

If you are only concerned with acute data, you can enter it in the NOEC column for conversion and the number calculated will be equivalent to the T<sub>Ua</sub>. The calculation is the same: 100/NOEC = T<sub>Uc</sub> or 100/CS<sub>50</sub> = T<sub>Ua</sub>.

Cell: C138

Comment:

Invertebrates are:  
Ceriodaphnia dubia  
Mysidopsis bahia

# Spreadsheet for determination of WET test endpoints or WET limits

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023	1024	1025	1026	1027	1028	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1472	1473	1474	1475	1476	1477	1478	1479	1480	1481	1482	1483	1484	1485	1486	1487	1488	148
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	-----



**Page 3 - Follow directions to develop a site specific ACR (Acute to Chronic Ratio)**

To determine Acute/Chronic Ratio (ACR), insert usable data below. Usable data is defined as valid paired test results, acute and chronic, tested at the same temperature, same species. The chronic NOEC must be less than the acute LC<sub>50</sub>, since the ACR divides the LC<sub>50</sub> by the NOEC. LC<sub>50</sub>'s > 100% should not be used.

Convert LC <sub>50</sub> 's and NOEC's to Chronic TU's															
for use in WLA.EXE															
ACR used: 10															
Table 3.															
Enter LC <sub>50</sub>															
1															
2															
3															
4															
5															
6															
7															
8															
9															
10															
11															
12															
13															
14															
15															
16															
17															
18															
19															
20															
if WLA.EXE determines that an acute limit is needed, you need to convert the TUC answer you get to TUA and then an LC <sub>50</sub> .															
enter it here:															
NO DATA															
NO DATA															
TUA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO DATA															
NO															

Cell: I9

Comment:

This is assuming that the data are Type 2 data (none of the data in the data set are censored - "<" or ">").

Cell: K18

Comment:

This is assuming that the data are Type 2 data (none of the data in the data set are censored - "<" or ">").

Cell: J22

Comment:

Remember to change the "N" to "Y" if you have ratios entered, otherwise, they won't be used in the calculations.

Cell: C40

Comment:

If you have entered data to calculate an ACR on page 3, and this is still defaulted to "10", make sure you have selected "Y" in cell E21

Cell: C41

Comment:

If you have entered data to calculate an effluent specific CV on page 2, and this is still defaulted to "0.6", make sure you have selected "Y" in cell E20

Cell: L48

Comment:

See Row 151 for the appropriate dilution series to use for these NOEC's

Cell: G62

Comment:

Vertebrates are:  
Pimephales promelas  
Oncorhynchus mykiss  
Cyprinodon variegatus

Cell: J62

Comment:

Invertebrates are:  
Ceriodaphnia dubia  
Mysidopsis bahia

Cell: C117

Comment:

Vertebrates are:  
Pimephales promelas  
Cyprinodon variegatus

Cell: M119

Comment:

The ACR has been picked up from cell C34 on Page 1. If you have paired data to calculate an ACR, enter it in the tables to the left, and make sure you have a "Y" in cell E21 on Page 1. Otherwise, the default of 10 will be used to convert your acute data.

Cell: M121

Comment:

If you are only concerned with acute data, you can enter it in the NOEC column for conversion and the number calculated will be equivalent to the TUs. The calculation is the same: 100/NOEC = TUc or 100/(CS50 = TUs.

Cell: C138

Comment:

Invertebrates are:  
Ceriodaphnia dubia  
Mysidopsis bahia

**Attachment 9**

## Revision of Control Equation

- Refer to page 2, item #3 of July 12, 1978 (copy attached).

NOD concentration for 6.0 mg/l TKN equals  $6 \times 4.5 \times 0.25 = 6.75$  (instead of 15.75).

$$\text{Therefore, } LW_u = 1.5625 LW_5 + 6.75 \quad (\text{ref. eqn (1), p 2})$$

substituting and solving as before,

$$LW_5 = 3.4 \frac{Q_s}{Q_w} + 0.3 \quad (\text{ref. eqn (3), p 3})$$

For simplicity, omit 0.3 which makes insignificant contribution.

Therefore, new control equation is

$$LW_5 = 3.4 \frac{Q_s}{Q_w}$$

- The control equation must now be adjusted to reflect the Doswell water treatment plant and BIPCO raw water intakes on the North Anna above the discharge point. The intake capacities are 3.0 MGD for Doswell and 4.0 MGD for BIPCO. (See attached letter dated May 6, 1985 from Mr. John Jackson, County Administrator.)

$$7 \text{ MGD} \times 1.55 = 10.85 \text{ cfs}$$

Therefore, control equation becomes

$$LW_5 = 3.4 \frac{Q_s - 10.85}{Q_w}$$



- using new control equation, the 7 day/10 year allocation is:

$Q_w = 5.0 \text{ MGD} : 1 \text{ MGD Doswell} ; 4 \text{ MGD BIPCO.}$  BIPCO is in the early stages of planning for a mill expansion to double production. Wastewater flow projected at 4 MGD.

$$LW_5 = \frac{3.4 (43.68 - 10.85)}{5 \text{ MGD}(1.55)}$$

$$= 14.4 \text{ mg/l}$$

$$14.4 \text{ mg/l} \times 5 \text{ MGD} \times 8.34 = 600 \text{ lbs/day}$$

- The current permit establishes a maximum discharge of 1500 #/d BOD<sub>5</sub> and TSS. This value is based on 1 MGD from Doswell at 30 mg/l and 3 MGD from BIPCO at 50 mg/l. (The 3 MGD represented a doubling of the facility based on the initial design flow of 1.5 MGD.) The attached graph titled "BIPCO Effluent Storage Analysis" was prepared by BIPCO's consultant Mr. John Combs for a meeting on May 2, 1985. At a BIPCO effluent flow of 4 MGD, this graph indicates that the current maximum of 1500 #/d (which corresponds to approx. 100 cfs stream flow) does not allow emptying of the storage basin in a reasonable period of time. The company has therefore, requested that a new maximum be established based on a stream flow of 300 cfs. As the control equation establishes an allowable discharge given any stream

flow, an increase in the maximum limitation is acceptable. Using the control equation, the maximum limitation based on 300 cfs is:

$$LW_5 = 3.4 \frac{(300 - 10.85)}{5(1.55)}$$

$$= 127 \text{ mg/l}$$

$$127 \text{ mg/l} \times 5 \text{ MGD} \times 8.34 = 5296 \text{ \#/d}$$

say 5300 \#/d

RRJ  
5-21-85

# MEMORANDUM

## State Water Control Board

2111 North Hamilton Street

P. O. Box 11143

Richmond, VA. 23230

SUBJECT: Amendment of Doswell NPDES Permit, VA0029521. Supplement to Memorandum dated June 19, 1978

TO: File (42-0525)

FROM: Ray R. Jenkins, Jr. *Ray Jenkins*

DATE: July 12, 1978

COPIES: L. G. Lawson, J. J. Cibulka, W. D. Jones, Dale F. Jones

On June 28, 1978, Wes Jones, John Combs, and the writer traveled to Philadelphia, Pennsylvania to discuss the proposed Doswell tiered permit with personnel of the EPA's Region III Office. The attached list of people were in attendance.

All aspects of the proposed permit and some of the reasons for proposing a tiered permit were discussed. One of the most significant results of the meeting was the realization that the modeling recalculations detailed in the June 19, 1978, memorandum were not entirely appropriate. Charlie App pointed out that not only did the York River Basin 303(e) plan allocate wasteloads, but it also established a stream modeling methodology that took into account NOD (nitrogenous oxygen demand) and a 20% reserve assimilative capacity (p.53, 67-69 and Appendix F from the plan are attached). In our original work, it had been decided that we would strictly follow the methodology (no NOD or reserve) used in the 1973 Doswell modeling. (It should be noted that the 303(e) Plan indicates that NOD and a 20 % reserve were taken into account in establishing the 200 #d/ CBOD<sub>5</sub> allocation. These values however, were derived (back-calculated) from the 200 #/d CBOD<sub>5</sub> allocation as this allocation was already in the Doswell NPDES permit when the Plan was prepared.) Charlie App advised that if changes in the allocation and therefore, the 303(e) Plan were to be proposed, the changes should incorporate the modeling methodology outlined in the Plan. These changes essentially involved reassigning rate coefficients to be consistent with other modeling in the Basin Plan, and incorporating the methodology of Appendix F.

The attached memorandum titled "Proposed Discharge to North Anna River, Hanover County" dated June 30, 1978 details the inputs to the modeling as described above. The UCBOD to CBOD<sub>5</sub> ratio was 1.25 (ref. Appendix F). The particular modeling effort detailed in the June 30 memorandum was intended to define the 7 day/10 year low flow allocation. It also served as a check on the accuracy of the CBOD<sub>5</sub> control equation which was generated by letting L<sub>0</sub> (now UOD of the discharge-river mix) be the input variable to the modeling equation (refer to June 19 memorandum for methodology).

Following the procedure detailed in the June 19, 1978, memorandum, the allowable L<sub>0</sub> using the revised rate coefficients was determined to be 7.2 mg/l. The critical dissolved oxygen deficit of 0.96 mg/l occurred just prior to the confluence of the North and South Anna Rivers. The river was observed to recover with the entry of the South Anna River.

The revised control equation was generated through the following approach, which is in accordance with the Plan methodology. The NOD was subtracted from the discharge concentration in ultimate demand terms. The resultant was converted to 5-day demand and the 20% reserve was subtracted. The resulting expression was rewritten in order that the UOD of the wastewater could be substituted into the mass balance equation of the wastewater-river mix, which was set equal to 7.2 mg/l. The wastewater TKN concentration was calculated to be 14 mg/l using 1.0 MGD of Doswell wastewater at 20 mg/l TKN and 1.5 MGD of BATO wastewater at 10 mg/l TKN. This wastewater mix can be considered to be a worst case condition in that any increase in BATO flow above 1.5 MGD would lower the TKN concentration of the combined discharge. Assuming such a "worst case" TKN concentration was considered preferable to adding another variable (TKN) to the control equation.

The following computations delineate the derivation of the revised control equation:

1. Ultimate oxygen demand (UOD) = ultimate CBOD + nitrogenous oxygen demand (NOD).
2.  $\text{UOD \#/d} = \text{LW}_u \times \text{Q}_w \times 8.34$ , where  $\text{LW}_u$  = ultimate oxygen demand of waste; and  $\text{Q}_w$  = wastewater flow rate (MGD)
3.  $\text{NOD} = 15.75 \times \text{Q}_w \times 8.34$

$$15.75 = 0.25 \times 4.5 \times \frac{20(1) + 10(1.5)}{1 + 1.5}$$

\* see p. 53 from York 303 (e), attached

4.  $\text{UCBOD} \times 0.8 = \text{CBOD}_5$  ( $\text{UCBOD}/\text{CBOD}_5 = 1.25$ )
5.  $20\% \text{ reserve} = \text{CBOD}_5 \times 0.8$

Therefore  $\text{BOD}_5$  discharge in #/d =

$$0.8 \times 0.8 \times [(\text{LW}_u \times \text{Q}_w \times 8.34) - (15.75 \times \text{Q}_w \times 8.34)]$$

$$\text{BOD}_5 (\#/d) \div (8.34 \times \text{Q}_w) = \text{discharge } \text{CBOD}_5 \text{ concentration} = \text{LW}_5$$

Therefore,

$$\text{LW}_5 = \frac{0.8 \times 0.8 \times [(\text{LW}_u \times \text{Q}_w \times 8.34) - (15.75 \times \text{Q}_w \times 8.34)]}{8.34 \times \text{Q}_w}$$

solving for  $\text{LW}_u$ :

$$\text{LW}_u = 1.5625 \text{ LW}_5 + 15.75 \quad \text{Equation (1)}$$

Remembering now that  $\text{L}_o$  must equal 7.2 mg/l, the following mass balance equation can be written:

$$\frac{(\text{LW}_u \times \text{Q}_w) + (1.875 \times \text{Q}_s)}{\text{Q}_w + \text{Q}_s} = 7.2 \quad \text{Equation (2)}$$

\*\* stream background UCBOD

Substituting equation (1) into (2) yields,

$$\frac{[(1.5625 LW_5 + 15.75) \times Q_w] + (1.875 \times Q_s)}{Q_w + Q_s} = 7.2$$

Solving for  $LW_5$  and simplifying,

$$LW_5 = 3.4 \frac{Q_s}{Q_w} - 5.5. \quad \text{Equation (3)}$$

This expression will be the permit controlling equation for allowable  $CBOD_5$  discharge based upon the water quality standards. (This expression replaces equation (1) in the June 19 memorandum.)

At a 7 day/10 year low flow of 43.68 cfs (North Anna and Little Rivers) and a wastewater flow of 2.5 MGD, the allowable  $CBOD_5$  discharge from equation (3) is 684 #/d. This compares well with the value computed from the 7 day/10 year modeling detailed in the June 30, 1978, memorandum, which is as follows:

1407 #/d	UOD
- 330 #/d	NOD ***
<u>1077 #/d</u>	UCBOD
$\div 1.25$	ratio of UCBOD to $CBOD_5$
<u>861.6</u>	
-20%	reserve
<u>690 #/d</u>	allowable $CBOD_5$ discharge

*** Doswell:	20 mg/l TKN x .25 x 4.5 x 1.0 x 8.34 = 188 #/d
BATO :	10 mg/l TKN x .25 x 4.5 x 1.5 x 8.34 = 140 #/d
	<u>328 #/d</u>

The 6 #/d difference is the result of not including  $Q_w$  in the wastewater-river mass balance when establishing the 7.2 mg/l mix concentration.

Another item discussed with the EPA personnel was the location of stream flow measurement. The State Water Control Board (previously the USGS) maintains a gaging station on the North Anna River at the Route 1 bridge (approximately 8 miles above the discharge point.) At the suggestion of EPA, it was agreed that this gage would provide the most reliable stream measurement. It should be noted that by measuring stream flow at this point, some additional conservatism is added to the control equation (i.e.; use of this measurement excludes a segment flow of 0.45 cfs between the gage and the discharge point, and the Little River at 1.77 cfs, both flows being 7 day/10 year low flows; the conservatism is a result of the fact that these flows were included in the derivation of Equation (3)).

One final item discussed with the EPA was statement number 4 on page 5 of the June 19, 1978, memorandum. There is some difference of opinion concerning the direction of change of  $K_2$  once the model enters the Pamunkey River. In any event, the present modeling used a  $K_2$  computed in accordance with Appendix F.

In accordance with the revised low flow allocation generated in accordance with the 303(e) Plan methodology as described above, it is proposed to modify the York River Basin 303(e) Plan to show a 7 day/10 year low flow allocation of 690 #/d  $BOD_5$ . This figure accounts for a 20% reserve assimilative capacity and an NOD of 330 #/d. The ultimate oxygen demand would be 1407 #/d.

ntp

Attendees - 6/28/78 Meeting on Hanover Co.

Phil Senghorin

Charles App

- by Hodgkiss

Stuart Kerzner

Michael Zickler

Paul E Ambrose

Wesley D. Jones

Fay R. Jenkins, Jr.

James Combs

H

Stan Siskowski

EPA III - Eff 597-8211

EPA III - Water Planning 597-8323

EPA III - Enforcement 597-2945

EPA III - Water Planning 597-3847

" ENFORCEMENT 597-2726

EPA III ENFORCEMENT 597-2459

VSNCR 804-897-0056

DR. J. L. B. - PRO 804-257-121

Roy F. Weston 804-277-405

Recent evidence reported in the literature indicates that<sup>1</sup> nitrogenous BOD demand occurs in all parts of a river system. The ultimate nitrogenous BOD was calculated stoichiometrically, and each segment of the basin was assigned a percentage of ultimate nitrogenous BOD as follows, to reflect the detention time available for the BOD to take effect:

- Headwaters - 25%
- Tidal/Non-Tidal Interface 50%
- Tidal - 100%

Maximum daily loads for any stream segment depend on its flow and on the location and magnitude of point discharges. Lake Anna will change the low-flow conditions in the downstream portion of the North Anna River and in the Pamunkey River. Then the assimilative capacity of the rivers will be much greater because supplemental water discharged from the lake can maintain a higher level of stream flow, and, therefore, the rivers can accommodate higher maximum daily loads. The maximum daily loads for all segments are presented in Table IV-2.

#### C. Identification and Location of Water Quality Violations

##### 1. Dissolved Oxygen (DO) Problems

Water quality violations were identified by applying BPCTCA (1977) levels of treatment (obtained from EPA effluent guidelines) and the Virginia water quality standards (Appendix D) to point source discharges. The Virginia standard for DO is a minimum of 5.0 mg/L, and State policy on non-degradation limits the DO decrease to 0.2 mg/L. Water quality conditions were modeled to determine assimilative capacities of major streams in the York System. A summary of assumptions made for this modeling effort is presented in Appendix F. The results of the selected alternatives are depicted in Figures IV-3 through IV-7.

##### a. South Anna River

Figure IV-3 presents the dissolved oxygen profile for the South Anna River under 1977 loading conditions. The treatment plants in the headwaters (Gordonsville and Louisa-Mineral) are required to provide 92 and 93 percent carbonaceous BOD removal. The high degree of removal is necessitated by the relatively low stream flow and the correspondingly low assimilative capacity of the headwaters.

<sup>1</sup>"Zones of Nitrification", T. J. Tuffely, J. V. Hunter and V. A. Matulewic, AWRA, Volume 10, No. 3, June 1974

All fecal coliform contamination in the lower York River Basin cannot be attributed to traditional sources. Chesapeake Corporation may be discharging organisms that have been identified as fecal coliform. It is possible that this may be due to organism misidentification, and Chesapeake Corporation has contracted with VIMS to determine this possibility. The results of this study could have significant impact on condemned shellfish areas.

Although no loading reduction has been established for Contrary Creek, an abatement program is being implemented to reduce the Creek's acid mine drainage. This program includes the following:

- Restore and regrade surrounding areas to minimize erosion and remove tailing piles.
- Mix soil with limestone, appropriate fertilizer, and digested sludge.
- Seed the entire area to establish a vegetative cover.
- Dredge Contrary Creek.
- Develop a monitoring program, involving:
  - Continuous flow at selected locations.
  - Grab samples at selected locations (including Lake Anna) for analysis of heavy metals.

The influence of salt marsh discharges is clearly illustrated in the DO profile for the Pamunkey River (Figure IV-6). This water quality segment was modeled under 1977 loading conditions with zero discharge from all point sources. The conclusions were that this segment is water quality limited by natural causes and that the discharges of Chesapeake Corporation and of the proposed Hanover County regional treatment plant will have little effect on water quality in this segment.

#### G. Allocation of Reduction Responsibilities

No specific loading reductions are required for any segment in the York River Basin.

#### H. Assignment of Effluent Limitations

During the course of this study, the rivers, streams, and creeks were analyzed to determine waste load assimilative capacities. Recommendations for 1977 waste loads are based on the magnitude of waste load at each significant point



source required to maintain high quality water. Twenty percent of that load has been set aside as a reserve wherever possible.

Table IV-5 shows the recommended effluent limitations in terms of BOD<sub>5</sub> and Ultimate BOD. The first column is the waste load allocation for 1977; these waste discharges were used to establish the existing water quality, which was defined as that resulting after the 1977 effluent limitations were applied.

The maximum daily load allocations were determined by calculating the magnitude of the daily load beyond the 1977 baseline load that could be added without decreasing the D<sub>0</sub> at the sag point more than 0.2 mg/L (the state policy on non-degradation). The recommended allocation is 80% of the maximum (wherever possible), which reserves 20% as a safety factor. Required removal efficiency to meet the maximum daily load by 1995 is also provided.

TABLE IV-5  
WASTE LOAD ALLOCATIONS (IN LBS PER DAY)

POINT SOURCE	1977 WASTE LOAD <sup>2</sup>		MAXIMUM DAILY LOAD		RECOMMENDED ALLOCATION			RAW WASTE LOAD AT 1995		REQUIRED % REMOVAL EFFICIENCY 1995	
	CBOD <sub>5</sub>	UBOD <sup>1</sup>	CBOD <sub>5</sub>	UBOD	CBOD <sub>5</sub>	UBOD	PERCENT RESERVE	CBOD <sub>5</sub>	UBOD	CBOD <sub>5</sub>	UBOD
Gordonsville	145	398	150	412	150	412	0	1950	2730	92	85
Louisa-Mineral	50	108	55	118	55	118	0	850	1150	93	90
Doswell	52	110	250	417	200	334	20	1080	1444	85(4)	71
Thornburg	63	150	68	162	68	162	0	1240	1690	94	90
Bowling Green	27	64	29	68	29	68	0	680	926	96	93
Ashland	160	303	235	559	183	447	23	2250	3825	92	88
Hanover (Regional STP)	170	437	280	820	280	820	0	5730	7930	96	90
Chesapeake Corp.	6400	8000	6170 <sup>5</sup>	7710 <sup>5</sup>	6170 <sup>5</sup>	7710 <sup>5</sup>	N/A	51700	64630	90	90
West Point	105	380	281 <sup>3</sup>	1020	225	814	20	1000	1600	85 <sup>4</sup>	66
York & James City SD #1	213	641	2630 <sup>3</sup>	7843	2100	6270	20	4480	6780	85 <sup>4</sup>	72
American Oil	406	1360	73 <sup>5</sup>	245	73	245	N/A	4620	6630	96	98
York Regional STP	2280	9230	10000 <sup>3</sup>	40900	8010	32700	20	26900	44900	85 <sup>4</sup>	67

<sup>1</sup> UBOD is Ultimate Biochemical Oxygen Demand. Its concentration is derived by the following:  $80D_5/0.80 + 4.5$  (TKN) = (UBOD)  
NOTE: The amount of TKN utilized depends on the location in the basin.

<sup>2</sup> Projected for 1977 based on population projections.

<sup>3</sup> Recommended allocation based on BPTCA effluent guidelines applied to raw waste loads at 2020.

<sup>4</sup> Minimum removal efficiency.

<sup>5</sup> Allocation based on BATEA Guidelines at 2020.

<sup>6</sup> Based on assumed influent characteristics.

APPENDIX F: CALCULATION OF ASSIMILATIVE CAPACITY AND WASTELOAD ALLOCATIONS  
FOR OXYGEN-DEMANDING MATERIALS IN NON-TIDAL AND TIDAL STREAMS

1. Non-Tidal

In the modeling of all non-tidal streams, a modified Streeter-Phelps oxygen-sag model was used for both carbonaceous and nitrogenous oxygen-demanding materials. The basic equation utilized in the simulation may be written as:

$$D = \frac{E_1 L_a}{K_2 - K_1} (e^{-K_1 t} - e^{-K_2 t}) + D_a e^{-K_2 t}$$

where D = oxygen deficit at time t (mg/l)

D<sub>a</sub> = oxygen deficit at origin, where t = 0 (mg/l)

L<sub>a</sub> = ultimate oxygen demand in stream at origin (mg/L)

K<sub>1</sub> = log base e deoxygenation coefficient

K<sub>2</sub> = log base e reaeration coefficient

t = time of travel from origin

K<sub>2</sub> values for all streams were calculated using critical low-flow stream depths and velocities, and K<sub>1</sub> was chosen to conform to a typical sanitary waste and to provide the most reasonable fit to existing stream dissolved oxygen data. It must be emphasized that, in all cases, existing stream data were minimal with respect to water quality, and the modeling parameters used must be regarded as best available estimates which may be considered adequate only for purposes of interim planning. Further explanation of the model components is presented in the following paragraphs.

a. Ultimate Biochemical (Carbonaceous) Oxygen Demand (UCBOD)

The amount of ultimate CBOD discharge is calculated by multiplying reported BOD<sub>5</sub> loadings by 1.25 or by the following equation:

$$\text{UCBOD (lbs/day)} = \frac{\text{Effluent BOD}_5 \text{ concentrations (mg/l)} \times \text{flow (mgd)} \times 8.34}{0.8}$$

b. Ultimate Nitrogenous Oxygen Demand

Ultimate nitrogenous oxygen demands (UNOD) are calculated stoichiometrically as follows:

$$\text{UNOD (lbs/day)} = \text{effluent TKN concentration (mg/l)} \times \text{flow (mgd)} \times 4.5 \times 8.34$$

Wherever the effluent concentration of TKN is not available, 20 mg/L is used as the effluent concentration unless otherwise indicated.

c. Ultimate Oxygen Demand

The ultimate oxygen demand at the point of discharge is equal to the sum of ultimate carbonaceous biochemical oxygen demand and nitrogenous oxygen demand.

d. Non-Point Source Contribution

In general, non-point sources of oxygen demanding material are not adequately defined and must at present be considered as a background dissolved oxygen deficit. In the absence of actual stream water quality data, values between 1.0 and 2.0 mg/L were used.

e. Waste Load Distribution

In the process of evaluating stream assimilative capacity, it is necessary to determine the decay of waste loads from all points of discharge as materials flow downstream. For any given segment this may be expressed as follows:

$$L = L_o \exp (-K_1 t)$$

where  $L_o$  = ultimate oxygen demand at the upstream end of the segment

$K_1$  = coefficient of deoxygenation at the ambient stream temperature

$t$  = average time of travel to the point of application in the segment at the 7-day, 10-year average low-flow conditions

f. Critical Low Flow

The 7-day average low flow with a 10-year return period was used for analysis. Annual low-flow series for Virginia were obtained from USGS gaging station records. For segments lacking a gaging station, the critical flow was obtained based on known drainage basin areas and geologic considerations.

g. Velocity and Depth

Stream hydraulic characteristics were estimated from maps and field data, since stream sampling and geometry data were not available.

h. Temperature

In this study, the temperature used in modeling the non-tidal stream segments is 25°C. Statistical analysis showed 25° to be the critical temperature.

i. DO Saturation

Dissolved oxygen concentrations at saturation used in these computations are taken from the table of saturation values found in "Standard Methods for the Examination of Water and Wastewater", 13th edition.

j. Deoxygenation and Reaeration Rate

The deoxygenation rate,  $K_1$  is estimated by the discharged waste characteristics. Further refinement in  $K_1$  is not justified on the basis of existing data. The above rate is considered to be an appropriate average for both carbonaceous and nitrogenous materials within the context of this study.

The reaeration rate  $K_2$  is estimated from the O'Connor-Dobbins formula. It is based on estimated hydraulic depths and velocities. Generally,  $K_2$  values have a higher level of confidence than  $K_1$  values in this study.

Both  $K_1$  and  $K_2$  are corrected for ambient stream temperatures according to the relationships:

$$K_1 = K_{1_{20^{\circ}}} (1.047)^{T-20}$$

$$\text{and } K_2 = K_{2_{20^{\circ}}} (1.024)^{T-20}$$

where  $K_1, K_2$  = corrected rate constants ( $\text{day}^{-1}$ )

$K_{1_{20^{\circ}}}, K_{2_{20^{\circ}}}$  = estimated rate constants at  $T = 20^{\circ}\text{C}$  ( $\text{day}^{-1}$ )

$T$  = Ambient Stream Temperature ( $^{\circ}\text{C}$ )

## k. Stream Assimilative Capacity

A discussion of stream assimilative capacity is given in Chapter IV. Calculation of the assimilative capacity of each reach is based on the definition of the maximum upstream loading required to allow the stream to meet the specified dissolved oxygen criteria at each critical point (minimum points on the dissolved oxygen versus river mile curve). Since downstream conditions depend on the distribution and magnitude of all upstream discharge points, the calculated assimilative capacity (CAC) was first calculated for the upstream reaches and proceeded downstream. The magnitude and location of all point sources were accounted for in these calculations.

### 1. Waste Load Allocations

Using the calculated assimilative capacity (CAC), the recommended waste load allocation was calculated according to the expression:

$$\text{Waste load allocation (BOD)} = 0.8 (\text{CAC})$$

If the projected 1977 BOD<sub>5</sub> load to the segment is less than the target load, allocation is required. Allocations are normally made in terms of BOD<sub>5</sub>. However, an option for negotiation between the discharger and regulatory agencies for increasing BOD<sub>5</sub> discharge allocation in return for reducing ultimate biochemical oxygen demand may be considered.

### 2. Tidal Model

The dissolved oxygen in the tidal estuaries of the York River Basin was simulated with the use of a one-dimensional, non-steady state model developed by VIMS. This model is based on the finite element method of volume integration. It has been developed for the Virginia State Water Control Board for the specific purpose of serving as a planning and management tool in the analysis of river systems.

The model covers the physical area of the tidal portions of the Pamunkey and the Mattaponi, as well as the York estuary itself. The input data necessary for the tidal model is extensive. The main program requires the total drainage area, tidal cycles, time increments, weighting factor for advection of sea salt, Manning's roughness factor for each section, etc. In addition, sub-routines require extensive data. Fortunately, through cooperation with VIMS staff, the input requirements for this study were reduced to changes in the loadings typified by various alternatives.

One limitation of the VIMS model is its average DO predictions in the area below the Yorktown Bridge. In this area, the assumption of one-dimensionality is invalid. Significant density stratification, as well as vertical and horizontal variations, mandate a three-dimensional model. Such an effort is presently underway at VIMS. However, for the present study, the resulting dissolved oxygen values obtained in this area from the VIMS model were used to determine relative impacts. The absolute levels of dissolved oxygen in this area were obtained from a model recently completed as part of a 201 Facilities Plan for the Hampton Roads Sanitation Commission. Both models predicted little impact on water quality from point source discharges in the area below the Yorktown bridge.

# MEMORANDUM

## State Water Control Board

2111 North Hamilton Street

P. O. Box 11143

Richmond, VA. 23230

SUBJECT: Proposed Discharge to North Anna River, Hanover County

TO: W. D. Jones

FROM: K. C. Das *K. C. Das*

DATE: June 30, 1978

COPIES: D. F. Jones, J. J. Cibulka, D. B. Richwine, J. K. Bailey, R. R. Jenkins,  
C. T. Bathala

In accordance with your suggestion, I am summarizing here below the results of the analysis relative to the proposed discharge into North Anna River. The methodology used herein is in keeping with the procedures as outlined in the York River Basin 303(e) Plan (Appendix F).

The 7-day, 10-year low flow was computed in the manner indicated below:

The drainage area at the dam site is 343 sq.miles. (Ref: App. C-York Plan)  
The drainage area between the dam site and the outfall is 127 sq.miles. This dam will release a minimum drought flow of 40 cfs. The contribution due to an additional 127 sq.miles is 1.9 cfs based on a drought flow rate of 0.015 cfs/sq.mile. The Little River contributes 1.77 cfs at the discharge point which is based on a drainage area of 118 sq. miles. (See attached letter)

The reaeration rate was computed using O'Connor-Dobbins equation (see Appendix F of the 303(e) Plan). Using an average velocity of 0.5 fps and an average depth of 3 ft., a reaeration rate of  $1.76 \text{ day}^{-1}$  (base e,  $20^{\circ}\text{C}$ ) was obtained. An average depth of 3 ft. was assumed to reflect summer low flow conditions in the North Anna River. We have used the deoxygenation rate of  $0.23 \text{ day}^{-1}$  (base e,  $20^{\circ}\text{C}$ ). The same  $K_1$  rate was used for discharge into South Anna River by Roy Weston. A temperature of  $29^{\circ}\text{C}$  was used for the analysis which reflects the highest temperature recorded at the Rt. 30 Bridge on August 17, 1977 (see attached memo). The DO of the effluent is assumed to be 6.5 mg/l which is in agreement with the present NPDES permit limits. The results are summarized in Table 1.

If you have any questions concerning this matter, please let me know.

SW

Attachments



TABLE 1

<u>Parameters</u>	<u>Proposed Discharge to North Anna River</u>	<u>Source of Information</u>
<u>Stream Characteristics</u>		
Receiving Stream	North Anna River	North Anna River
7/10 Low Flow Upstream of Outfall (cfs)*	43.68	
Stream Velocity (fps)	0.5	**
Background DO (mg/l)	6.82	
Critical Water Temperature (°C)	29	PRO
Background BOD (ultimate) (mg/l)	1.88	**
<u>Reaction Rate Constants</u>		
K <sub>1</sub> Deoxygenation (Base e, 20°C)	0.23	**
K <sub>2</sub> Reaeration (Base e, 20°C)	1.76	**
<u>Allowable Effluent Limits</u>		
Effluent Discharge (mgd)	2.5	
DO <sub>eff</sub> (mg/l)	6.5	
BOD (ultimate) (mg/l)	67.5	
BOD (ultimate) (lbs/day)	1407.0	

---


$$\text{BOD (ultimate)} = \text{CBOD (ultimate)} + \text{NBOD (ultimate)}$$

\* 7-Day, 10-Year Low Flow = 41.91 (North Anna) + 1.77 (Little Creek) = 43.68 cfs

\*\* Information gathered via telephone conversation with Kevin Phillips of Roy Weston by PRO staff. This information was used for Pamunkey and South Anna Rivers.

# Associated Engineers

ENGINEERS • SURVEYORS • PLANNERS

STATE WATER CONTROL BOARD

JAN 8 1973




Post Office Box 5189

Ashland, Virginia 23005

Phone (A/C 703) 798-5773

January 8, 1972



State Water Control Board  
P. O. Box 11143  
Richmond, Va. 23230

Attn: Mr. C. L. Jones

Dear Mr. Jones;

We are preparing a preliminary proposal submittal for a waste treatment facility to serve the community of Doswell, Va. and the Kings Dominion Amusement Park which is now under construction.

In this regard we would like to request from you the degree of treatment that will be required for this installation.

We are enclosing a data sheet and location map for your use in making your determinations.

The aforementioned amusement park is scheduled to open on April 1, 1975 and will require sewerage services approximately 6 months prior to opening. We would, therefore, appreciate your requirements and recommendations as soon as scheduling will permit.

If additional information is needed or elaboration required on the attached data please contact us at any time.

We appreciate your assistance in this matter.

Sincerely,

William F. Goodfellow, P. E.  
Associated Engineers

cc: Mr. Norman Phillips, S.H.D.


WFG/mfh

1/12/73  
C.L.

ROSEMILL WASTE TREATMENT FACILITY

DATA SHEET

- A. Plant Location- Lat 37° 49' 51", Long 77° 25' 43", on the northwest bank of the confluence of the North Anna and Little Rivers. (See Attached Sketch).
- B. County of Facility- County of Hanover.
- C. Plant Design Discharge- 1. Initial Stage - 0.5 MGD  
2. Ultimate Stage - 2.0 MGD
- D. Receiving Stream- North Anna and Little Rivers (Tributaries to York River)
- E. Stream Particulars- 1. Drainage area at discharge point is 589 square miles (118 sq. mi. from Little River and 471 sq. mi. from North Anna River.  
2. Vepco's North Anna Dam, located 29.7 miles upstream, will release a minimum drought flow of 40 CFS. Drainage area between the dam and discharge point is 127 square miles.  
3. Jarrell's Truck Stop, located at U. S. Route 30 and I-95, is currently operating a waste treatment facility (sewage lagoon) which will be obviated by the County plant.
- F. Other Data- A water treatment facility of equal design capacities will be constructed concurrently with the waste treatment plant and will be located approximately 1200 feet upstream.



# MEMORANDUM

## State Water Control Board

2111 North Hamilton Street

P. O. Box 11143

Richmond, VA. 23230

SUBJECT: Choosing Flow and Temperature Values for Modeling the North Anna River for the Doswell STP Discharge

TO: File

FROM: Joyce L. Hoyle

DATE: May 23, 1978

COPIES:

The seven-day, ten-year low flow recorded at the gage on the North Anna River is 6.5 cfs (0.015 cfs/sq.mile), but this is augmented by 40 cfs from the dam. This makes the total flow above the discharge 46.5 cfs.\*

The closest USGS water quality gage is on the Pamunkey River near Hanover. The monthly average temperatures for the months of May through September are shown below for the period of record.

### AVERAGE MONTHLY TEMPERATURE (°C)

Station: Pamunkey River near Hanover (01673000)\*\*

<u>Year</u>	<u>May</u>	<u>June</u>	<u>July</u>	<u>August</u>	<u>September</u>
1975	19.5	25.0	25.5	25.5	22.5
1974	19.5	22.5	-	25.5	21.0
1973	19.5	23.0	25.5	27.0	24.5
1972	18.0	21.5	24.0	23.5	21.0
1971	17.5	22.5	25.5	25.0	21.0
1970	21.3	23.3	26.2	26.3	23.7
1969	19.0	23.0	25.0	24.0	-
1968	16.0	22.0	-	25.0	19.0

(-) Incomplete Data.

\*\* Source: Water Resources Data for Virginia (1968-1975).

\* See Page 56 of the York River Basin Plan.

Memorandum to File

Choosing Flow and Temperature Values for Modeling the North Anna River  
for the Doswell STP Discharge

Page 2

May 23, 1978

A glance at the table above will show that  $27^{\circ}\text{C}$  was the highest monthly average temperature. The highest instantaneous temperature recorded was  $28^{\circ}\text{C}$ .

There are six ambient monitoring stations on the North Anna River in Hanover County. Ambient monitoring only records instantaneous temperatures. The highest temperature recorded at any of these stations is  $29^{\circ}\text{C}$  at the Route 30 bridge on August 17, 1977. Since the temperature of  $29^{\circ}\text{C}$  was actually recorded in the North Anna River under conditions of fairly low flow, I suggest using  $29^{\circ}\text{C}$  for modeling.

SW

# MEMORANDUM

## State Water Control Board

2111 North Hamilton Street

P. O. Box 11143

Richmond, VA. 23230

~~JKB~~  
*ref*

SUBJECT: Amendment of Doswell NPDES Permit VA0029521

TO: File (42-0525)

FROM: S. S. Waldo and R. R. Jenkins *Ray Jenkins*

DATE: June 19, 1978

COPIES: L. G. Lawson, J. J. Cibulka, W. D. Jones, Dale F. Jones,  
60-0033

By letter dated April 7, 1978, John E. Longmire, Hanover County Administrator, transmitted a permit amendment request for the Doswell Wastewater Treatment Plant. The permit amendment request reflected the discharge of treated wastewater from the proposed Bato plant. The amendment request was updated by a letter dated April 28, 1978 and completed by correspondence with transmittal dates of May 8, 1978 and May 26, 1978. Mr. Longmire requested that the Board consider a tiered permit to take into account increased assimilative capacity in the stream during the periods of high flow in the North Anna River (other permits incorporating this concept have been written in the State, although this is the first permit that incorporates an "instantaneous" correlation between river flow and discharge).

The staff has investigated the feasibility of a tiered permit concept for the Doswell permit. In that an allocation for Doswell is already included in an adopted 303(e) plan (York River Basin), the original intent of the investigation was to preserve all parameters used in the adopted allocation modeling. By retaining the original inputs, the generation of tiered levels of discharge does not constitute remodeling, but only a recalculation using the existing model. Subsequently, it was discovered that an obvious error had been made in the original allocation. The original modeling in 1973 resulted in an allowable discharge of 400 lbs/day at 2 MGD wastewater flow. But when Hanover County decided to build only a 1 MGD treatment plant, this 400 lbs/day was simply halved to obtain an allocation of 200 lbs/day. In addition, it was determined that the river temperature used in the modeling and the 7-day/10-year low flow used were incorrect. It was then decided that the errors would be corrected and appropriate revisions to the 303(e) plan proposed. These revisions were to change the stream temperature (29°C instead of 32.2°C) and to revise the flow (46.5 cfs\* instead of 42.4 cfs for the North Anna River at 7-day/10-year low flow). No other changes were made; i.e., rate coefficients selected at 20°C in the original modeling ( $K_1^* = 0.13$ ,  $K_2^* = 0.68$ ),  $UBOD^*/BOD_5^*$  ratio(1.3),

\*Terms: cfs = cubic feet per second  
 $K_1$  = deoxygenation rate  
 $K_2$  = reaeration rate  
UBOD = ultimate biochemical oxygen demand  
BOD<sub>5</sub> = 5-day biochemical oxygen demand

File No. 42-0525

Page 2

June 19, 1978

etc. remain the same. The resulting calculations were run precisely in accordance with the procedure previously used in the 303(e) allocation, with the exception of the temperature change and flow change mentioned above and discussed more fully below. Thus the basic modeling remains unchanged. All inputs to the modeling equation were those determined for the seven-day/ten-year low flows; the inputs were not adjusted at increased river flows. Fixing these factors keeps the calculations more conservative (i.e., increases the "safety factors")

The original modeling used a stream temperature of  $32.2^{\circ}\text{C}$ . This temperature was taken directly from the Water Quality Standard for a Class III stream (i.e.,  $90^{\circ}\text{F} = 32.2^{\circ}\text{C}$ ). This methodology of choosing a stream temperature was used only for a short time by the Board and since then the ambient temperature, as measured instream, has been used exclusively. For the North Anna River this temperature was determined to be  $29^{\circ}\text{C}$ , which is the maximum temperature observed.

The original modeling used a critical flow in the North Anna River of 42.4 cfs. An investigation of stream flow for the North Anna River has determined that, in fact, the critical flow is 46.5 cfs. This is based on a guaranteed release from Lake Anna of 40 cfs and a "stretch" flow in the drainage area between the lake and the Doswell gaging station of 6.5 cfs. The use of the corrected values for river temperature and flow more precisely reflect actual conditions in the stream.

In making the calculations a simplification was made by letting the input variable to the modeling equation be the ultimate biochemical oxygen demand (UBOD) of the discharge-river mix (hereafter referred to as  $L_0$ ). This procedure was preferred to the more typical procedure of inputting various wastewater flow and concentration values.

When the temperature was corrected to  $29^{\circ}\text{C}$ , an additional simplification was made in the modeling. The existing Doswell permit requires a minimum dissolved oxygen (DO) level of 6.5 mg/l. At  $32.2^{\circ}\text{C}$ , the background river DO is also 6.5 mg/l. Therefore, at any wastewater volume-river volume mix, the DO of the mix is 6.5 mg/l. At  $29^{\circ}\text{C}$ , however, the background stream DO is 6.84 mg/l and the effluent DO is still 6.5 mg/l. Effluent volume now influences the DO of the mix and, therefore, influences the results of the modeling calculations. The simplification in the calculations was to input an initial DO of the mix of 6.8 mg/l. This value results from the mass balance of 4.0 MGD (in accordance with Hanover's amendment application for ultimate flows) of wastewater with a DO of 6.5 mg/l and a river flow of 49 cfs with a DO of 6.84, and should represent the lowest initial DO under any conditions (Note: The flow of 49 cfs includes 46.5 cfs from the North Anna River and the 7-day/10-year low flow of 2.5 cfs from the Little River, which enters the North Anna immediately below the discharge.). Since the effluent volume is small in comparison to total flow, this simplification impacts the results only slightly.

File No. 42-0425

Page 3

June 19, 1978

As a result of setting all of the foregoing parameters constant at "worst case conditions", the calculations were performed with only one variable - the UBOD of the discharge-stream mix ( $L_o$ ). It was then observed that by having fixed all other input values,  $L_o$  did not change with increased river flow when the same DO value at the "sag" was calculated. Using an  $L_o$  so determined, a mass balance equation is used to calculate the allowable discharge concentration for various wastewater and stream flows. The inputs to the calculations included the Little River at a 7-day/10-year low flow of 2.5 cfs and the South Anna River 3.7 miles downstream of the discharge at a 7-day/10-year low flow of 12.1 cfs. The UBOD background of the rivers was 3.0 mg/l ( $BOD_5 = 3.0/1.3 = 2.3$ ) and all stream velocities were 0.5 fps. The calculations indicated that the sag point occurred below the confluence with the South Anna River. The critical dissolved oxygen deficit of 0.96 mg/l (10% of D.O. saturation at 29°C, 0.76 mg/l, plus 0.2 mg/l, anti-degradation application for this case) occurred at an  $L_o$  of 5.5 mg/l.

When used as described above, the calculations indicate that the Board's anti-degradation policy will be met as long as a UBOD ( $L_o$ ) of 5.5 mg/l ( $UBOD/BOD_5 = 1.3$ ; therefore,  $BOD_5 = 4.2$  mg/l) is maintained in the mix of the stream and wastewater flow. Using this knowledge, an equation was developed which can be used to determine an allowable  $BOD_5$  discharge concentration at various stream flows. This equation was derived from the basic mass balance equation:

$$L_{mix} = \frac{Q_S L_S + Q_W L_W}{Q_S + Q_W}$$

Where:

$L_{mix}$  =  $BOD_5$  of the stream-wastewater mix

$Q_S$  = stream flow

$Q_W$  = wastewater flow

$L_S$  = background  $BOD_5$  in stream

$L_W$  =  $BOD_5$  of wastewater

• Using known values and calculating for  $L_W$ :

$$4.2 = \frac{Q_S (2.3) + Q_W L_W}{Q_S + Q_W}$$



File No. 42-0525

Page 4

June 19, 1978

or, in another form,

$$L_w = \frac{4.2 + 1.9Q_s}{Q_w} \quad \text{Equation (1)}$$

Use of this equation enables an operator or a regulatory agency to easily enter stream flow and wastewater flow to determine the allowable effluent BOD<sub>5</sub> ( $L_w$ ) which will maintain the State's water quality standards. At a wastewater flow of 2.5 MGD, which is the proposed start-up flow, and critical low flow of 49 cfs, the low flow allocation was determined to be 584 lbs/day. This low flow allocation will be one of the proposed changes to the 303(e) plan.

There is a requirement which is also controlling for this discharge. 40CFR133 limits domestic waste discharges to a concentration of 30 mg/l BOD<sub>5</sub> and total suspended solids (TSS). However, 40CFR133.103(b)(Secondary Treatment Definition: Industrial Waste) allows for an increase in the "secondary treatment" limitation of 30 mg/l for BOD and suspended solids in proportion to the industrial contribution to the total wastewater flow at the industrial wastewater concentration which would apply for an industrial point source discharge by that industry type. Since the Bato wastewater will be treated to levels of 50 mg/l BOD<sub>5</sub> and total suspended solids (which will be defined by the Board as "new source" discharge limitations for this industry), this concentration is used in the following mass balance equation to define an allowable discharge concentration for BOD<sub>5</sub> and total suspended solids:

$$\text{TSS or BOD}_5 (\text{mg/l}) = \frac{30Q_H + 50Q_B}{Q_H + Q_B} \quad \text{Equation (2)}$$

While the BOD<sub>5</sub> limitation is controlled by either Equation (1) or Equation (2), whichever is more stringent, Equation (2) is the only controlling equation for the total suspended solids discharge.

A maximum limitation has also been established for BOD<sub>5</sub> and total suspended solids quantity. This limitation is based on 1 MGD of Doswell wastewater at 30 mg/l BOD<sub>5</sub> and TSS and 3.0 MGD at Bato wastewater at 50 mg/l. The flow figures are in accordance with Hanover's amendment application. The appropriate quantity calculation gives a maximum allowable quantity discharge of 1500 lbs/day. This limit cannot be exceeded regardless of the value determined by Equations (1) or (2).

File No. 42-0525

Page 5

June 19, 1978

Before describing the actual proposed permit amendment, it is important to summarize the conservative factors which were used in the derivations of the above equations. These are listed below:

1. Segment flow (runoff, groundwater and small streams) was not included below the discharge point.
2. Stream velocity and other inputs to the calculation were set at critical low flow and were not changed with increased river flow.
3. A minimum initial mix DO of 6.8 mg/l was used instead of recalculating the mix at higher stream flows; recalculating would have the effect of slightly increasing the mix DO.
4. The rate of coefficients were not redefined below the confluence of the North and South Anna Rivers (deoxygenation coefficient would actually drop; reaeration coefficient would actually increase).

The investigators point out that these calculations assume a complete mix at the discharge. However, the point should also be made that this assumption is used in every "free flowing" modeling effort and is completely in accordance with prior modeling practices.

#### Permit Conditions

The proposed permit amendments were drafted in such a way as to maximize the use of Equations (1) and (2) above. This necessitated a unique permit in that BOD<sub>5</sub> and suspended solids limitations are not specifically placed in the permit. Each value must be calculated using Equations (1) or (2).

Because Equation (1) is geared towards an "instantaneous" correlation between river flow and discharge concentration, it was necessary to provide a shorter limitation period than a one month average, which is normal on most other permits. It was resolved that the BOD<sub>5</sub> and total suspended solids limitations will be reported as a weekly average of 7 calendar day values, and also that additional monitoring would be required to have an "instantaneous" correlation between BOD<sub>5</sub> and some other parameter (TOC\* or COD\*) to enable an operator to determine at any point in time with some degree of surety whether or not he is in compliance with the permit. The limitations included on the composite waste discharge (point source 001) are as follows:

\*Terms: TOC = Total organic carbon  
COD = Chemical oxygen demand

File No. 42-0525

Page 6

June 19, 1978

The BOD<sub>5</sub> limitation is referenced as paragraphs 4(a) through (d) in Part I, paragraph A-1 of the attached proposed amendments. 4(a) is a modification of Equation (1) listed above, which requires a weekly average. 4(b) does the same for Equation (2) above. 4(c) states that the more stringent of (a) and (b) above shall be the effluent BOD<sub>5</sub> concentration, except when flows are at 7-day/10-year low flow or less, at which time the more stringent of the following shall apply:

1. The maximum quantity allowable shall be no greater than 584 lbs (this is the waste load allocation which is proposed to be included in the 303(e) plan).
2. The concentration established by 4(b) above (which is the "secondary treatment" limitation).

4(d) states that the effluent BOD<sub>5</sub> quantity discharge shall not exceed 1500 lbs/day at any time.

Paragraphs 5(a) and (b) are the limitations for total suspended solids and are based on Equation (2) above modified to show a weekly average. 5(b) also limits the maximum quantity discharge at 1500 lbs/day.

Paragraph 6 is included to provide "real time" control over the amount of waste discharged. Because a lag time of 5 days is inherent in the BOD<sub>5</sub> test, it was realized that it was necessary to have some instantaneous determination of effluent quality for the operator to use in determining his allowable discharge. It was determined that this could be done best by a plot of TOC vs. BOD<sub>5</sub>, which would be updated using corresponding 24-hour composite samples of TOC and BOD<sub>5</sub> daily. This plot would be composed of data from a rolling 30 consecutive day period so that when a new data point is added, the oldest data point would be removed. Since it is possible that a plot of TOC vs. BOD<sub>5</sub> might not give the best correlation for these particular wastewaters, a special requirement was included in the proposed amendment which requires the permittee to also run COD tests on the same frequency as TOC to determine if COD would be a better correlation. At the end of the first six months of operation, the results will be evaluated to determine which parameter (i.e., TOC or COD) gives the closer correlation.

It is also necessary to place monitoring requirements on the separate waste streams coming into the combined outfall so that waste quality can be determined on each. These monitoring requirements are included as paragraph A-2 for Bato and paragraph A-3 for Hanover. Additionally,

Re: Amendment of Doswell NPDES Permit VA0029521

File No. 42-0525

Page 7

June 19, 1978

it was necessary to place a total chlorine residual limitation on the effluent from Hanover which is included in Paragraph A-3. The Bato waste stream does not include any sanitary waste (it is separately transported to the Doswell plant), thus, no chlorination is required. The permit requires that a plot of TOC vs. BOD<sub>5</sub> will be developed for each of these waste streams so that an operator can determine immediately the approximate quality of either waste stream.

Because of the special nature of the effluent limitations for this plant, it was necessary to develop a new reporting form also. This form is attached to the memorandum. The form includes spaces for entering all parameters which will be necessary to calculate the BOD<sub>5</sub> and total suspended solids limitations and for reporting actual final discharge values of BOD<sub>5</sub>, total suspended solids, pH, and dissolved oxygen (and total chlorine residual for the Doswell waste stream). In addition, a report form for the TOC, COD, and BOD<sub>5</sub> data used to develop the correlation plot is also included as an attachment.

Because the BOD<sub>5</sub> and total suspended solids limitations are based on a calendar week average, it was necessary to address this fact in the development of the monitoring report form. Paragraph 7 of Part I, A-1, states that if any month ends in an incomplete calendar week, the report for that week shall be included in the following monthly reporting period. For that reason, the report form has spaces for five weeks on it realizing that during some months there will only be three calendar weeks filled out and in others there will be five. Beyond these special reporting requirements the monitoring report form contains all the information required and included in the standard DMR format currently used in other NPDES permits, including a space for bypass and overflow information and a signature block.

The remainder of the permit shall be made up of standard pages, therefore, no discussion of those conditions is included here.

Any questions concerning the development of this proposed permit should be directed to the writers or Wesley Jones.

/pc  
Attachments

**Attachment 10**

## F. LAKE LEVEL CONTINGENCY PLAN


The intent of this condition is to allow specific reductions in the lake discharge flow when the lake water level drops below designated levels due to drought conditions, taking into account and minimizing any adverse effects of any release reduction requirements on downstream users.

1. Except as provided in 2. below, the permittee shall at all times provide a minimum instantaneous release from the Lake Anna impoundment of 40 cfs.
2. When the level in Lake Anna reaches 248 feet above mean sea level (msl), the permittee will begin reducing releases below the 40 cfs minimum in accordance with the following conditions:
  - a. Minimum instantaneous releases shall not drop below 20 cfs.
  - b. The Water Compliance Manager of DEQ's Piedmont Regional Office and the downstream users identified below will be given at least 72 hours notice by the permittee prior to the initiation of flow reductions:
    - ◆ Hanover County Public Utilities
    - ◆ Bear Island Paper Company
    - ◆ Engel Farms, Inc
    - ◆ Pamunkey Indian Tribal Government
  - c. Skimmer gate adjustments will be performed in accordance with Station Operating Procedures.
  - d. Releases shall be stepped down in increments of approximately 5 cfs with at least a 72-hour period following each incremental reduction and prior to any subsequent reduction.
  - e. During the period in which releases are reduced below 40 cfs, conditions in the North Anna River shall be monitored in accordance with the monitoring plan submitted by the permittee and approved by the DEQ prior to implementation of the Lake Level Contingency Plan.
  - f. Releases from the dam shall return to 40 cfs upon the Lake level returning to greater than 248 ft. msl. Increases of flow will occur in 5 cfs increments with a 24 hour wait period prior to the next gate adjustment.
  - g. If any downstream user identifies an adverse effect at any time during flow reductions and notifies the DEQ of the adverse effect, the Director shall make a timely investigation. If after notice to the permittee and the affected downstream users the Director finds an adverse effect from the flow reductions, the flows shall be increased in 5 cfs increments with a 24 hour wait period prior to the next gate adjustment, until the flow reaches 40 cfs or the Director finds that the adverse effect has been eliminated.
  - h. Adverse effect is defined as the inability to withdraw/discharge water for proper operation of facilities, or impairment of water quality.

**Attachment 11**

WATER QUALITY MODELING  
NORTH ANNA AND PAMUNKEY RIVERS  
YORK RIVER BASIN, VIRGINIA

Prepared for:  
Bear Island Paper Company  
Ashland, Virginia



HDR Project Number 317-10-35

Prepared by:  
HDR Infrastructure, Inc.  
6400 Fairview Road  
Charlotte, North Carolina

January 1988



TABLE OF CONTENTS (continued)

	<u>Page</u>
7.0 1987 MODEL SIMULATIONS.....	83
7.1 General Approach.....	83
7.2 Oxygenation of Effluent.....	84
7.3 Deaeration Under Supersaturated Conditions.....	87
7.4 Model Simulation.....	89
8.0 PROPOSED NPDES CRITERIA.....	99
8.1 Allowable CBOD.....	99
8.2 Oxygen Addition.....	105
REFERENCES.....	111
APPENDICES	
A. NPDES Permit	
B. Field Sampling Plan and Quality Assurance/Quality Control Document	
C. River Channel Profiles	
D. Stream Gaging and Velocity Calculations	
E. Laboratory Water Quality Analytical Reports	
F. In-Situ Sediment Oxygen Demand in North Anna and Pamunkey Rivers	
G. Literature Review of Sediment Oxygen Demand in Rivers and Streams	
H. 7Q10 Low-Flow Information	
I. Computer Model Output	
J. Development of TKN Design Wasteload	
K. Historical Water Temperature and Flow	
L. Analysis of Biodegradable TKN Fraction	
M. Selected Papers on Post-Aeration of Effluent and Deaeration Under Supersaturated Conditions	

## ANALYSIS OF BIODEGRADABLE TKN FRACTION

Prepared for

Bear Island Paper Company and Hanover County, Virginia

### INTRODUCTION

The Bear Island Paper Company operates a TMP pulp and paper mill in Ashland, Virginia. Wastewater from the mill is treated on site and is discharged into a national pollutant discharge elimination system (NPDES) regulated outfall (NPDES #VA0029521) controlled by Hanover County, Virginia. The NPDES permit was renewed in October 1985, and, as part of that renewal, the effluent standard was modified.

The previous permit had not been regulated for either ammonia or total kjeldahl nitrogen (TKN). An effluent TKN limitation of 6 mg/l was implemented as part of the permit renewal. The TKN limitation was imposed to control oxygen utilization in the receiving stream. The TKN oxygen utilization was based on 4.5 mg of oxygen per mg TKN.

The use of the TKN limit in the final October 1985 NPDES permit was a last minute alteration of the draft (as a draft of the permit had previously been based on ammonia). The assumption made by Hanover County and Bear Island Paper Company (BIPCO) in accepting the TKN limit was that the only TKN in the effluent would be in the form of ammonia nitrogen. The long-term wastewater treatment plant data had indicated that a discharge of less than 6 mg/l ammonia could be achieved. Therefore, the 6 mg/l TKN limit was thought to be an acceptable limitation.

In the final NPDES permit issuance, the State had a provision for the substitution of the ammonia limit for the TKN limit. However, any such

substitution would require approval from the State Water Control Board (SWCB) staff.

Subsequent to the implementation of the revised permit, it has been found that the combined effluent consistently exceeds the 6 mg/l TKN limitation. However, the discharge has been in compliance with the 6 mg/l ammonia limitation.

HDR was retained in 1986 to evaluate this situation. A preliminary analysis was conducted which indicated that a significant portion of the TKN in the Bear Island wastewater was non-biodegradable and the use of a theoretical TKN oxygen utilization would not be correct. The program to determine oxygen utilization of the waste was conducted utilizing inhibited and noninhibited BOD analyses. The results of this program are presented in Table 1. This indicated that the TKN in the Bear Island wastewater did not exert the 4.5 mg/l oxygen demand.

Based on the results of the preliminary testing program, the Bear Island Paper Company, in conjunction with Hanover County, entered into a consent agreement with the State of Virginia. A primary objective of that consent agreement was to identify the biodegradable portion of the TKN in the BIPCO effluent.

The results of the biodegradation program are presented in this report.

#### BIODEGRADATION PROGRAM

The methodologies for conducting the biodegradation program followed the procedures which had been previously submitted to and approved by the SWCB. A copy of the procedure is presented in Appendix A. All samples were

TABLE 1  
SUMMARY OF TKN OXYGEN UTILIZATION  
BEAR ISLAND EFFLUENT

Sample Date	TKN (mg/l)	NH <sub>3</sub> -N (mg/l)	BOD <sub>20</sub> Inhibited (mg/l)	BOD <sub>20</sub> Uninhibited (mg/l)	TKN Oxygen Utilization $\frac{\text{mg O}_2}{\text{mg TKN}}$	Organic Nitrogen Oxygen Utilization $\frac{\text{mg O}_2}{\text{mg O-N}}$
May 9	10.92	0.17	31	40	0.82	0.75
May 14	6.97	0.21	24	29	0.72	0.58
May 19	12.35	3.30	73	73	0	0
May 22	1.29	0.07	49	51	1.55	1.30

collected by personnel from either BIPCO or Hanover County and all analyses were conducted by Environmental Laboratories, Inc. of Ashland, Virginia.

### BIODEGRADATION RESULTS

In order to determine the biodegradable portion of the TKN a series of flask tests were initiated. The first tests were set up with waste samples collected on July 14, 1987, (sulfonation being utilized) and the second set with samples collected on August 26, 1987, (TMP production with purchased Kraft). Tests were performed on both TMP with purchased Kraft and sulfonation wastewaters. Phase I consisted of sulfonation wastes and Phase II was comprised of the TMP with purchased Kraft.

The samples for analysis were prepared by combining the wastewater samples with dilution water and seed in accordance with the test procedure and were maintained in test flasks under an oxygen blanket. Samples from the TKN testing flasks were collected and analyzed every 10 days. A summary of the data from the individual flasks is presented in Appendix B.

The TKN biodegradability data for the tests are presented on Table 2. The results from the tests are plotted and are presented in Figures 1 thru 6. The analysis of the data indicates that the degradable portion on BIPCO wastewater and combined Doswell/BIPCO wastewater is very similar, i.e., 34 to 46% degradable TKN. Therefore, for the purposes of performing the water quality modeling, it is recommended that the analysis be based on 46% degradable and 54% nondegradable TKN.

TABLE 2  
TKN BIODEGRADABILITY

Phase	Sample	Initial TKN, mg/l	Final TKN, mg/l	% Degradable TKN	% Non-degradable TKN
I	BIPCO	4.76	3.17	33	67
	Doswell	5.82	1.15	80	20
	Combined	6.16	4.08	34	66
II	BIPCO	11.40	6.16	46	54
	Doswell	1.89	0.22	88	12
	Combined	9.25	5.76	38	62






Figure 1: Chronological Variation - Phase I BIPCO






Figure 2: Chronological Variation - Phase I Doswell






Figure 3: Chronological Variation - Phase I Combined




Figure 4: Chronological Variation - Phase II BIPCO






Figure 5: Chronological Variation - Phase II Doswell




Figure 6: Chronological Variation - Phase II Combined

## APPENDIX A

### Procedure for Analysis of Non-Biodegradable TKN

## PROCEDURE FOR ANALYSIS OF NON-BIODEGRADABLE TKN

### I. DILUTION WATER

Dilution water shall be prepared as described below:

Buffer solution prepared according to Standard Methods contains ammonium ion, which would add to the measured nitrogenous BOD. Instead of using that formulation, prepare buffer as follows:

- Add the following reagents to approximately 500 mg of distilled/deionized water and dissolve. Then make up to one liter in a volumetric flask.
- 15.7 g.  $K_2HPO_4$
- 24.1 g.  $Na_2HPO_4 \cdot 7H_2O$
- 11.1 g.  $KH_2PO_4$

This solution should have a pH of 7.2 as prepared.

- Dilution water should be prepared according to Standard Methods, but with substitution of the above buffer.

### II. SAMPLE PREPARATION

Prepare sample for analysis consisting of:

- A. 1000 ml mill final effluent.
- B. 500 ml dilution water.
- C. Add commercially available nitrifying seed to culture.

Note: All testing to be performed in duplicate and with a control consisting of glucose-glutamic acid and ammonium chloride.

### III. INITIAL ANALYSIS

Analyze mill final effluent for TKN,  $NO_2/NO_3-N$ , and  $NH_3-N$ .

Analyze dilution water for TKN,  $NO_2/NO_3-N$ , and  $NH_3-N$ .

Analyze combined sample for pH, TKN,  $NO_2/NO_3-N$ , and  $NH_3-N$ .


- IV. Place sample in 2000 ml flask (as shown in Attachment A), maintain flask at ambient laboratory temperature, maintain under an oxygen blanket for 40 days

- V. Prior to aeration, at days 2, 5, 10, 20, 30 and 40, remove 50 ml sample and check pH and dissolved oxygen. The pH will be maintained in the 6.5 to 8.5 range and the dissolved oxygen in excess of 2 mg/l. If, at day 2 or any time low pH and DO levels are found, these will be adjusted and more frequent sampling will be initiated. Do not return sample to flask.
- VI. Analyze sample at days 10, 20, 40, and conclusion for TKN,  $\text{NO}_2/\text{NO}_3\text{-N}$ , and  $\text{NH}_3\text{-N}$ . The conclusion of the test will be tied into the conclusion of the ultimate BOD test.
- VII. Non-biodegradable TKN percentage is defined as:

$$\text{TKN}_R = \frac{\text{TKN}_i - \text{TKN}_f}{\text{TKN}_i}$$

where:

$\text{TKN}_R$  = non-biodegradable TKN (Percent)  
 $\text{TKN}_i$  = initial TKN (mg/l)  
 $\text{TKN}_f$  = final TKN (mg/l)



REFRACTORY TKN TESTING APPARATUS



APPENDIX B

TKN Biodegradation Test Data

PROJECT : 317-03-35  
ANALYSIS BY: ENVIRONMENTAL LABORATORIES  
PHASE II. 66 PERCENT KRAFT WASTEWATER

SAMPLE:BIPCO

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.19		10.40	11.90	1.58
2	7.20	8.0			
5	7.63	8.0			
10	7.42	9.6	8.67	16.60	1.17
20	7.96	8.0	6.25	16.20	0.80
30					
40	7.76	12.0	6.82	23.40	0.55
50			8.54	28.60	0.23
60	8.04	8.5	7.23	25.90	0.32
70	7.93	7.2	6.22	24.30	0.36
80					
90	8.21	8.1	5.80		

SAMPLE B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.15		12.40	14.40	1.78
2	7.19	9.4			
5	7.56	9.2			
10	7.37	11.5		14.90	1.04
20	7.83	9.6	7.82	17.30	0.77
30					
40	7.74	12.0	6.94	24.70	0.68
50		6.7	5.41	27.20	0.23
60	8.38	11.5	5.88	28.20	0.29
70	7.98		6.11	24.60	0.35
80					
90	8.20	8.3	6.51		

AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.17		11.40	13.15	1.68
2	7.20	8.68			
5	7.60	8.60			
10	7.40	10.55	4.34	15.75	1.11
20	7.90	8.80	7.04	16.75	0.79
30					
40	7.75	12.00	6.88	24.05	0.62
50	0.00	3.35	6.98	27.90	0.23
60	8.21	10.00	6.56	27.05	0.31
70	7.96	3.60	6.17	24.45	0.36
80					
90	8.21	8.20	6.16		

SAMPLE:D0SHELL

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.39		1.63	29.40	0.77
2	7.43	10.0			
5	7.60	10.6			
10	7.53	8.6	1.14	28.60	1.80
20	8.11	7.4	0.64	27.90	0.93
30					
40	7.73	12.5	0.93	37.80	0.77
50			0.31	39.00	0.29
60	8.31	9.3	0.40	48.90	0.23
70	8.22	7.9	1.11	41.70	0.59
80					
90	8.21	8.2	0.34		

SAMPLE B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.28		2.14	24.30	1.88
2	7.27	11.3			
5	7.49	12.0			
10	7.30	14.5	1.20	27.50	1.67
20	8.26	9.2	2.06	27.90	0.82
30					
40	8.30	13.0	0.95	39.00	0.56
50			0.32	37.10	0.32
60	8.11	6.3	0.70	38.60	0.35
70	8.07	7.6	0.49	40.80	0.58
80					
90	8.14	8.2	0.10		

AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.34		1.89	26.85	1.33
2	7.35	10.65			
5	7.55	11.30			
10	7.42	11.55	1.17	28.05	1.74
20	8.19	8.28	1.35	27.90	0.88
30					
40	8.02	12.75	0.94	38.40	0.67
50			0.32	38.05	0.31
60	8.21	7.80	0.55	43.75	0.29
70	8.15	7.75	0.80	41.25	0.64
80					
90	8.18	8.20	0.22		

SAMPLE:COMBINED

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.18		9.57	21.20	2.12
2	7.19	9.4			
5	7.41	9.4			
10	7.25	10.8	8.46	18.70	3.90
20	7.77	7.6	8.61	17.50	2.17
30					
40	7.54	14.5	7.36	24.90	2.80
50			7.56	53.40	0.68
60	7.84	7.9	6.58	28.90	0.66
70	7.62	7.4	6.46	29.60	0.49
80					
90	8.01	7.9	5.58		

SAMPLE B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.20		8.93	18.80	1.04
2	7.19	9.0			
5	7.41	8.5			
10	7.20	10.6	9.74	17.80	3.92
20	7.55	8.1	11.49	18.20	2.14
30					
40	7.45	10.5	7.38	27.20	0.94
50			7.53	56.90	0.49
60	7.77	8.5	7.41	28.40	0.38
70	7.65	7.6	4.43	29.40	5.94
80					
90	6.79	8.1	5.93		

AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.19		9.25	20.00	1.58
2	7.19	9.20			
5	7.41	8.93			
10	7.23	10.70	9.10	18.25	3.91
20	7.66	7.85	10.05	17.85	2.16
30					
40	7.50	12.50	7.37	26.05	1.87
50			7.55	55.15	0.59
60	7.81	8.20	7.00	28.65	0.52
70	7.74	7.50	5.45	29.50	3.22
80					
90	7.40	8.00	5.76		

PROJECT : 317-03-35  
ANALYSES BY: IRONMONT LABORATORIES  
66 PERCENT SULFONATION WASTEWATER  
PHASE I.

SAMPLE: BIPCO

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
--------------	----	------------	-------------	-------------------	---------------

0	7.17	15.8	4.12	0.20	0.15
2	7.36	15.1	8.28		
5	7.12	15.1	10.10		
10	7.24	9.6		<0.02	0.93
20	7.41	7.3		<0.02	2.84
30	7.45	6.8			
40	7.28	10.8	6.46	0.94	0.83
50	7.24	12.7	4.29	3.41	0.20
60	7.30	13.0	3.51	4.48	0.42
70	8.36	8.5	3.98	4.31	0.22
80					
90	8.59	8.0	5.69	5.96	0.38
100			3.14	6.53	0.38
114	8.18	7.3	2.03	5.49	0.11
120					
130	8.17	10.1	4.51	6.76	0.09
140	8.26	11.8	4.12	4.47	
150	8.80	16.5	2.70	5.60	

SAMPLE B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
--------------	----	------------	-------------	-------------------	---------------

0	7.18	9.20	5.40	0.19	0.15
2	7.30	14.60			
5	7.37	8.50	1.44	<0.02	0.43
10	7.38	8.40	8.54	0.07	1.68
20	7.31	6.80			
30	7.35	6.80			
40	7.28	12.00	6.56	0.85	0.83
50	7.29	14.90	5.83	1.42	0.31
60	7.25	15.10	5.16	2.36	0.28
70	8.47	9.40		2.50	0.22
80					
90	8.79	9.00	7.16	3.51	0.91
100			5.08	5.99	0.17
114	8.19	7.70	7.78	9.19	<0.02
120					
130	8.15	10.50	3.65	7.00	0.13
140	8.34	12.80	3.83	4.47	
150	8.92	16.00	3.64	5.21	

AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
--------------	----	------------	-------------	-------------------	---------------

SAMPLE: DOSHELL

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
--------------	----	------------	-------------	-------------------	---------------

0	7.25	16.50	5.54	14.66	2.01
2	7.69	16.80			
5	7.50	16.80			
10	7.60	9.60	6.02	1.25	3.08
20	6.90	8.80	1.75	12.50	0.55
30	7.24	7.18			
40	7.40	12.70	1.09	14.40	0.25
50	7.33	14.40	1.12	20.95	0.29
60	7.30	14.50	<0.10	18.29	0.27
70	8.58	7.10	<0.10	22.40	0.23
80					
90	8.10	13.50	0.68	41.60	0.24
100			0.38	26.00	0.65
114	8.15	7.80	0.53	18.03	0.15
120					
130	7.66	10.30	0.52	24.00	0.08
140	8.22	12.00	0.81	15.20	
150	8.84	18.50	0.53	17.50	

SAMPLE B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
--------------	----	------------	-------------	-------------------	---------------

0	7.22	6.80	6.09	12.73	1.95
2	7.14	10.40			
5	6.82	10.40			
10	7.00	10.20	5.15	7.75	3.36
20	6.50	11.10	2.47	9.89	1.25
30	6.83	7.40			
40	7.08	12.00	1.20	14.40	0.17
50					
60					
70					
80					
90					
100					
114					
120					
130					
140					
150					

AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
--------------	----	------------	-------------	-------------------	---------------

CONTAMINATED

SAMPLE: COMBINED

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
--------------	----	------------	-------------	-------------------	---------------

0	7.26	15.00	6.30	2.18	0.81
2	7.42	13.40			
5	7.28	10.10	4.60	0.52	1.18
10	7.29	8.30	7.49	1.02	2.24
20	7.23	6.80			
30	7.24	11.00	5.49	0.20	0.36
40	7.33	11.90	4.84	4.29	
50	6.40	11.50	1.49	6.04	
60	7.40	7.30	5.04	6.22	
70	8.57				
80					
90	9.04	8.40	7.25	8.48	0.20
100			6.77	14.32	0.46
114	8.20	9.70	7.04	9.99	0.23
120					
130	8.12	10.90	4.11	12.83	0.28
140	8.35	12.50	4.91	8.65	
150	9.11	13.50	7.11	NA	


AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
--------------	----	------------	-------------	-------------------	---------------

## **Attachment 12**

Three schematics that address the proposed mill expansion at Bear Island are attached:

1. Overall water flow schematic reflecting the Bear Island mill expansion
2. Proposed upgrade of wastewater treatment facilities at Bear Island
3. Detail of proposed effluent oxygenation




**NOTE:** THE 1.0 MGD EFFLUENT FROM THE COUNTY WWTP CAN BE DISPOSED THROUGH ANY OF THE 3 ROUTES (OR COMBINATION THEREOF):

- A) TO DOSWELL ONE: 0.4 TO 1.0 MGD
- B) TO BIPCO: 0.2 TO 1.0 MGD
- C) TO THE RIVER THROUGH OUTFALLS 101-001: 0.0 TO 1.0 MGD  
IN CASE BOTH DOSWELL ONE AND BIPCO ARE NOT OPERATIONAL

## PROJECT WATER WITHDRAWAL

BEAR ISLAND PAPER COMPANY, L.P.  
ASHLAND, VIRGINIA

SCALE	NOT TO SCALE	APPROVED BY :	DRAWN BY: D.A.O.
DATE	MAY 1994	DESIGNED BY :	REVISED
PROJECT NUMBER	N100 01	ALIA/AF	DRAWING NO.



**TMP, PAPER MACHINE AND RECYCLING PLANT HIGH SOLIDS**

**LEGEND**

NEW IQUID INF

NEW SLUDGE LINE

---


**EXTINGUISHING LIQUID LINE**

EXISTING SLUDGE LINE

EXISTING FILTRATE LINE

 PROPOSED CONSTRUCTION[illegible]

PROPOSED EFFLUENT DIFFUSER



**FIGURE 2**  
**CONCEPTUAL LAYOUT OF OXYGENATION SYSTEM**  
 NOT TO SCALE

### **Attachment 13**

Attachment 13 includes Attachments 13A and 13B. **Attachment 13A** develops the control equation for a mill expansion consisting only of a second, TMP paper line. As the mill now uses recycled paper, and therefore, the expansion would also use recycled paper (approximately 40% recycled newsprint), the control equation was reevaluated in regard to the larger water use associated with recycled paper. **Attachment 13B** discusses those revisions. As it turns out, the control equation remained the same, but the dissolved oxygen requirements changed.



**Attachment 13A**

## SECTION 7.0

### 1987 MODEL SIMULATIONS

Computer simulations were performed using various input conditions to define the capacity of the river to assimilate wastewater in compliance with the SWCB anti-degradation policy. All model simulations used the calibrated model presented in Section 5.0.

#### 7.1 General Approach

The modeling for the proposed mill expansion uses the same approach as previous models of the North Anna, except that this model uses the actual stream data to define model parameters and input conditions (Section 3.0). The model was used to evaluate discharge at the wasteload allocation defined in the York River Plan (690 lbs CBOD<sub>5</sub> per day). The allowable in-stream UCBOD of the wastewater was then used in the mass balance equation (of the wastewater-river mix) to define effluent limits, which can be expressed in terms of an effluent limitation control equation.

The modeling analysis and controls for the proposed mill expansion have been based on the ultimate and 5-day carbonaceous BOD. The 16th edition of Standard Methods for the Analysis of Water and Wastewater (Greenberg et al, 1985) has introduced a procedure for carbonaceous analysis as the method to differentiate CBOD<sub>5</sub> and nitrogenous oxygen demand.

For this modeling analysis, the South Anna River DO is given as a function of the temperature of the North Anna River, as developed from probability distributions of DO data collected by Hanover County since 1982. For example, for days when the North Anna temperature was 25°C, the 90th percentile DO in the South Anna River was 6.46 mg/l (Figure 6-5). The

measured 90th percentile South Anna DO values are presented as a function of North Anna temperature in Figure 7-1. (The DO is related to the North Anna temperature, since the North Anna temperature is the critical temperature for the modeling.) A relationship function which may be used to estimate the 90th percentile DO from a given North Anna temperature is

$$SA\ DO\ 90 = 12.97 - 0.4058 (NA\ TEMP) + 0.005734 (NA\ TEMP)^2 \quad (7-1)$$

where

SA DO 90 = 90th percentile South Anna DO (mg/l),

NA TEMP = North Anna temperature (°C).

From this function, the South Anna DO input condition may be obtained for any North Anna temperature.

A summary of model parameters and input conditions which have been used in the model simulations is presented in Table 7-1.

The model was used to determine the allowable CBOD<sub>5</sub> loadings and the required initial in-stream DO concentrations which would meet the SWCB anti-degradation policy. It was anticipated that supplemental effluent oxygenation would be required under certain conditions to attain the necessary in-stream DO mix.

## 7.2 Oxygenation of Effluent

Applying Henry's Law to a water column in the presence of an oxygen-containing gas, the equilibrium DO in the water is directly proportional to the partial pressure of oxygen in the overlying gas. This may be expressed as




FIGURE 7-1. THE 90TH PERCENTILE SOUTH ANNA DISSOLVED OXYGEN VS. NORTH ANNA TEMPERATURE.

TABLE 7-1  
MODEL PARAMETERS AND INPUT CONDITIONS

Model Parameters: Reaction Rates (20°C)

<u>Stream Reach</u>	<u>K<sub>1</sub>-20°C</u>	<u>K<sub>2</sub>-20°C</u>	<u>K<sub>N</sub>-20°C</u>	<u>SOD<sub>20°C</sub></u>
1	0.11	1.30	0.30	5.0
2	0.11	1.00	0.20	2.0
3	0.11	1.90	0.20	1.8
4	0.10	2.00	0.20	2.5
5	0.10	2.50	0.20	1.5

Model Input Conditions

Justification

TKN Doswell	10 mg/l	Section 6.4; Appendix J
Flow Doswell	4.5 MGD	Anticipated flow after expansion
Water Withdrawal	10.5 MGD	Section 6.3
Headwater CBOD <sub>u</sub>	4.2 mg/l	Average (Aug. 19, Oct. 13 & 15)
Headwater TKN	0.4 mg/l	Average (Aug. 19, Oct. 13 & 15)
Little River CBOD <sub>u</sub>	2.5 mg/l	Average (Oct. 13, Oct. 15)
Little River TKN	0.5 mg/l	Average (Oct. 13, Oct. 15)
South Anna CBOD <sub>u</sub>	3.6 mg/l	Average (Aug. 19, Oct. 13 & 15)
South Anna TKN	0.50 mg/l	Average (Aug. 19, Oct. 13 & 15)
South Anna DO	$12.97 - 0.4058 (\text{NA TEMP}) + 0.005734 (\text{NA TEMP})^2$ where NA temp = North Anna temperature (°C). (This is equation 7-1.)	

$$C_s = \frac{1}{H_e'} P_o$$

where

$C_s$  = saturated DO (mg/l),

$H_e'$  = Henry's Constant (atm-l/mg),

$P_o$  = partial pressure of oxygen (atm).

For example, for water at 20°C in the presence of atmospheric air,  $H_e' = 0.023$  atm-l/mg,  $P_o = 0.209$  atm, and  $C_s = 9.09$  mg/l.

At a given temperature, the equilibrium DO increases with increasing partial pressure of the oxygen in the overlying gas. This may be accomplished by (1) increasing the percentage of oxygen in the overlying gas, and/or (2) increasing the gage pressure of the oxygen-containing gas. For example, replacing atmospheric air ( $P_o = 0.209$  atm) with pure oxygen ( $P_o = 1.0$  atm) would result in a saturated DO of  $C_s = 43.47$  mg/l at 20°C and standard atmospheric pressure.

A number of papers pertaining to post-aeration are presented in Appendix M.

### 7.3 Deaeration Under Supersaturated Conditions

According to Thomann and Mueller (1987), the transfer of a chemical across the air-water interface at atmospheric pressure may be derived from

$$V \frac{dC}{dt} = k_1 A \left( \frac{C_g}{H_e} - fC \right) \quad (7-2)$$

where

$V$  = volume of water column ( $L^3$ ),

$C$  = chemical concentration in the water column ( $M/L^3$ ),

- $t$  = time (T),  
 $k_l$  = overall exchange coefficient (L/T),  
 $A$  = surface area (L<sup>2</sup>),  
 $C_g$  = chemical concentration in the overlying air (M/L<sup>3</sup>),  
 $H_e$  = Henry's constant,  
 $f$  = fraction of total chemical which is dissolved.

The equation shows that flux of a chemical may be from the air to the water (if  $C_g/H_e$  is greater than  $fC$ ) or from the water to the air (if  $fC$  is greater than  $C_g/H_e$ ). Application of the two-film theory results in the overall transfer coefficient being given as

$$\frac{1}{k_l} = \frac{1}{K_l} + \frac{1}{K_g H_e} \quad (7-3)$$

where

- $K_l$  = liquid film coefficient (L/T),  
 $K_g$  = gas film coefficient (L/T).

This theory may be applied to the transfer of oxygen across an air-water interface. In such case,  $C_g/H_e$  is the saturated DO concentration and  $f = 1$ . Since  $H_e$  is relatively high, the oxygen transfer rate is controlled by the liquid phase. The reaeration coefficient is given by

$$K_2 = \frac{k_l A}{V} \quad (7-4)$$

where  $K_2$  is the atmospheric reaeration coefficient (T<sup>-1</sup>). Thus, for oxygen transfer, equation 7-2 may be written as

$$\frac{dC}{dt} = K_2 (C_s - C) \quad (7-5)$$

where  $C_s$  is the saturated DO concentration ( $M/L^3$ ). As with equation 7-2, the solution to equation 7-5 does not depend on the sign of the right-hand side. In terms of DO deficit, the solution is given by

$$D = D_0 \exp (-K_2 t) \quad (7-6)$$

where

$$D = C_s - C = \text{oxygen deficit (M/L}^3\text{)},$$

$$D_0 = \text{initial oxygen deficit (M/L}^3\text{)}$$

Since equation 7-2 is applicable to mass flow in either direction, it follows that equation 7-6 is appropriate for both reaeration and deaeration.

Similarly, equation 3-1 may be applied to supersaturated water, although there are some important assumptions involved. First, it must be assumed that the CBOD and NBOD decay processes are not affected by the existence of supersaturated conditions. Also, it must be assumed that SOD will not be affected by the additional oxygen. The use of equation 3-1 to evaluate supersaturated conditions is a common practice (Thomann, 1987).

A number of papers pertaining to post-aeration and deaeration under supersaturated conditions are presented in Appendix M.

#### 7.4 Model Simulations

The calibrated Streeter-Phelps model (as described in Section 5.0) indicates that a natural DO sag would exist in the North Anna River. Therefore, the upstream dissolved oxygen concentrations are adjusted to maintain the critical river DO at the sag location. The DO concentrations



required at NA-3.5 to maintain the critical background DO throughout the North Anna River are presented in Table 7-2 for each season. The modeling used to develop these required DO levels was based on critical temperatures, 7Q10 flow, and upstream CBOD and TKN values measured during the data acquisition phase of this study (Table 7-1).

#### 7.4.1 Model Simulations for Spring Season

For the months of April, May, and June, the critical temperature is 24°C and the critical background DO is 6.43 mg/l (Table 7-2). The model indicates that the minimum DO of 6.23 mg/l (6.43 mg/l minus 0.2 mg/l) can be maintained at 7Q10 flow in the North Anna River for an initial in-stream UCBOD<sub>5</sub> mix of 20.04 mg/l (4.5 MGD and 690 lbs CBOD<sub>5</sub> per day), if the initial in-stream DO mix is 11.70 mg/l (Figure 7-2). For an upstream DO of 7.90 mg/l (Table 7-2), this requires effluent oxygenation to a concentration of 27 mg/l, based on a mass balance at the discharge point.

The model indicates that with the maximum mill discharge (5.4 MGD and 1,350 lbs CBOD<sub>5</sub> per day), a North Anna flow of 92.73 cfs, and an upstream DO of 7.90 mg/l; the minimum DO of 6.23 mg/l can be maintained in the North Anna River without supplemental effluent oxygenation (Figure 7-3).

The model indicates that with the maximum combined discharge of the mill and the storage ponds (21.2 MGD and 5,300 lbs CBOD<sub>5</sub> per day), a North Anna flow of 218.73 cfs, and an upstream DO of 7.90

TABLE 7-2  
SUMMARY OF EFFLUENT OXYGENATION REQUIREMENTS AND ALLOWABLE DISCHARGES

Line		Spring	Summer	Fall	Winter
1	Critical Temperature (°C)	24	27	16	11
2	Critical DO (mg/l)	6.43	5.97	7.87	8.91
3	Initial DO to maintain critical DO throughout North Anna for no effluent at critical temperature and 7Q10 flow (mg/l) <sup>a</sup>	7.90	7.73	8.75	9.31
4	Minimum DO (mg/l) <sup>b</sup>	6.23	5.77	7.67	8.71
5	Initial in-stream DO required at 7Q10 flow and discharge of 690 lbs CBOD <sub>5</sub> per day to maintain minimum DO (Line 4) throughout the North Anna (mg/l) <sup>c</sup>	11.70	12.65	10.50	9.93
6	Effluent O <sub>2</sub> requirement at 7Q10 flow and discharge of 690 lbs per day, based on an upstream DO in the North Anna equal to Line 3 (mg/l) <sup>c</sup>	27	32	17	12
7	North Anna flow above which no O <sub>2</sub> is required (cfs): <sup>c</sup>				
7(a)	Discharge = 1,350 lbs CBOD <sub>5</sub> per day	92.73	97.73	86.73	79.73
7(b)	Discharge = 5,300 lbs CBOD <sub>5</sub> per day	218.73	222.73	195.73	175.73

<sup>a</sup> From modeling (Appendix I)

<sup>b</sup> Critical DO minus 0.2 mg/l.

<sup>c</sup> Sections 7.4.1 through 7.4.4.




FIGURE 7-2. DISSOLVED OXYGEN PROFILE FOR 7Q10 FLOW, TEMPERATURE OF 24°C INITIAL UCBOD OF 20.04 MG/L, AND INITIAL DISSOLVED OXYGEN OF 11.70 MG/L.




FIGURE 7-3. DISSOLVED OXYGEN PROFILE FOR FLOW OF 92.73 CFS, TEMPERATURE OF 24°C INITIAL UCBD OF 14.48 MG/L, AND INITIAL DISSOLVED OXYGEN OF 7.90 MG/L.

mg/l; the minimum DO of 6.23 mg/l can be maintained without supplemental effluent oxygenation (Figure 7-4).

#### 7.4.2 Model Simulation For Summer Season

For the months of July, August, and September, the critical temperature is 27°C and the critical background DO is 5.97 mg/l (Table 7-2). The model indicates that the minimum DO of 5.77 mg/l (5.97 mg/l minus 0.2 mg/l) can be maintained at 7Q10 flow in the North Anna River for an initial in-stream UCBOD mix of 20.04 mg/l (4.5 MGD and 690 lbs CBOD<sub>5</sub> per day), if the initial in-stream DO mix is 12.65 mg/l. For an upstream DO of 7.73 mg/l (Table 7-2), this requires effluent oxygenation to a concentration of 32 mg/l, based on a mass balance at the discharge point.

The model indicates that with the maximum mill discharge, a North Anna flow of 97.7 cfs, and an upstream DO of 7.73 mg/l; the minimum DO of 5.77 mg/l can be maintained in the North Anna River without supplemental effluent oxygenation.

The model indicates that with the maximum combined discharge of the mill and the storage ponds, a North Anna flow of 222.7 cfs, and an upstream DO of 7.73 mg/l; the minimum DO of 5.77 mg/l can be maintained without supplemental effluent oxygenation.

#### 7.4.3 Model Simulation For Fall Season

For the months of October, November, and December, the critical temperature is 16°C and the critical background DO is 7.87 mg/l (Table 7-2). The model indicates that the minimum DO of 7.67 mg/l (7.87 mg/l




FIGURE 7-4. DISSOLVED OXYGEN PROFILE FOR FLOW OF 218.7 CFS, TEMPERATURE OF 24°C INITIAL UCBOD OF 20.56 MG/L, AND INITIAL DISSOLVED OXYGEN OF 7.90 MG/L.

minus 0.2 mg/l) can be maintained at 7Q10 flow in the North Anna River for an initial in-stream UCBOD mix of 20.04 mg/l (4.5 MGD and 690 lbs CBOD<sub>5</sub> per day), if the initial in-stream DO mix is 10.50 mg/l. For an upstream DO of 8.75 mg/l (Table 7-2), this requires effluent oxygenation to a concentration of 17 mg/l, based on a mass balance at the discharge point.

The model indicates that with the maximum mill discharge, a North Anna flow of 86.7 cfs, and an upstream DO of 8.75 mg/l; the minimum DO of 7.67 mg/l can be maintained in the North Anna River without supplemental effluent oxygenation.

The model indicates that with the maximum combined discharge of the mill and the storage ponds, a North Anna flow of 195.7 cfs, and an upstream DO of 8.75 mg/l; the minimum DO of 7.67 mg/l can be maintained without supplemental effluent oxygenation.

#### 7.4.4 Model Simulation For Winter Season

For the months of January, February, and March, the critical temperature is 11°C and the critical background DO is 8.91 mg/l (Table 7-2). At the critical temperature of 11°C, it was assumed that the NBOD deoxygenation coefficient ( $K_N$ ) is equal to zero. The model indicates that the minimum DO of 8.71 mg/l (8.91 mg/l minus 0.2 mg/l) can be maintained at 7Q10 flow in the North Anna River for an initial in-stream UCBOD mix of 20.04 mg/l (4.5 MGD and 690 lbs CBOD<sub>5</sub> per day), if the initial in-stream DO mix is 9.93 mg/l. For an upstream DO of 9.31 mg/l (Table 7-2), this requires effluent oxygenation to a concentration of 12 mg/l, based on a mass balance at the discharge point.

The model indicates that with the maximum mill discharge, a North Anna flow of 79.7 cfs, and an upstream DO of 9.31 mg/l; the minimum DO of 8.71 mg/l can be maintained in the North Anna River without supplemental effluent oxygenation.

The model indicates that for the maximum combined discharge of the mill and the storage ponds, a North Anna flow of 175.7 cfs, and an upstream DO of 9.31 mg/l, the minimum DO of 8.71 mg/l can be maintained without supplemental effluent oxygenation.

#### 7.4.5 Summary

The allowable CBOD<sub>5</sub> discharges and effluent oxygenation requirements are summarized in Table 7-3.



TABLE 7-3  
SUMMARY OF EFFLUENT OXYGENATION REQUIREMENTS

	Spring	Summer	Fall	Winter
Critical Temperature (°C)	24	27	16	11
Effluent O <sub>2</sub> requirement (mg/l)	27	32	17	12
North Anna flow above which no O <sub>2</sub> is required (cfs):				
a. Normal mill discharge	92.73	97.73	86.73	79.73
b. Normal mill discharge plus release from hydrograph-controlled release pond	218.73	222.73	195.73	175.73

## SECTION 8.0

### PROPOSED NPDES CRITERIA

The proposed NPDES criteria are based on maintaining the SWCB anti-degradation policy in the North Anna River. The results of the modeling indicate that the addition of oxygen to the effluent using pure oxygen is required when the river flow is less than 100 cfs and there is no discharge from the hydrograph-controlled release lagoon, and up to river flow of 235 cfs when there is a discharge from the hydrograph-controlled release lagoon. A cascade type aeration system, similar to the existing unit, will be used in all other discharge cases.

#### 8.1 Allowable CBOD

The current permit has a control equation which regulates the allowable effluent discharge in proportion to the river flow. At higher stream flows, the allowable discharge is increased. The control equation has been updated based on the results of the modeling (Table 7-2).

The control equation is based on solving a mass balance around the UCBOD mix in the river. The results of the modeling indicated a critical UCBOD mix in the river of 20.04 mg/l. The control equation will define allowable discharge CBOD<sub>5</sub> in lbs/day. The basic mass balance is:

$$\begin{aligned} \text{Input Load (North Anna - Withdrawal + Little River + Effluent)} = \\ \text{UCBOD mix in river} \end{aligned} \quad (8-1)$$

$$\frac{(Q_U - Q_W)(4.2) + (1.77)(2.5) + (6.98)S_0(8.34)}{Q_U - Q_W + 1.77 + 6.98} = 20.04$$

where

$Q_U$  = stream flow in North Anna River before withdrawal (cfs),

$Q_w$  = withdrawal from North Anna (cfs),

$S_o$  = UCBOD of effluent (mg/l).

The allowable CBOD<sub>5</sub> discharge in lb/day can be defined as

$$\text{Allowable CBOD}_5 = \frac{S_o}{F} (Q_D) 8.34$$

where

$F = \text{CBOD}_u / \text{CBOD}_5$ ,

$Q_D$  = effluent discharge flow (MGD).

This mass balance is solved for allowable CBOD<sub>5</sub>, based on monitoring of the North Anna River flow at the Doswell discharge gage. Hanover County would initiate continuous monitoring of the flow in the river, which could be accomplished by telemetry from a gaging station located immediately upstream (approximately within 100 ft) of the effluent discharge (Figure 2.2). A typical cross section of this gaging location during low-flow conditions is presented in Figure 8-1. A gaging station at this location would allow measurement of the actual flow in the river.

The proposed effluent criteria would be defined by the following control equation:

$$\text{Allowable CBOD}_5 = 18.97 Q_s + 204.77 \quad (8-2)$$

where  $Q_s$  = stream flow in North Anna River after withdrawal.

The derivation of this equation from the mass balance is presented in Table 8-1. This control equation would be valid under all conditions. This equation would apply for all temperatures up to a maximum CBOD<sub>5</sub> level of 5,300 lb/day. A graphical interpretation of equation 8-2 is presented in Figure 8-2.




FIGURE 8-1. TYPICAL CROSS SECTION OF PROPOSED GAGING STATION

TABLE 8-1  
DERIVATION OF CONTROL EQUATION

The mass balance of (In-stream CBOD<sub>u</sub> Mix = Input Flow) is solved:

$$\text{In-stream UCBOD Mix} = \frac{(Q_S)(\text{CBOD}_{u1}) + (Q_{LR})(\text{CBOD}_{u2}) + Q_D(S_0)}{Q_S + Q_{LR} + Q_D} \quad (1)$$

where

Input Load = (North Anna - withdrawal + Little River + Effluent)/(Total Flow)

In-stream UCBOD Mix = 20.04 (from Section 7.4 model simulations)

$Q_S$  = stream flow in North Anna after withdrawal (cfs)

$\text{CBOD}_{u1}$  = ultimate CBOD in North Anna = 4.2 mg/l  
(from Table 7-1)

$\text{CBOD}_{u2}$  = ultimate CBOD in Little River = 2.5 mg/l  
(from Table 7-1)

$Q_{LR}$  = 7Q10 stream flow in the Little River (cfs)

$Q_D$  = effluent discharge flow = 6.98 cfs

$S_0$  = effluent ultimate CBOD

$F$  =  $\text{CBOD}_u/\text{CBOD}_5$  = 4.5 (from Table 4-5)

Conversions: mg/l x MGD x 8.34 = lbs/day

MGD x 1.547 = cfs

Solving:

$$20.04 = \frac{(Q_S)(4.2) + 1.77(2.5) + 6.98(S_0)}{Q_S + 1.77 + 6.98}$$

$$20.04 = \frac{4.2(Q_S) + 4.425 + 6.98(S_0)}{Q_S + 8.75}$$

(continued)

TABLE 8-1 (continued)  
DERIVATION OF CONTROL EQUATION

---

In terms of  $S_0$ :

$$S_0 = \frac{1}{6.98} (20.04(Q_s + 8.75) - 4.2 Q_s - 4.425) \quad (2)$$

The allowable 5-day CBOD, in terms of lb/day BOD<sub>5</sub>:

$$\begin{aligned} \text{Allowable BOD}_5 &= \frac{S_0}{F} (8.34) Q_D \\ &= \frac{S_0}{4.5} (8.34) \frac{6.98}{1.547} \end{aligned}$$

This can be substituted into equation 2 and results in:

$$\text{Allowable CBOD}_5 = \frac{8.34 (6.98)}{4.5 (6.98)(1.547)} (20.04 (Q_s + 8.75) - 4.2 Q_s - 4.425) \quad (3)$$

This equation can be further simplified to:

$$\text{Allowable CBOD}_5 = 18.97 Q_s + 204.77$$

These controls will comply with the SWCB anti-degradation policy and provide for the long-term water quality in the North Anna River.

---




FIGURE 8-2. PROPOSED EFFLUENT CRITERIA

## 8.2 Oxygen Addition

The result of the modeling indicate that oxygenation of the effluent using pure oxygen will be required under low flow conditions to maintain water quality in the North Anna River. The required effluent dissolved oxygen concentrations are presented in Table 8-2. This is based on the results of the modeling presented in Table 7-2. Table 8-3 presents the North Anna River flow conditions for the various seasons where oxygen addition will not be required.

The mill uses a hydrograph-controlled release pond to store effluent under low flow conditions. With this type of storage, there are three basic discharge scenarios which can occur. These are:

1. Under normal conditions, the mill will discharge an average flow of 4.5 MGD and a maximum flow of 5.4 MGD.
2. If there are low river flow conditions, a portion of the mill effluent flow will be diverted to the hydrograph-controlled release pond.
3. If the river flow increases, then the waste stored in the hydrograph-controlled release pond will be discharged based on equation 8-2.

When there is no waste stored in the hydrograph-controlled release lagoon, the maximum discharge will be 5.4 MGD at 30 mg/l CBOD<sub>5</sub> (1,350 pounds CBOD<sub>5</sub> per day); if there is waste stored in the hydrograph-controlled-release pond, a discharge of up to 5,300 pounds CBOD<sub>5</sub> per day can occur, based on the river flow (equation 8-2).



TABLE 8-2  
REQUIRED EFFLUENT DISSOLVED OXYGEN LEVEL

Season	Effluent Dissolved Oxygen <sup>a</sup> (mg/l)
Summer (July, August, September)	32
Fall (October, November, December)	17
Winter (January, February, March)	12
Spring (April, May, June)	27

<sup>a</sup> The effluent dissolved oxygen concentration is calculated through a mass balance where

DO inputs = DO mix in river

North Anna DO + Little River DO + effluent DO = DO mix in river

$$\frac{Q_s DO_A + 1.77 DO_B + 1.547 Q_D DO_D}{Q_s + 1.77 + 1.547 Q_D} = \text{DO mix in River}$$

where

DO mix in river - from Table 7-2 (mg/l)

Q<sub>s</sub> = stream flow in North Anna after withdrawal (cfs)

DO<sub>A</sub> = North Anna background DO, based on Table 7-2.

DO<sub>B</sub> = Little River DO (mg/l) = DO<sub>A</sub>

Q<sub>D</sub> = effluent discharge flow (MGD)

DO<sub>D</sub> = effluent DO (mg/l)

(continued)

TABLE 8-2 (continued)  
REQUIRED EFFLUENT DISSOLVED OXYGEN LEVEL

---

For example:

at 27°C       $DO_A = 7.73 \text{ mg/l}$  (from Table 7-2)

$DO_B = 7.73 \text{ mg/l}$

$Q_D = 4.5 \text{ MGD}$

$Q_S = 41.91 - 16.28$  (7Q10 conditions)

$= 25.63 \text{ cfs}$

$DO \text{ mix in river} = 12.65 \text{ mg/l}$  (from Table 7-2)

$$DO_D = \frac{(DO \text{ mix in river})(Q_S + 1.77 + 1.547 Q_D) - Q_S DO_A - 1.77 DO_B}{1.547 Q_D}$$

$$= \frac{((12.65)(25.63) + 1.77 + 6.96) - (25.63)(7.73) - (1.77)(7.73)}{(1.547)(4.5)}$$

$= 32 \text{ mg/l}$

---

TABLE 8-3  
SUMMARY OF RIVER FLOWS WHERE PURE OXYGEN  
ADDITION IS NOT REQUIRED

Season	Minimum River Flow (cfs)	
	Mill Waste Discharge (5.4 MGD Max.)	Mill Waste Plus Hydrograph- Controlled Pond Discharge (21.2 MGD Max.)
Summer (July, August, September)	100	231
Fall (October, November, December)	89	202
Winter (January, February, March)	81	181
Spring (April, May, June)	95	224

For simplicity, it is proposed to operate on a two-season basis, summer and winter, with the summer season being April through September, and the winter season being October through March. For the summer season, the effluent dissolved concentration will be 32 mg/l, and during the winter season it will be 17 mg/l. The oxygen addition will be required under all conditions when the river flow is less than 100 cfs. Oxygen addition will not be required at river flows over 100 cfs, unless there is the need to discharge from the hydrograph-controlled release pond. If there is any discharge from the hydrograph-controlled release pond, oxygen addition will be required up to a river flow of 235 cfs.

A summary of the proposed regulations is presented in Table 8-4. These controls will comply with the State Water Control Board anti-degradation policy and provide for the long-term water quality of the North Anna River.

TABLE 8-4  
PROPOSED DISCHARGE CRITERIA

Season	Effluent DO Using Pure Oxygen Post-Oxygenation (mg/l)	Minimum River Flow to Switch to Cascade Aeration (cfs)	
		Mill Waste Discharge (5.4 MGD Max.)	Mill Waste Plus Hydrograph- Controlled Pond Discharge
Summer (April - September)	32	100	235
Winter (October - March)	17	100	235

**Attachment 13B**

(Begin at Item 12.)

- Item 9: Figure 2 has been modified per your comments, with the future 1 MGD at the Doswell STP deleted, and with the oxygen supply valve position changed to the "closed" position, to reflect the correct operating scheme of the treatment system; and is included as Attachment 5.
- Item 10: Item 10 - The daily flow rate is utilized in the equation and the daily flow rate is used to set the oxygen addition. The sentence in question should read "A set of controls, based on daily discharge flow, allows supplemental effluent oxygenation to be suspended when the river flow exceeds 100 cfs, when the existing cascade aeration system can be used instead."
- Item 11: Item 11 - The note on Table 4 and Table 5 should be 6.5 mg/L and should read "NOTE: When switching to cascade aeration, effluent DO criteria is 6.5 mg/L". The narrative on Page 15 should read "At these minimum flow rates, the use of cascade aeration systems to oxygenate the effluent to a dissolved oxygen concentration of 6.5 mg/L is sufficient to maintain the required minimum DO conditions in the North Anna River."
- Item 12: You are correct in noting that the Effluent Oxygenation Controls discussed on Page 15, in Table 5, in Table 6, and on Page 19 include an additional 1.0 MGD from the Doswell STP, even though, as is also stated in the Engineering Report, that plant expansion will not occur during the lifetime of the VPDES permit. One reason is

that the design of the oxygenation system should take into account possible future expansion of Doswell, as it is anticipated that the oxygenation system will have an operating life longer than the five year term of this permit. The effect of operating under these conditions can best be observed by a comparison of the Effluent Oxygenation Controls with the Doswell expansion to the Effluent Oxygenation Controls without the Doswell expansion. Tables 5 and 6 from the Engineering Report, attached here for your convenience as Attachment 6, outlines the effluent oxygenation controls based on an average flow of 6.75 MGD and a maximum flow of 7.34 MGD (i.e., with the Doswell expansion). Tables 5a and 6a, also included in Attachment 6, outline the effluent oxygenation controls based on an average flow of 5.75 MGD and a maximum flow of 6.75 MGD (i.e., without the Doswell expansion).

4.211

Comparing the two operating schemes, the two operating schemes differ in the effluent oxygen required, and in the North Anna flow above which no supplemental oxygenation is required. The Doswell expansion causes the effluent oxygen requirement at 7Q10 flow to decrease slightly, from 29 mg/L to 27.19 mg/L in the summer and from 16 mg/L to 15.4 mg/L in the fall. Because the effluent DO concentrations in either case



is lower than the effluent DO concentration of 32 mg/L and 17 mg/L originally listed in the original VPDES permit application, the original permit DO concentrations of 32 mg/L and 17 mg/L were maintained originally to avoid additional permit modifications. The correct limits for the new permit should be 29 mg/L summer and 16 mg/L winter. The higher effluent DO concentrations result in a higher in-stream DO concentration, which in turn results in a higher minimum DO concentration in the river, thus ensuring compliance with the State Water Control Board's antidegradation policy requiring a DO sag of no more than 0.2 mg/L below the critical DO in the North Anna and Pamunkey Rivers.

The Doswell expansion causes the minimum N. Anna flow above which no oxygenation is required to increase, from 111 to 121 cfs in summer and from 97 to 105 cfs in the fall. If BIPCO chooses to operate under the oxygenation control scheme outlined in Table 5 while the Doswell expansion does not occur, then more oxygen will be added to the North Anna River than estimated to be necessary to maintain the minimum DO concentration throughout the North Anna, which again will help ensure compliance with the State Water Control Board's antidegradation policy. If desired by the SWCB, the

effluent oxygenation controls included in Table 5a can be utilized until the Doswell expansion occurs.

Several other items in this letter address the derivation of some of the parameters in Table 6. To avoid confusion, any questions in these areas will be answered only for the 6.75/7.34 MGD case presented in the Engineering Report. If the SWCB desires, comparable documentation for the 5.75/6.34 MGD case can be presented.

Item 13: The omitted footnote c in Table 6 states "River sections 7.4.1 through 7.4.4 ", which covers the sections of the North Anna that reflect the minimum DO conditions that Lines 5 and 7 in Table 6 are based on. Note that this footnote was included in the tables included in Attachment 6. These are the river sections included in Appendices B and C of the Engineering Report. The source of the information in Lines 5 and 7 is from the water quality model, via iterative runs to determine first the in-stream DO to maintain the minimum DO in the river (Line 5 of Table 6), then the North Anna flow above which no oxygenation is required (Line 7 of Table 6). Copies of the computer printouts showing the derivation of these values are attached as Attachment 7.

## **Attachment 14**

Effluent Limitation Development for the Bear Island Expansion

## Mixing Zone Predictions for

## Doswell WWTP expansion

Effluent Flow = 6.34 MGD  
Stream 7Q10 = 29 MGD  
Stream 30Q10 = 32 MGD  
Stream 1Q10 = 27 MGD  
Stream slope = 0.00038 ft/ft  
Stream width = 75 ft  
Bottom scale = 2  
Channel scale = 1

---

### Mixing Zone Predictions @ 7Q10

Depth = 1.5445 ft  
Length = 5004.32 ft  
Velocity = .4722 ft/sec  
Residence Time = .1226 days

#### Recommendation:

A complete mix assumption is appropriate for this situation and the entire 7Q10 may be used.

---

### Mixing Zone Predictions @ 30Q10

Depth = 1.6232 ft  
Length = 4794.79 ft  
Velocity = .4875 ft/sec  
Residence Time = .1138 days

#### Recommendation:

A complete mix assumption is appropriate for this situation and the entire 30Q10 may be used.

---

### Mixing Zone Predictions @ 1Q10

Depth = 1.4907 ft  
Length = 5159.18 ft  
Velocity = .4616 ft/sec  
Residence Time = 3.1045 hours

#### Recommendation:

A complete mix assumption is appropriate for this situation providing no more than 32.21% of the 1Q10 is used.

---

# FRESHWATER WATER QUALITY CRITERIA / WASTELOAD ALLOCATION ANALYSIS

Facility Name: Doswell WWTP expansion  
Receiving Stream: North Anna River

Permit No.: VA0029521

Version: OWP Guidance Memo 00-2011 (8/24/00)

Stream Information		Stream Flows		Mixing Information		Effluent Information	
Mean Hardness (as CaCO <sub>3</sub> ) =	19.4 mg/L	1Q10 (Annual) =	27 MGD	Annual - 1Q10 Mix =	32.21 %	Mean Hardness (as CaCO <sub>3</sub> ) =	562 mg/L
90% Temperature (Annual) =	26.2 deg C	7Q10 (Annual) =	29 MGD	- 7Q10 Mix =	100 %	90% Temp (Annual) =	30.6 deg C
90% Temperature (Wet season) =	deg C	30Q10 (Annual) =	32 MGD	- 30Q10 Mix =	100 %	90% Temp (Wet season) =	deg C
90% Maximum pH =	7.4 SU	1Q10 (Wet season) =	0 MGD	Wet Season - 1Q10 Mix =	%	90% Maximum pH =	7.9 SU
10% Maximum pH =	6.4 SU	30Q10 (Wet season) =	0 MGD	- 30Q10 Mix =	%	10% Maximum pH =	7.7 SU
Tier Designation (1 or 2) =	1	30Q9 =	33 MGD			Discharge Flow =	6.34 MGD
Public Water Supply (PWS) Y/N? =	n	Harmonic Mean =	81 MGD				
Trout Present Y/N? =	n	Annual Average =	MGD				
Early Life Stages Present Y/N? =	y						

Parameter (µg/l unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Acenaphthene	0	--	--	na	2.7E+03	--	--	na	1.7E+04	--	--	--	--	--	--	na
Acrolein	0	--	--	na	7.8E+02	--	--	na	4.8E+03	--	--	--	--	--	--	na
Acrylonitrile <sup>c</sup>	0	--	--	na	6.6E+00	--	--	na	9.1E+01	--	--	--	--	--	--	na
Aldrin <sup>c</sup>	0	3.0E+00	--	na	1.4E-03	7.1E+00	--	na	1.9E-02	--	--	--	--	7.1E+00	--	na
Ammonia-N (mg/l)	0	1.85E+01	2.04E+00	na	--	4.4E+01	1.2E+01	na	--	--	--	--	--	4.4E+01	1.2E+01	na
Ammonia-N (mg/l) (High Flow)	0	1.01E+01	2.80E+00	na	--	1.0E+01	2.8E+00	na	--	--	--	--	--	1.0E+01	2.8E+00	na
Anthracene	0	--	--	na	1.1E+05	--	--	na	6.8E+05	--	--	--	--	--	--	na
Antimony	0	--	--	na	4.3E+03	--	--	na	2.7E+04	--	--	--	--	--	--	na
Arsenic	0	3.4E+02	1.5E+02	na	--	8.1E+02	8.4E+02	na	--	--	--	--	--	8.1E+02	8.4E+02	na
Barium	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Benzene <sup>c</sup>	0	--	--	na	7.1E+02	--	--	na	9.8E+03	--	--	--	--	--	--	na
Benzidine <sup>c</sup>	0	--	--	na	5.4E-03	--	--	na	7.4E-02	--	--	--	--	--	--	na
Benzo (a) anthracene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Benzo (b) fluoranthene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Benzo (k) fluoranthene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Benzo (a) pyrene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Bis(2-Chloroethyl) Ether	0	--	--	na	1.4E+01	--	--	na	8.7E+01	--	--	--	--	--	--	na
Bis(2-Chloroisopropyl) Ether	0	--	--	na	1.7E+05	--	--	na	1.1E+06	--	--	--	--	--	--	na
Bromofom <sup>c</sup>	0	--	--	na	3.6E+03	--	--	na	5.0E+04	--	--	--	--	--	--	na
Butylbenzylphthalate	0	--	--	na	5.2E+03	--	--	na	3.2E+04	--	--	--	--	--	--	na
Cadmium	0	1.1E+01	1.3E+00	na	--	2.6E+01	7.1E+00	na	--	--	--	--	--	2.6E+01	7.1E+00	na
Carbon Tetrachloride <sup>c</sup>	0	--	--	na	4.4E+01	--	--	na	6.1E+02	--	--	--	--	--	--	na
Chlordane <sup>c</sup>	0	2.4E+00	4.3E-03	na	2.2E-02	5.7E+00	2.4E-02	na	3.0E-01	--	--	--	--	5.7E+00	2.4E-02	na
Chloride	0	8.6E+05	2.3E+05	na	--	2.0E+06	1.3E+06	na	--	--	--	--	--	2.0E+06	1.3E+06	na
TRC	0	1.9E+01	1.1E+01	na	--	4.5E+01	6.1E+01	na	--	--	--	--	--	4.5E+01	6.1E+01	na
Chlorobenzene	0	--	--	na	2.1E+04	--	--	na	1.3E+05	--	--	--	--	--	--	na

Parameter (ug/l unless noted)	Background Conc.	Water Quality Criteria			Wastewater Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Chlorobromomethane <sup>c</sup>	0	--	--	na	3.4E+02	--	--	na	4.7E+03	--	--	--	--	--	--	na
Chloroform <sup>c</sup>	0	--	--	na	2.9E+04	--	--	na	4.0E+05	--	--	--	--	--	--	na
2-Chloronaphthalene	0	--	--	na	4.3E+03	--	--	na	2.7E+04	--	--	--	--	--	--	na
2-Chlorophenol	0	--	--	na	4.0E+02	--	--	na	2.5E+03	--	--	--	--	--	--	na
Chlorpyrifos	0	8.3E-02	4.1E-02	na	--	2.0E-01	2.3E-01	na	--	--	--	--	--	2.0E-01	2.3E-01	na
Chromium III	0	1.2E+03	8.4E+01	na	--	2.8E+03	4.7E+02	na	--	--	--	--	--	2.8E+03	4.7E+02	na
Chromium VI	0	1.6E+01	1.1E+01	na	--	3.8E+01	6.1E+01	na	--	--	--	--	--	3.8E+01	6.1E+01	na
Chromium, Total	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Chrysene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Copper	0	3.2E+01	1.0E+01	na	--	7.5E+01	5.7E+01	na	--	--	--	--	--	7.5E+01	5.7E+01	na
Cyanide	0	2.2E+01	5.2E+00	na	2.2E+05	5.2E+01	2.9E+01	na	1.3E+06	--	--	--	--	5.2E+01	2.9E+01	na
DDD <sup>c</sup>	0	--	--	na	8.4E-03	--	--	na	1.2E-01	--	--	--	--	--	--	na
DDE <sup>c</sup>	0	--	--	na	5.9E-03	--	--	na	8.1E-02	--	--	--	--	--	--	na
DDT <sup>c</sup>	0	1.1E+00	1.0E-03	na	5.9E-03	2.6E+00	5.6E-03	na	8.1E-02	--	--	--	--	2.6E+00	5.6E-03	na
Demeton	0	--	1.0E-01	na	--	--	5.6E-01	na	--	--	--	--	--	--	5.6E-01	na
Dibenz(a,h)anthracene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Dibutyl phthalate	0	--	--	na	1.2E+04	--	--	na	7.4E+04	--	--	--	--	--	--	na
Dichloromethane	0	--	--	na	1.6E+04	--	--	na	2.2E+05	--	--	--	--	--	--	na
(Methylene Chloride) <sup>c</sup>	0	--	--	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
1,2-Dichlorobenzene	0	--	--	na	2.6E+03	--	--	na	1.6E+04	--	--	--	--	--	--	na
1,3-Dichlorobenzene	0	--	--	na	2.6E+03	--	--	na	1.6E+04	--	--	--	--	--	--	na
1,4-Dichlorobenzene	0	--	--	na	7.7E-01	--	--	na	1.1E+01	--	--	--	--	--	--	na
3,3-Dichlorobenzidine <sup>c</sup>	0	--	--	na	4.6E+02	--	--	na	6.3E+03	--	--	--	--	--	--	na
Dichlorobromomethane <sup>c</sup>	0	--	--	na	9.9E-02	--	--	na	1.4E+04	--	--	--	--	--	--	na
1,2-Dichloroethane <sup>c</sup>	0	--	--	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
1,1-Dichloroethylene	0	--	--	na	1.4E+05	--	--	na	8.7E+05	--	--	--	--	--	--	na
1,2-trans-dichloroethylene	0	--	--	na	7.9E-02	--	--	na	4.9E+03	--	--	--	--	--	--	na
2,4-Dichlorophenol	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
2,4-Dichlorophenoxy acetic acid (2,4-D)	0	--	--	na	3.9E+02	--	--	na	5.4E+03	--	--	--	--	--	--	na
1,2-Dichloropropane <sup>c</sup>	0	--	--	na	1.7E+03	--	--	na	1.1E+04	--	--	--	--	--	--	na
1,3-Dichloropropene	0	2.4E-01	5.6E-02	na	1.4E-03	5.7E-01	3.1E-01	na	1.9E-02	--	--	--	--	5.7E-01	3.1E-01	na
Dieldrin <sup>c</sup>	0	--	--	na	1.2E+05	--	--	na	7.4E+05	--	--	--	--	--	--	na
Diethyl Phthalate	0	--	--	na	5.9E+01	--	--	na	8.1E+02	--	--	--	--	--	--	na
Di-2-Ethylhexyl Phthalate <sup>c</sup>	0	--	--	na	2.3E+03	--	--	na	1.4E+04	--	--	--	--	--	--	na
2,4-Dimethylphenol	0	--	--	na	2.9E+06	--	--	na	1.8E+07	--	--	--	--	--	--	na
Dimethyl Phthalate	0	--	--	na	1.2E+04	--	--	na	7.4E+04	--	--	--	--	--	--	na
Di-n-Butyl Phthalate	0	--	--	na	1.4E+04	--	--	na	8.7E+04	--	--	--	--	--	--	na
2,4 Dinitrophenol	0	--	--	na	7.6E+02	--	--	na	4.7E+03	--	--	--	--	--	--	na
2-Methyl-4,6-Dinitrophenol	0	--	--	na	9.1E+01	--	--	na	1.3E+03	--	--	--	--	--	--	na
2,4-Dinitrotoluene <sup>c</sup>	0	--	--	na	1.2E-06	--	--	na	na	--	--	--	--	--	--	na
Dioxin (2,3,7,8- tetrachlorodibenzo-p-dioxin) (ppb)	0	--	--	na	5.4E+00	--	--	na	7.4E+01	--	--	--	--	--	--	na
1,2-Diphenylhydrazine <sup>c</sup>	0	2.2E-01	5.6E-02	na	2.4E+02	5.2E-01	3.1E-01	na	1.5E+03	--	--	--	--	5.2E-01	3.1E-01	na
Alpha-Endosulfan	0	2.2E-01	5.6E-02	na	2.4E+02	5.2E-01	3.1E-01	na	1.5E+03	--	--	--	--	5.2E-01	3.1E-01	na
Beta-Endosulfan	0	--	--	na	2.4E+02	--	--	na	1.5E+03	--	--	--	--	--	--	na
Endosulfan Sulfate	0	8.6E-02	3.6E-02	na	8.1E-01	2.0E-01	2.0E-01	na	5.0E+00	--	--	--	--	2.0E-01	2.0E-01	na
Endrin	0	--	--	na	8.1E-01	--	--	na	5.0E+00	--	--	--	--	--	--	na
Endrin Aldehyde	0	--	--	na	8.1E-01	--	--	na	5.0E+00	--	--	--	--	--	--	na

Parameter (ug/l unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Ethylbenzene	0	--	--	na	2.9E+04	--	--	na	1.8E+05	--	--	--	--	--	--	na
Fluoranthene	0	--	--	na	3.7E+02	--	--	na	2.3E+03	--	--	--	--	--	--	na
Fluorene	0	--	--	na	1.4E+04	--	--	na	8.7E+04	--	--	--	--	--	--	na
Foaming Agents	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Guthion	0	--	1.0E-02	na	--	--	5.6E-02	na	--	--	--	--	--	--	5.6E-02	na
Heptachlor <sup>c</sup>	0	5.2E-01	3.8E-03	na	2.1E-03	1.2E+00	2.1E-02	na	2.9E-02	--	--	--	--	1.2E+00	2.1E-02	na
Heptachlor Epoxide <sup>c</sup>	0	5.2E-01	3.8E-03	na	1.1E-03	1.2E+00	2.1E-02	na	1.5E-02	--	--	--	--	1.2E+00	2.1E-02	na
Hexachlorobenzene <sup>c</sup>	0	--	--	na	7.7E-03	--	--	na	1.1E-01	--	--	--	--	--	--	na
Hexachlorobutadiene <sup>c</sup>	0	--	--	na	5.0E+02	--	--	na	6.8E+03	--	--	--	--	--	--	na
Hexachlorocyclohexane	0	--	--	na	1.3E-01	--	--	na	1.8E+00	--	--	--	--	--	--	na
Alpha-BHC <sup>c</sup>	0	--	--	na	4.6E-01	--	--	na	6.3E+00	--	--	--	--	--	--	na
Beta-BHC <sup>c</sup>	0	--	--	na	6.3E-01	2.3E+00	--	na	8.7E+00	--	--	--	--	2.3E+00	--	na
Gamma-BHC <sup>c</sup> (Lindane)	0	9.5E-01	na	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
Hexachlorocyclopentadiene	0	--	--	na	8.9E+01	--	--	na	1.2E+03	--	--	--	--	--	--	na
Hexachloroethane <sup>c</sup>	0	--	2.0E+00	na	4.9E-01	--	1.1E+01	na	6.8E+00	--	--	--	--	--	1.1E+01	na
Hydrogen Sulfide	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Indeno (1,2,3-cd) pyrene <sup>c</sup>	0	--	--	na	2.6E+04	--	--	na	3.6E+05	--	--	--	--	--	--	na
Iron	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Isophorone <sup>c</sup>	0	--	0.0E+00	na	--	--	0.0E+00	na	--	--	--	--	--	--	0.0E+00	na
Kepone	0	3.8E+02	1.6E+01	na	--	9.0E+02	9.2E+01	na	--	--	--	--	--	9.0E+02	9.2E+01	na
Lead	0	--	1.0E-01	na	--	--	5.6E-01	na	--	--	--	--	--	--	5.6E-01	na
Malathion	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Manganese	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Mercury	0	1.4E+00	7.7E-01	na	5.1E-02	3.3E+00	4.3E+00	na	3.2E-01	--	--	--	--	3.3E+00	4.3E+00	na
Methyl Bromide	0	--	--	na	4.0E+03	--	--	na	2.5E+04	--	--	--	--	--	--	na
Methoxychlor	0	--	3.0E-02	na	--	--	1.7E-01	na	--	--	--	--	--	--	1.7E-01	na
Mirex	0	--	0.0E+00	na	--	--	0.0E+00	na	--	--	--	--	--	--	0.0E+00	na
Monochlorobenzene	0	--	--	na	2.1E+04	--	--	na	1.3E+05	--	--	--	--	--	--	na
Nickel	0	3.9E+02	2.3E+01	na	4.6E+03	9.3E+02	1.3E+02	na	2.9E+04	--	--	--	--	9.3E+02	1.3E+02	na
Nitrate (as N)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Nitrobenzene	0	--	--	na	1.9E+03	--	--	na	1.2E+04	--	--	--	--	--	--	na
N-Nitrosodimethylamine <sup>c</sup>	0	--	--	na	8.1E+01	--	--	na	1.1E+03	--	--	--	--	--	--	na
N-Nitrosodiphenylamine <sup>c</sup>	0	--	--	na	1.6E+02	--	--	na	2.2E+03	--	--	--	--	--	--	na
N-Nitrosodi-n-propylamine <sup>c</sup>	0	--	--	na	1.4E+01	--	--	na	1.9E+02	--	--	--	--	--	--	na
Parathion	0	6.5E-02	1.3E-02	na	--	1.5E-01	7.2E-02	na	--	--	--	--	--	1.5E-01	7.2E-02	na
PCB-1016	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1221	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1232	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1242	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1248	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1254	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1260	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB Total <sup>c</sup>	0	--	--	na	1.7E+03	--	--	na	2.3E+02	--	--	--	--	--	--	na

Parameter (ug/l unless noted) <sup>c</sup>	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH
Pentachlorophenol <sup>c</sup>	0	6.0E+00	4.0E+00	na	8.2E+01	1.4E+01	2.2E+01	na	1.1E+03	--	--	--	1.4E+01	2.2E+01	na	1.1E+03
Phenol	0	--	--	na	4.6E+06	--	--	na	2.9E+07	--	--	--	--	--	na	2.9E+07
Pyrene	0	--	--	na	1.1E+04	--	--	na	6.8E+04	--	--	--	--	--	na	6.8E+04
Radionuclides (pCi/l except Beta/Photon)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	na	--
Gross Alpha Activity	0	--	--	na	1.5E+01	--	--	na	9.3E+01	--	--	--	--	--	na	9.3E+01
Beta and Photon Activity (mrem/yr)	0	--	--	na	4.0E+00	--	--	na	2.5E+01	--	--	--	--	--	na	2.5E+01
Strontium-90	0	--	--	na	8.0E+00	--	--	na	5.0E+01	--	--	--	--	--	na	5.0E+01
Tridium	0	--	--	na	2.0E+04	--	--	na	1.2E+05	--	--	--	--	--	na	1.2E+05
Selenium	0	2.0E+01	5.0E+00	na	1.1E+04	4.7E+01	2.8E+01	na	6.8E+04	--	--	--	4.7E+01	2.8E+01	na	6.8E+04
Silver	0	1.6E+01	--	na	--	3.9E+01	--	na	--	--	--	--	3.9E+01	--	na	--
Sulfate	0	--	--	na	--	--	--	na	--	--	--	--	--	--	na	--
1,1,2,2-Tetrachloroethane <sup>c</sup>	0	--	--	na	1.1E+02	--	--	na	1.5E+03	--	--	--	--	--	na	1.5E+03
Tetrachloroethylene <sup>c</sup>	0	--	--	na	8.9E+01	--	--	na	1.2E+03	--	--	--	--	--	na	1.2E+03
Thallium	0	--	--	na	6.3E+00	--	--	na	3.9E+01	--	--	--	--	--	na	3.9E+01
Toluene	0	--	--	na	2.0E+05	--	--	na	1.2E+06	--	--	--	--	--	na	1.2E+06
Total dissolved solids	0	--	--	na	--	--	--	na	--	--	--	--	--	--	na	--
Toxaphene <sup>c</sup>	0	7.3E-01	2.0E-04	na	7.5E-03	1.7E+00	1.1E-03	na	1.0E-01	--	--	--	1.7E+00	1.1E-03	na	1.0E-01
Tributyltin	0	4.6E-01	6.3E-02	na	--	1.1E+00	3.5E-01	na	--	--	--	--	1.1E+00	3.5E-01	na	--
1,2,4-Trichlorobenzene	0	--	--	na	9.4E+02	--	--	na	5.8E+03	--	--	--	--	--	na	5.8E+03
1,1,2-Trichloroethane <sup>c</sup>	0	--	--	na	4.2E+02	--	--	na	5.8E+03	--	--	--	--	--	na	5.8E+03
Trichloroethylene <sup>c</sup>	0	--	--	na	8.1E+02	--	--	na	1.1E+04	--	--	--	--	--	na	1.1E+04
2,4,6-Trichlorophenol <sup>c</sup>	0	--	--	na	6.5E+01	--	--	na	9.0E+02	--	--	--	--	--	na	9.0E+02
2-(2,4,5-Trichlorophenoxy) propionic acid (Silvex)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	na	--
Vinyl Chloride <sup>c</sup>	0	--	--	na	6.1E+01	--	--	na	8.4E+02	--	--	--	--	--	na	8.4E+02
Zinc	0	2.5E+02	1.3E+02	na	6.9E+04	6.0E+02	7.5E+02	na	4.3E+05	--	--	--	6.0E+02	7.5E+02	na	4.3E+05

Notes:

- All concentrations expressed as micrograms/liter (ug/l) unless noted otherwise
- Discharge flow is highest monthly average or Form 2C maximum for Industries and design flow for Municipals
- Metals measured as Dissolved, unless specified otherwise
- "C" indicates a carcinogenic parameter
- Regular WLAs are mass balances (minus background concentration) using the % of stream flow entered above under Mixing Information.  
Antidegradation WLAs are based upon a complete mix.  
Antidegrad. Baseline = (0.25(WQC - background conc.) + background conc.) for acute and chronic  
= (0.1(WQC - background conc.) + background conc.) for human health
- WLAs established at the following stream flows: 1Q10 for Acute, 30Q10 for Chronic Ammonia, 7Q10 for Other Chronic, 30Q5 for Non-carcinogens, Harmonic Mean for Carcinogens, and Annual Average for Dioxin. Mixing ratios may be substituted for stream flows where appropriate.

Metal	Target Value (SSTV)
Antimony	2.7E+04
Arsenic	3.2E+02
Barium	na
Cadmium	4.3E+00
Chromium III	2.8E+02
Chromium VI	1.5E+01
Copper	3.0E+01
Iron	na
Lead	5.5E+01
Manganese	na
Mercury	3.2E-01
Nickel	7.7E+01
Selenium	1.7E+01
Silver	1.6E+01
Zinc	2.4E+02

Note: do not use QL's lower than the minimum QL's provided in agency guidance



Facility = Doswell WWTP expansion  
Chemical = Ammonia  
Chronic averaging period = 30  
WLAa = 44  
WLAc = 12  
Q.L. = .2  
# samples/mo. = 30  
# samples/wk. = 8

Summary of Statistics:

# observations = 1  
Expected Value = 6  
Variance = 12.96  
C.V. = 0.6  
97th percentile daily values = 14.6005  
97th percentile 4 day average = 9.98274  
97th percentile 30 day average = 7.23631  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

6

Guidance Memorandum No. 00-2011 directs that an ammonia effluent concentration of 9 mg/L be used to evaluate the need for an ammonia limitation for a municipal discharge. Although this discharge consists predominantly of industrial wastewater, it is reasonable to check to see if the cited guidance would result in a limitation. In this case, the permit already limits TKN to 10 mg/L. Ammonia typically makes up 40% to 60% of the TKN in a municipal effluent. Ammonia makes up 46% of the TKN in the Bear Island wastewater (see "Outfall 001 – Supplement to Table I"). Using 60% as a worse case scenario, the ammonia concentration could be as high 6.0 mg/L, which is the concentration used in the above analysis ( $10 \times 0.6 = 6$ ). The above result that "no limit is required" establishes that the TKN limitation is also protective of the ammonia water quality standard. Note that the number of samples per month used in the above analysis matches the frequency of BOD monitoring.

Facility = Doswell WWTP expansion

Chemical = Chloride

Chronic averaging period = 4

WLAa = 2000000

WLAc = 1300000

Q.L. = 1

# samples/mo. = 1

# samples/wk. = 1

#### Summary of Statistics:

# observations = 1

Expected Value = 29000

Variance = 3027600

C.V. = 0.6

97th percentile daily values = 70569.1

97th percentile 4 day average = 48249.9

97th percentile 30 day average = 34975.5

# < Q.L. = 0

Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

29000

Facility = Doswell WWTP expansion  
Chemical = Total Residual Chlorine  
Chronic averaging period = 4  
WLAa = 45  
WLAc = 61

Q.L. = 0.1  
# samples/mo. = 1  
# samples/wk. = 1

#### Summary of Statistics:

# observations = 3  
Expected Value = 360  
Variance = 46656  
C.V. = 0.6  
97th percentile daily values = 876.030  
97th percentile 4 day average = 598.964  
97th percentile 30 day average = 434.179  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

#### **A limit is needed based on Acute Toxicity**

Maximum Daily Limit = 45  
Average Weekly Limit = 45  
Average Monthly Limit = 45

The data are:

190  
410  
480

Chlorine is not used for disinfection at the Doswell treatment plant and chlorine is not used in the Bear Island process. The above concentrations were determined in conjunction with the failed *Ceriodaphnia dubia* chronic bioassay test in March 2007 (see Attachment 8). These TRC concentrations are believed to be false positives due to possible interference by manganese or alkalinity. Because chlorine is not used at either site, limitations are not included in the draft permit. (It is not appropriate to "force" chlorine limitations with an input of value of 20,000 µg/L per Guidance Memorandum No. 00-2011 because chlorine is not added to the system at any point.)

Facility = Doswell WWTP expansion  
Chemical = Dissolved Copper  
Chronic averaging period = 4  
WLAa = 75  
WLAc = 57  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 6  
Variance = 12.96  
C.V. = 0.6  
97th percentile daily values = 14.6005  
97th percentile 4 day average = 9.98274  
97th percentile 30 day average = 7.23631  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

6

The dissolved copper data reported with the permit renewal application were 6 µg/L, <5 µg/L, and <5 µg/L (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the copper data.

Facility = Doswell WWTP expansion  
Chemical = Cyanide  
Chronic averaging period = 4  
WLAa = 52  
WLAc = 29  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 2  
Expected Value = 10.5  
Variance = 39.69  
C.V. = 0.6  
97th percentile daily values = 25.5508  
97th percentile 4 day average = 17.4697  
97th percentile 30 day average = 12.6635  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

11  
10

The cyanide data reported with the permit renewal application were 11 µg/L, 10 µg/L, and <10 µg/L (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the cyanide data. Note in Attachment 6A that a cyanide study was conducted starting in March 2004 and ending in October 2005. The above data are consistent with the data collected during that study period. Although the data from the cyanide study are more than three years old, they are still representative and could have been included in the above analysis. The above analysis using only two data points is a more extreme analysis however, which indicates that limitations are not needed.

Facility = Doswell WWTP expansion  
Chemical = Dissolved Lead  
Chronic averaging period = 4  
WLAa = 900  
WLAc = 92  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 30  
Variance = 324  
C.V. = 0.6  
97th percentile daily values = 73.0025  
97th percentile 4 day average = 49.9137  
97th percentile 30 day average = 36.1815  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

30

The dissolved lead data reported with the permit renewal application were (all in µg/L): <20, <20, 30, <20, <20, <20, <20, <20, and <20 (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the lead data.

Facility = Doswell WWTP expansion

Chemical = Dissolved Zinc

Chronic averaging period = 4

WLAa = 600

WLAc = 750

Q.L. = 1

# samples/mo. = 1

# samples/wk. = 1

#### Summary of Statistics:

# observations = 11

Expected Value = 133.937

Variance = 1605.77

C.V. = 0.299185

97th percentile daily values = 222.573

97th percentile 4 day average = 175.236

97th percentile 30 day average = 147.698

# < Q.L. = 0

Model used = lognormal

**No Limit is required for this material**

The data are:

108

101

134

218

173

98

113

110

104

109

204